The Home User's Guide to Commodore Computing

RUN

U.S.A. $2.95
CANADA $3.50
A CWC/I Publication
April 1985

UNIQUE CREATIONS FOR YOUR COMMODORE

Computerized Sundial
Biorhythms
Celestial Swami

The Pros and Cons Of SIMONS' BASIC

LET IT SCROLL On Your C-64 and VIC-20

A Beginner's Guide to Assembly Language

74470 12069 04

Circle 19 on Reader Service card.

COMMODOR

RITEMAN

DISTRIBUTORS:

Hamburg Brothers/NE 412-227-6239
Johnson Drug Company/SE 813-872-6631
Southern Electronics Distributors/SE 404-491-8962
Stokes Brothers/Utah 801-566-4117
Frisco Electronics/TX 512-657-7741
Ryan Distributing/Rocky Mt. 801-972-4721
First Source/SW 602-263-1950
Southern Micro Distributors/TX 214-258-6636

Compare these specs before you buy...

RITEMAN C+ vs. COMMODORE PRINTERS

FEATURES	RITEMAN C+	ACTUAL PRINT	COMMODORE PRINTERS				
			MPS 801	MPS 802	MPS 803	VIC1525	VIC1526
PRINT SPEED (CPS)	105		50	60	60	50	60
BIDIRECTIONAL PRINT	YES		NO	YES	YES	NO	YES
(COLUMN WIDTH)							
40 CHARACTERS PER LINE	YES	40 CPL	YES	YES	YES	YES	YES
80 CHARACTERS PER LINE	YES	80 CPL	YES	YES	YES	YES	YES
66 CHARACTERS PER LINE	YES	66 CPL					
132 CHARACTERS PER LINE	YES	132 CPL					
(PAPER HANDLING)							
FRONT LOADING FOR EASY PAPER SETTINGS	YES						
BUILT-IN PRINTER STAND	YES						
PRINT ON POST CARDS	YES						
(WARRANTY)							
ONE-YEAR WARRANTY	YES						
(SOFTWARE COMMANDS)							
DOUBLE STRIKE	YES	DOUBLE STRIKE					
EMPHASIZED	YES	EMPHASIZED					
COMPRESSED	YES	COMPRESSED					
UNDERLINE	YES	UNDERLINE					
SUPER/SUBSCRIPTS	YES	SUPER SUB SCRIPTS					
ITALICS	YES	*ITALICS*					
DOUBLE DENSITY BIT IMAGE	YES	C64					
(CHARACTERS)							
9X9 FONT	YES						
TRUE DISCENDERS	YES	abcgjpqyabc					
ITALICS	YES	*ITALICS*					
COMMODORE GRAPHICS	YES	♠♥♦♣ ◜◝▒◘●					
(OTHER FEATURES)							
SINGLE DENSITY BIT IMAGE	YES	C64	YES	NO	YES	YES	NO
EXPANDED	YES	EXPANDED	YES	YES	YES	YES	YES
REVERSE	YES	REVERSED	YES	YES	YES	YES	YES

NO

RITEMAN R64



RITEMAN LQ



■ LQ is available at Best Products. BEST®

Features

RITEMAN R64

Same as above except:

- 120 cps
- 2 ports: Centronics Parallel & Commodore*
- Portable
- Standard top loading

RITEMAN LQ

- Letter Quality Print
- Portable — Only 6½ lbs.
- Low price
- Centronics Parallel

*Commodore is a registered trademark of Commodore Business Machine, Inc.
**Epson is a registered trademark of Epson America Corp.

RITEMAN

INFORUNNER CORPORATION Airport Business Center 431 N. Oak St. Inglewood, CA 90302
(213) 672-4848 (In Calif) (800) 824-3044 (Outside Calif)

Fleet System 2.™
Word processing that *spells* V-A-L-U-E.

Complete word processing with built-in 70,000 word spell checking - Only $79.95

Up till now, you'd have to spend a minimum of about $70 to get a good word processor for your Commodore 64™. And if you added a small, *separate* spell checking program, you'd be out well over $100!

Now there's Fleet System 2! It's two powerful programs in one, and it's perfect for book reports, term papers or full office use.

Fleet System 2 combines the EASIEST and most POWERFUL word processor available with a lightning-fast 70,000 word spelling dictionary — all in one refreshingly EASY TO USE integrated system. Finally, spell checking is now available at your fingertips.

You can even add over 15,000 "custom" words to the built-in 70,000 word dictionary. And at a suggested retail price of $79.95, Fleet System 2 really spells V-A-L-U-E, and 70,000 other words too!

Fleet System 2 helps people of all ages to learn to *spell correctly* and *write better* too. It's the ONLY full featured word processor that provides you with helpful writing and vocabulary feedback such as: the total number of words in your document, the number of times each word appears, and total number of "unique" words, just to name a few.

Fleet System 2 has every important feature that will help you make child's play out of the most heavy duty typing tasks. There's Built-in 80 Column Display — so what you see is what you get, Horizontal Scrolling During Typing, Easy Correction and Movement of Text, Page Numbering, Centering, Indenting, Headers and Footers, Math Functions, Search and Replace, Mail Merge, BUILT IN 70,000 word SPELL CHECKING and much, much more!

Ask for Fleet System 2. Exceptionally Easy. Packed with Power. Perfectly Priced.

PSI Professional Software, Inc., 51 Fremont Street, Needham, MA 02194 (617) 444-5224 Telex: 951579

Fleet System 2™ is a trademark of Professional Software, Inc. — Fleet System 2™ was designed and written by Visiontronics, Ltd. — Commodore 64™ is a trademark of Commodore Electronics Ltd. — Some printers may not support certain Fleet System 2 functions and/or require an interface. Please check with your dealer. — Dealer and Distributor inquiries are invited.

ALL AIRLINES DEPART FROM THIS TERMINAL.

Presenting Travelshopper℠ ...new from CompuServe and TWA.

Now you can save time and money by getting information and reservations on virtually any flight on any airline—worldwide—from one source. It's TWA's new Travelshopper, available now through CompuServe's Information Service.

With Travelshopper, you can scan flight availabilities, discover airfare bargains and order tickets...on your own personal computer...at home or in the office.

You also receive automatic membership in TWA's Frequent Flight Bonus℠ program. And you can build bonus points by staying at Marriott and Hilton hotels and by using Hertz Rent-A-Car.

Besides Travelshopper, CompuServe offers an ever-growing list of other travel-oriented on-line services.

The Official Airline Guide Electronic Edition lists direct and connecting flight schedules for over 700 airlines worldwide plus over 500,000 North American fares.

Firstworld Travel offers worldwide travel advice and service.

Discover Orlando provides complete prices, hours and features on all of Central Florida's attractions and accommodations.

West Coast Travel offers travel information for the western states.

Pan Am's Travel Guide contains up-to-date information on immigration and health requirements for most foreign countries.

And TravelVision® provides complete automotive information, including road maps and an expert, personalized routing service.

Let your travel plans really take off. Use Travelshopper and lots, lots more from CompuServe.

To buy a CompuServe Starter Kit, see your nearest computer dealer. To receive our informative brochure, or to order direct, call or write:

CompuServe

P.O. Box 20212, 5000 Arlington Centre Blvd., Columbus, Ohio 43220

1-800-848-8199

In Ohio, Call 1-614-457-0802

Travelshopper and Frequent Flight Bonus are Service marks of TWA

Circle 64 on Reader Service card.

An H&R Block Company

April 1985 RUN Vol. 2, No. 4

FEATURES

24 COMMODORE SUNDIAL
Learn how to make a sundial with the aid of your Commodore computer.
By Howard Witt

30 CHARTING YOUR FUTURE
Biorhythms can tell you a lot about your state of being. This program lets you chart them.
By Allen E. Wheeler

35 CELESTIAL SWAMI
Did you know that your C-64 can double as a fortune teller?
By Jim Bernard

42 THE PLUS/4's FILE MANAGER
A review of the Plus/4's built-in database program.
By Margaret Morabito

46 VIDEO JUKEBOX
Relax with this program of kaleidoscopic color and sound patterns for your C-64.
By Joe W. Rocke

50 PICKING THE RIGHT SOUNDS
Tune your guitar with this program.
By Michael and Jeffrey Goller

54 TEACHER'S PET
This educational program generates worksheets to help students practice basic arithmetic skills.
By Frank Colosimo

58 EASY ASSEMBLY
Here's your chance to begin learning assembly language; the first installment of a new series.
By William B. Sanders

86 LET IT SCROLL!
Here's an easy-to-use subroutine that lets you scroll messages across your screen.
By Bruce Jaeger

87 PROGRAMMING BRIEFS
A list of disk commands for easy reference.
By Mary D. Brigito

88 THE NUMBER PUZZLE
It looks easy, but don't be so easily fooled.
By Zoltan Szepesi

93 A FIRST LESSON IN PROGRAMMING FOR KIDS
The Basic Print and Goto statements can make a child's introduction to programming easy and enjoyable.
By Amy and James Blodgett

94 SIMON'S BASIC
A hard look at a version of Basic that adds 100 commands to your C-64 system.
By Robert W. Baker

100 MAKING BOXES
Add a little punch to your programs—this short subroutine lets you box in your screen messages and menus with ease.
By Richard Lovett

102 SOUND SAMPLER
Seventeen amusing, captivating and out-of-this-world sounds that you can add to your own programs.
By Bruce Bartlett

110 GRAPH MAKER 64
Create, save and print colorful vertical bar graphs for use in your programs.
By Doug Smoak

116 A USER'S CASTLE
A blueprint for building your own convenient computer sanctuary.
By Jim Stephens

120 GATEWAY TO THE WORLD
This continuing series examines how to connect your Commodore to the outside world and gives you a small project for controlling the user port.
By Jim Grubbs

124 MENU, PLEASE
Here are routines that will add easy menu-handling to your Basic programs.
By Paul J. Motise

DEPARTMENTS

6 RUNNING RUMINATIONS

8 MAGIC
Hints and tricks that will let you perform computing wizardry.

12 SOFTWARE GALLERY
Gyruss
NATO Commander
Financial Cookbook
Exodus: Ultima III
Blue Moon
Promal

20 COMPUTER TUTOR
Educational software reviewed

93 COMING ATTRACTIONS

126 COMMODORE CLINIC
A questions-and-answers column to help your ailing computer.

134 BOOK GALLERY

136 NEW PRODUCTS RUNDOWN

142 MAIL RUN

143 HOW TO TYPE IN LISTINGS

143 RUN AMOK

Cover photograph by Ed Judice

Page 46

Page 30



Page 50

RUN (0741-4285) is an independent journal not connected with Commodore Business Machines, Inc. *RUN* is published monthly by CW Communications/Peterborough, Inc., 80 Pine St., Peterborough, NH 03458. U.S. subscription rates $19.97, one year; $29.97, two years; $41.97, three years. Canada and Mexico $22.97, one year, U.S. funds drawn on U.S. bank. Foreign $39.97, one year, U.S. funds drawn on U.S. bank. Foreign air mail subscriptions—please inquire. Application to mail at 2nd class postage rates is pending at Peterborough, NH 03458, and at additional mailing offices. (Canadian second class mail registration number 9565.) Phone: 603-924-9471. Entire contents copyright 1985 by CW Communications/Peterborough, Inc. No part of this publication may be printed or otherwise reproduced without written permission from the publisher. Postmaster: send address changes to *RUN*, Subscription Services, PO Box 954, Farmingdale, NY 11737. (Send Canadian changes of address to *RUN*, PO Box 1051, Fort Erie, Ontario, Canada L2A 5N8.) Nationally distributed by International Circulation Distributors. *RUN* makes every effort to assure the accuracy of articles, listings and circuits published in the magazine. *RUN* assumes no responsibility for damages due to errors or omissions.



Byting and Fighting

Don't you just love price wars?

If you've been around the computing scene for more than two years, you've probably witnessed more than your share of skirmishes in the low-end home computer arena.

For example, Texas Instruments was soundly defeated when it pitted its contender, the TI 99/4A, against the spunky Commodore VIC-20 in late 1982. And Atari emerged bloodied and battered when it went against the same Commodore foe with its Atari 400 computer.

Now Commodore and Atari are at it again. They're squaring off with drastic price reductions for their respective machines, the C-64 and the 800XL.

The C-64 is selling at a bargain price of around $150 (if you scout around, you may find it for less at some dealers and distributors). Atari head, ex-Commodore boss Jack Tramiel, has countered by dropping the price of the Atari computer to $99.

What this means is good news for the home computer shopper.

Clearly, Commodore and Atari are selling off their inventories to make way for new entries into the market. And these new offerings are more powerful, more sophisticated home computers.

Commodore's C-128 is expected to make its appearance sometime next month. For the first time, Commodore is introducing a computer that is compatible with the C-64 and its thousands of programs. In addition, Commodore's newest home computer features 128K and a CP/M mode. These capabilities, combined with a low price of around $300, make the C-128 a purchase difficult to pass up.

This poses a dilemma for Commodore enthusiasts: Should you wait for the release of the C-128 or take advantage of the bargain-priced C-64? Whatever, don't wait too long. You'll soon be faced with another buying decision.

Commodore is scheduled to introduce an even more powerful home computer later this summer. Tentatively called the Amiga, this latest of the new machines will sell for a little over $1000 and feature graphics capability not found in computers costing two to three times as much.

You'll be reading more about the Amiga in upcoming issues.

RUN's GAMEPAK

RUN has planned something very special for all Commodore owners, particularly for those who enjoy playing quality games on the C-64.

It's called RUN's GAMEPAK and is our first ReRUN issue devoted entirely to one theme—games. This GAMEPAK is packed with 19 super games to run on your C-64. It features the best of *RUN*'s published games, as well as games that we have not yet published and may never have the chance to publish due to space limitations.

Newcomers to *RUN* will be pleased at this opportunity to share in some of our games from previous issues and to get a feel for the quality of programs that we offer.

This ReRUN issue holds a wide appeal for game players of all ages. You can choose from an impressive array of action-packed arcade games.

If you want an intellectual challenge, we also have several brain teasers and educational games to exercise your brain muscles.

Furthermore, we have included some old-time favorites—Tag, Shuffleboard and the Shell game—that have been played by families and friends for years before the advent of the computer.

Finally, we are pleased to present a superb adventure game—the best ever submitted to *RUN*—that's guaranteed to keep you on the edge of your computer chair.

Of course, all ReRUN programs are fully tested and eliminate the tedious job of entering program listings. Just load ReRUN into your C-64 and enjoy the fun.

RUN's GAMEPAK will be available in May. To order, simply call toll-free 1-800-258-5473 or contact Debbie Bourgault, ReRUN, 80 Pine Street, Peterborough, NH 03458.

db

PUBLISHER
Stephen Twombly

EDITOR-IN-CHIEF
Dennis Brisson
MANAGING EDITOR/PRODUCTION
Swain Pratt
MANAGING EDITOR/EDITORIAL
Shawn Laflamme
COPY EDITOR
Marilyn Annucci
REVIEW EDITOR
Susan Tanona
EDITORIAL ASSISTANT
Harold Bjornsen

TECHNICAL MANAGER
Guy Wright
TECHNICAL EDITOR
Margaret Morabito
TECHNICAL ASSISTANT
Tim Walsh

ASSOCIATE EDITORS
Christine Adamec, Robert Baker,
Louis F. Sander, Jim Strasma

ADVERTISING SALES MANAGER
Steve Robbins
SALES REPRESENTATIVE
Ken Blakeman
AD COORDINATOR
Heather Paquette
1-800-441-4403
WEST COAST SALES
Giorgio Saluti, manager
1-415-328-3470
1060 Marsh Road
Menlo Park, CA 94025
WEST COAST BUREAU EDITOR
Jim Forbes
1-415-328-3470

ART DIRECTOR
Glenn Suokko
PRODUCTION SUPERVISOR
Rosalyn Scribner
PRODUCTION ASSISTANT
Lynne Simonson
AD/GRAPHICS MANAGER
Jane Preston

MANUFACTURING MANAGER
Susan Gross
GRAPHIC SERVICES SUPERVISOR
Dawn Matthews
TYPESETTING MANAGER
Dennis Christensen
FILM PREPARATION MANAGER
Robert M. Villeneuve
DARKROOM MANAGER
Nathaniel Haynes

VICE-PRESIDENT/GENERAL MANAGER
Debra Wetherbee
VICE-PRESIDENT/FINANCE
Roger Murphy
ASSISTANT GENERAL MANAGER
Matt Smith
ASSISTANT TO VP/FINANCE
Dominique Smith
EXECUTIVE CREATIVE DIRECTOR
Christine Destrempes
DIRECTOR OF CIRCULATION
William P. Howard
ASSISTANT CIRCULATION MANAGER
Frank S. Smith
DIRECT &NEWSSTAND SALES MANAGER
Raino Wirein
800-343-0728
DIRECTOR OF CREDIT SALES &COLLECTIONS
William M. Boyer
FOUNDER
Wayne Green

Circle 105 on Reader Service card.

TWO MINUTES FLAT



It takes two minutes flat for the PPI, using Doodle™, to print this picture...*properly.* Other interfaces take up to 43 minutes and cost as much as $149.95.
Enough said.

PPI with graphics buffer

$49.95 (Sugg. Retail)

PARALLEL PRINTER INTERFACE
FOR USE WITH THE COMMODORE Vic 20 and C64

PRINTERS

Fujitsu	Citizen	Olympia Compact NP	Blue Chip
Epson	BMC	Star Micronics Delta	Brother DX-5
Radix	Inforunner	Smith Corona DP Series	Brother DM-40
Riteman	Panasonic KXP	Star Micronics Gemini	Okidata
		Mannesmann Tally MT160	(in Transparent mode)

FEATURES

- True Commodore Graphics.
- Expanded Reverse Alpha, Numeric, and Graphic Characters.
- Total Emulation of Commodore's Graphic, Character, and Command Set.
- Combining of Expanded and Condensed Print features.
- Combining of Emulation and Transparent Modes.
- No confusing DIP switches.
- 15 page easy to follow Users Manual.
- Fully Shielded from end to end.

Distributor and dealer programs available.
Call 316-264-6118 for immediate information.

dsi

DATA SHARE, INC.
717 South Emporia - Wichita, Ks. 67211-2307
316-264-6118 Telex: 650 193 4977
DSI is a major OEM and private label manufacturer. Call for complete information and quotations.
Doodle Art by Wayne Schmidt courtesy of City Software.

Compiled by LOUIS F. SANDER

MAGIC is tricks, MAGIC is fun. MAGIC is doing what cannot be done.

MAGIC is tricks, MAGIC is fun.
MAGIC is doing what cannot be done.

Every month, Magic brings you brief and useful computer tricks from around the world—tricks to make computing easier, more enjoyable or more exciting. We number our tricks in hex, the counting system of sorcerers and computerists.

Magic solicits your simple hardware ideas, short programs, useful programming techniques, little-known computer facts and similar items of interest. We look for new or recycled material that can be implemented with a minimum of time, effort or theoretical knowledge and that is of current value to Commodore computerists (Plus/4 and C-16 owners, too). We typically pay $10 for each trick accepted. Really super ones get $20 or more. Send your tricks to:

MAGIC
c/o Louis F. Sander
PO Box 101011
Pittsburgh, PA 15237

If you enclose a self-addressed stamped envelope, we'll send you a Trick Writer's Guide.

This month's Magic will be especially useful for typing in programs and working with disk drives. But no matter what your interest, our *juju* bag surely has something you can use.

$1C1 April Fool's program—When he's not looking, run this on a friend's VIC or C-64. Then get him to type a line or two, and watch the fun as he scrambles for his warranty.

```
10 POKE207,0:POKE204,0:WAIT198,1:GETA$:PRINT
   "{CTRL RVS OFF}"CHR$(ASC(A$)+1.1*RND(0));:GOTO 10
```

Don't forget the semicolon after the Print statement. Add to the fun by entering POKE808,225 (for the VIC, POKE808,100) before you run the program. (It disables the Stop, Restore and List commands.)

People have become famous by running this program at school or on machines displayed in stores.

Larson E. Rapp
Newington, CT

$1C2 Linefeed fix—Commodore computers are subject to an occasional but maddening malady, where the cursor refuses to linefeed when the return key is pressed. It will jump to the end of the current line, but will refuse to go any further. The problem usually arises when hardcopy printing is aborted by the stop key or some other non-standard means.

Pressing the shift key along with the return key will move the cursor to the start of the next screen line. Then, typing a letter or two and pressing the return key will cause a Syntax error, which will end the linefeed problem.

At this point, there is probably some garbage in your printer's buffer. Give it something unimportant to print, and the buffer will clear itself.

Beldare Lecone
Remulac, France

$1C3 SX-64 printer interface—As most owners know, the SX-64 has no cassette port from which to pick up +5 volts for the popular Cardco +G printer interface. Not so many people know that on most printers with a Centronics interface, pin 18 of the printer connector is a source of +5 volts. That is the case on my Panasonic KX-P1091 printer, and I took advantage of it by making an easy modification to my Cardco.

I opened up the Cardco +G, cut the white 5-volt power wire that went to the cassette connector and resoldered it to pin 18 of the printer connector. This arrangement has worked for over six months without any sort of problem. My Cardco warranty is probably void, but at least I'm able to use my printer.

T.V. Dinsmore
Knoxville, TN

$1C4 Magazine hacking—Whenever my magazines arrive, I go through each with a colored marker in hand, usually a translucent yellow one. I circle small

YOUR COMMODORE 64™ CAN NOW USE STANDARD APPLE™ II+ HARDWARE AND SOFTWARE

WITH THIS

At Mimic we believe that you and your computer should dictate the choices of hardware and software you can use.

The Spartan™ was developed to allow you to choose the hardware and software that best suits your needs.

Our goal in designing the Spartan™ was simple. To take what you already have and give you more.

Mimic Systems is proud to give you the Spartan™ The Apple™ II + emulator for the Commodore 64™

Spartan™ Suggested Retail Prices:

The Spartan™ (includes BUSS, CPU, and DOS cards) $599.00
BUSS card $299.00
CPU card (requires BUSS card) $199.00
DOS card (requires BUSS and CPU card) $199.00

(All prices in U.S. Funds. Freight not included.)
American Express, Visa and MasterCard accepted.

Commodore 64 and Commodore logo are trademarks of Commodore Electronics Ltd. and or Commodore Business Machines, Inc. Apple® II + is a trademark of Apple Computer, Inc. Spartan™ is a trademark of Mimic Systems Inc., and has no association with Commodore Electronics or Apple Computer, Inc. The Spartan is manufactured by Mimic Systems Inc. under license granted by ATG Electronics Inc. of Victoria, B.C., Canada.

MIMIC

FOR INFORMATION WRITE:

MIMIC SYSTEMS INC.
1112 FORT ST., FL. 6A
VICTORIA, B.C.
CANADA V8V 4V2

Circle 43 on Reader Service card.

To Order Call:
1-800-MODULAR
(663-8527)

items of special interest to me, such as interesting Magic tricks. I scan each article briefly, and if it appears to be of interest, I circle its listing in the Table of Contents. For advertising, I circle items I'm interested in, then put a line through their listings on the advertiser's page in the back. I also circle the number on the page of the ad itself so it stands out when I flip through. Later, I make up a card file on articles and so on. When my disk drive operates properly, I will set up disk files to replace the cards.

D.G. Munoz
Dania, FL

$1C5 Bookwork—After working with my system for several months, I found myself returning again and again to the same few pages and tables in my computer's reference guide. To make things easier, I copied my most frequently used pages and glued them to different-colored sheets of construction paper. Now I have a series of easy-to-find color-coded reference cards with all the sprite information, ASCII codes and other functional charts as needed. What a time saver it has been for me!

Mrs. Ruth A. Hicks
Oak Run, CA

$1C6 Magazine work—Every computer magazine has its own system of listing programs, and there's little standardization in the symbols they use for cursor and other special characters. You can make your life easier by copying the "how to type in listings" sections from each of your favorite magazines, then pasting them all onto an 8½- × 11-inch card. If you keep the card close by, you can use it as a handy reference when typing in programs.

Deb Sullivan
Pittsfield, MA

$1C7 Musical stitchery typing tip—As an aid in typing programs, my husband and I have combined equipment from two other hobbies, music and cross-stitch. A music stand allows us to easily adjust the height of our material. To keep our place while typing, we use the metal sheet and magnetized strips that are sold as place holders for cross-stitch patterns. With the metal sheet behind the page we're working on, we slide the magnetized strip under the lines being typed. One word of warning: The magnetized strips can be disastrous to disks and tapes, so keep them away from your magnetic media.

Barbara Eberly
Cullowhee, NC

$1C8 Program placekeeping—When typing in long programs, use a hi-liter marker to record your progress. These markers are available in transparent pastel colors in any stationery department. Every five lines or so, cross off the completed material with your marker. This is also a good method to use when checking for typing mistakes.

Ellen Pekar
Florence, MA

$1C9 Magazine magnifier—I went to a store where needlepoint and embroidery notions are sold, and I bought a line magnifier, made for use with sewing instructions. It works quite nicely in magnifying the program lines as I type in goodies from *RUN*.

Mildred Carroll
Rosedale, NY

$1CA Keyboard overlays—When using complex programs like Easy Script and Simons' Basic, the function keys, and usually others, have many hard-to-remember purposes. Cardboard overlays for your keyboard can make it easier to use these programs.

Get pieces of thin cardboard from a stationery store or shirt laundry, then measure the dimensions of your computer and its keyboard area. Cut the cardboard to fit your computer, then cut out places for the keyboard areas. When you put the overlay in place, your keys will be surrounded by cardboard on which you can write the instructions appropriate to your program. If you own several complex programs, it's easy to make an overlay for each.

Mary D. Brigito
Old Forge, NY

**$1CB Escape literature**—Many printers require the ASCII escape character, CHR$(27), to be sent as part of various control sequences. Commodore computers don't have an escape key, and there's nothing in the documentation to show how one can be rigged. Fortunately, the matter is easily resolved, since pressing {CTRL : } generates an escape character.

If the computer is in Quote mode, a reverse-field left bracket will come up on the screen, and when that character is printed, the escape code will be sent. If your printer is open to file #4, an escape can be sent to it by entering:

```
PRINT #4,"{CTRL : }"
```

Of course, {CTRL :} means to hold down the control key, then hit the colon.

Mrs. Deane Maddocks
Glenwood, IA

$1CC Easy GO testing—When testing a program that uses On...Go commands, or perhaps computed Goto's, it's useful to establish dummy lines as the targets for those commands, so you can get easy proof that the program is going where you want it to. Once you have that proof, you can replace the dummies with more interesting sections of code.

Continued on p. 106.

Now You Can Add

New!

ARTIFICIAL INTELLIGENCE

To Your Programs Using a Powerful Combination

"SUPERFORTH 64" +AI

By Elliot Schneider & Jack Park

Heres Your Chance to Profit by being on the Forefront, Write 5th Generation Software

Learn How To:

- Create Intelligent Programs
- Build Expert Systems
- Write Stand Alone License Free Programs
- Construct Rule Bases
- Do Knowledge Engineering
- Use Inference Engines

Write Intelligent Programs For:

- Home Use
- Robotics
- Medical Diagnosis
- Education
- Intelligent CAI
- Scientific Analysis
- Data Acquisition
- Data Analysis
- Business
- Real Time Process Control
- Fast Games
- Graphics
- Financial Decisions

Extended Math Functions

- Fast ML Floating Point & Integer Math
- Double Precision 2E±38 with Auto. Sci Not.
- n×e× Logx Loge Sin Cos Tan SQR 1/X...
- Matrix and Multidimensional Lattice Math
- Algebraic Expression Evaluator

Easy Graphics & Sound Words

- Hires Plotting
- Windows
- Split Screen
- Printer/Plotter Ctrl
- Sprite & Animation Editor
- Turtle Graphics
- Koala Pad Graphics Integrator
- Hires Circle, Line, Arc
- Music Editor
- Sound Control

Easy Control of all I/O...

- RS232 Functions
- Access all C-64 Peripherals
- Interrupt Routines

Utilities

- Interactive Interpreter
- Forth Virtual Memory
- Full Cursor Screen Editor
- Full String Handling
- Trace & Decompiler
- Conditional Macro Assembler
- Interactive Compiler
- Romable Code Generator
- 40K User Memory
- All Commodore File Types
- Conversational User Defined Commands



Power of Languages Constructs

SuperForth 64 is more powerful than most other computer languages



Programming Time

SuperForth 64 Saves You Time and Money

Great Documentation

- Easy to Read 350 pg. Manual with Tutorials
- Source Screen Provided
- Meets all MVP Forth-79 Industrial Standards
- Personal User Support

A Total Integrated Package for the Commodore 64 & C-128



See us at the 10th West Coast Computer Faire Booth 2317 Moscone Center San Francisco March 30—April 2

SPECIAL INTRODUCTORY OFFER

Disk & Manual only **$99.00**

$203.00 Value
Limited Time Offer

MasterCard AMERICAN EXPRESS VISA

($2.50 Ship U.S.A. • $2.00 C.O.D., U.S.A. • $15.00 Overseas)

See Your Local Computer Store or CALL

for orders outside of California

(800) 633-6335

for additional information

(415) 651-3160

PARSEC RESEARCH

Box 1766 Fremont, CA 94538

Dealer Inquiries Invited

Commodore 64 TM of Commodore ®Parsec Research

Circle 208 on Reader Service card.



Compiled by SHAWN LAFLAMME

Gyruss

A

This C-64 Conversion From Parker Brothers Rivals the Arcade Original

You're 30 billion miles from Earth and two warps away from the planet Neptune. Your mission is to stop at each of the five worlds that separate you from Earth and destroy any enemy aircraft that you encounter. You must also beware of deadly meteors, run-away satellites and the hostile alien spacecraft that pursue you all the way to Earth.

Gyruss is an exceptionally well-written conversion of the arcade game. The graphics of Gyruss include well-designed spacecraft, meteors and an interesting space warping effect that rivals the graphics of the original. The planets are depicted with precision, with details such as the canals of Mars and the recently discovered rings of Uranus. An updated version of Bach's Toccata and Fugue in D Minor plays throughout the program, adding an interesting element to the game.

Gameplay consists of a series of warps and chance stages. During each warp, forty alien spacecraft dive and loop onto the screen in four squadrons. You must destroy as many airships as possible and avoid being hit by their return fire.

When you succeed in reaching a planet, chance stages begin. These are bonus screens that award 100 extra points for each ship that you destroy and a super 10,000-point bonus if you destroy all 40 of the aliens. These screens offer alien ships that don't fire back, but you have only seconds to destroy them before they disappear into the vastness of space.

There are two types of satellites in Gyruss. One resembles two blue molecules linked together by a connector. You must shoot the blue segments of the satellite for bonus points and destroy the connecting piece for double fire-power.

The second type of satellite consists of two white spheres connected by a long electromagnetic wave. You must shoot the white spheres of the satellite for extra points, without being destroyed by the deadly electromagnetic wave.

Meteors offer a very special challenge to the space pilot in Gyruss. These huge chunks of space rock cannot be destroyed, so you should avoid them as much as possible. The game is over when all of your spacecraft have been destroyed. If you do manage to complete your journey to Earth, your spaceship will reappear two warps from Neptune and the game will resume.

Gyruss combines excellent graphics with numerous sound effects and fantastic background music. The actual area that you control is quite small—only a one-inch circular band beginning an inch from the outside edge of the screen. Although it seems that you would have little control over your fate under these circumstances, this game actually plays quite well. I recommend Gyruss to anyone who appreciates an excellent version of a very successful arcade game. *(Parker Brothers, 50 Dunham Road, Beverly, MA 01915. C-64/$40 cartridge.)*

John Jermaine
Taylorville, IL

Report Card

A ***Superb!*** An exceptional program that outshines all others.

B ***Very Good.*** One of the better programs available in its category. A worthy addition to your software library.

C ***Good.*** Lives up to its billing. No hassles, headaches or disappointments here.

D ***Mediocre.*** There are some problems with this program. There are better on the market.

E ***Poor.*** Substandard, with many problems. Should be deepsixed!

NATO Commander

B

Command NATO Forces In a Confrontation With The Warsaw Pact

You have recently been sworn in as commander of the NATO forces deployed in West Germany. These troops consist of U.S., West

PlayNET announces 19 exciting ways to bring people together.

$19.95 SPECIAL LIMITED TIME OFFER–Expires April 15th
39.95 SUGGESTED RETAIL PRICE

Now there's a Home Computer Network that lets you communicate with all kinds of people—all over the country! Make new friends, play exciting games, barter—shop—trade, all from the comfort of your home.

The network operates 6PM–7AM every weeknight, and 24 hours on Saturday, Sunday and Holidays. All you need to access PlayNET™ is a COMMODORE 64,* DISK DRIVE and MODEM.

1 TALK.
By typing on-line you can *talk to anyone,* or everyone, on the system. Meet fascinating people and make new friends from coast to coast.

2 ELECTRONIC MAIL.
You can *send private messages* to people on the system, and the message will be waiting when they sign on!

3 BULLETIN BOARDS.
You can *post announcements,* or check the listings of other members. There are lots of boards for hobbies and special interests! If you don't find the one you're looking for—create your own!

4 FILE TRANSFER.
You can even *transfer non-commercial programs* to other members! There is a small extra fee for this service.

5-17 GAMES! GAMES! GAMES!
PlayNET lets you play exciting games with real people, not just a computer. All our games have *full color* graphics, and they're all *interactive!*

- Plus the added feature of being able to talk with your opponent while you play. Discuss strategy, comment on moves, even try and psych your opponent out!
- New games are added all the time, and there are tournaments for every skill level.

CURRENT GAMES INCLUDE:

- Backgammon
- Boxes
- Capture the Flag
- Checkers
- Chess
- Chinese Checkers
- Contract Bridge
- Four-In-A-Row
- Go
- Hangman
- Quad 64™
- Reversi
- Sea Strike™

18 MORE! MORE! MORE!
There's *on-line updating* of your PlayNET Software as games and services are added. You have access to PlayNET's *Shopping Center* and *Information Center,* and every month you'll get our *Newsletter.*

19 YOUR SATISFACTION IS GUARANTEED for 30 days (or your full subscription price will be refunded upon receipt of the package).

39.95 Suggested retail/Now 19.95

- $19.95 for the PlayNET Software Package (3 disks and a User Manual), Monthly Newsletter, and 90 MINUTES ON-LINE TIME FREE!
- $6 monthly service charge.
- $2 an hour on-line time (the $2 includes the telecommunication charges). That's much less than a long distance phone call.

Here's how you can become a member!
It's easy to join, simply call PlayNET on the toll-free number, **1-800-PLAYNET,** or send the coupon below and access all your Commodore 64 has to offer. The sooner you do, the sooner PlayNET can put the whole country at your fingertips!

PlayNET
The Network that has people talking

SEND TO PLAYNET, INC.
P.O. BOX 596,
WYNANTSKILL, N.Y. 12198

SPECIAL OFFER EXPIRES
Postmark or call 1-800-PLAYNET
by April 15, 1985

50

YES! I WANT PlayNET TO PUT THE WHOLE COUNTRY AT MY FINGERTIPS. I UNDERSTAND THAT MY SATISFACTION IS GUARANTEED FOR 30 DAYS (or my full subscription price will be refunded upon return of the package) I may cancel my membership at any time by writing PlayNET.

Bill my charge card or checking account via CHECKFREE® for $19.95 and subsequent monthly fees. (Plus sales tax for New York State residents). No cash or money orders accepted. Please send me the PlayNET Software, User Manual, and 90 minutes of free on-line time.

Please print.
Name_____
Address_____
City_____ State_____ Zip_____
Phone ( )_____
Check one: ☐ MasterCard ☐ VISA ☐ Checking Account via CHECKFREE (please attach voided check)
Card #_____ Exp. Date_____
Signature_____

™ PlayNET, Quad 64 and Sea Strike are trademarks of PlayNET, Inc. *Commodore 64 is a trademark of Commodore Business Machines Inc. © 1985 PlayNET, Inc.

Circle 221 on Reader Service card.



German, Dutch, British and Belgian infantry, armor and air forces. If war breaks out, you must block Warsaw Pact armies from overrunning Germany and western Europe. As the days pass, you receive news reports of growing tension between the east and west; everyone is preparing for a new war.

So begins NATO Commander, a strategy game played in simulated real time. You have a choice of four scenarios, which are minor variations of the main theme, and three difficulty levels. You always assume the role of NATO Commander and the computer plays the part of Warsaw Pact Commander.

The game is played on a vertically scrolling map of Germany, with symbols for towns, roads, rivers, mountains and forests. Eastern and Western units are displayed in different colors and each type of military unit is represented by a different symbol.

As night falls, the screen turns dark and the units are highlighted in color. At midnight on each day of combat, you receive a coded commander report in text if you correctly enter a supposedly secret code. (After the first day, the reports are automatic.)

Throughout the battle, radio messages flash across the screen to tell you which of your units have encountered the enemy or surrendered.

NATO Commander uses colorful map displays, but almost no sound. Map and unit symbols take some getting used to, and while the manual does explain unit symbols, it does not offer a table of map symbols.

Unfortunately, the program always distributes forces in the same way, no matter which game or level of difficulty you choose. The game is fairly easy to win at the lowest difficulty level and the added difficulty at the more advanced levels is rather unrealistic. Your casualty rates simply go up and you are forced to use your air force to suppress the enemy's air force rather than to support your ground forces.

Perhaps the most outstanding feature of NATO Commander is that it really gives you the feeling of being a senior military commander in a rapidly changing and frequently deteriorating military situation. Have you ever wondered why a general would consent to unleashing chemical or nuclear war? NATO Commander might give you a few answers. It is one of a new breed of games that combines the challenge of a thinker's strategy game with the excitement of an arcade game. *(MicroProse Software, 10616 Beaver Dam Road, Hunt Valley, MD 21030. C-64/$35 disk, tape.)*

Jerome Beck
Glendora, CA

Financial Cookbook

B

A Collection of Recipes for Better Financial Management

Money, and how to manage it effectively, is what Financial Cookbook is all about. Do you have a clear idea of what you're actually paying in interest on a loan, or the financial impact of inflation? If you're interested in where your money goes or how it is being utilized, then Financial Cookbook should fill your needs.

Many people are intimidated by the idea of high finance, principal vs. interest, variable-rate mortgages, IRAs, leasing vs. buying and so on. You would be surprised to learn what you're actually paying to rent someone else's money. The challenge in producing this program was to make it highly flexible, yet simple to use. It succeeds gloriously on both counts.

Here are a few examples of what's on the menu (or recipe) index: Understanding Your Marginal Tax Rate, Single Savings Deposits, Long Term Investments, Saving Money with IRAs, Mortgage Schedule (Yearly) and Buying or Renting a Home. It's quite an impressive recipe collection!

For example, if you are considering a home mortgage, select the Yearly Mortgage Schedule recipe. You input the amount of the loan, the interest rate percentage and the term of the loan. That's all there is to it. The results will come up on the screen, and if you scroll down the table, you can see how much of your payment will go toward interest and principal each year. All the menu options are equally simple. It's like having your own private accountant or investment planner right there giving you custom-tailored projections (but without the high fees).

Before you make that major investment or financial commitment, your money will be well spent to first get a copy of Financial Cookbook so that you can explore all of your options. I highly recommend it! *(Electronic Arts, 2755 Campus Drive, San Mateo, CA 94401. C-64/$40 disk.)*

Tom Benford
Bricktown, NJ

Exodus: Ultima III

A

Battle the Evil Exodus In Your Quest to Save the Land of Sosaria

First came the evil wizard Mondain, then his cunning apprentice Minax. After tremendous struggles and heroic sacrifices, both were duly defeated and overthrown. But the omens indicate that a far greater evil, known only as Exodus, has arisen to vent his fury upon the land of Sosaria.

A Printer For All Reasons

Search For The Best High Quality Graphic Printer

If you have been looking very long, you have probably discovered that there are just too many claims and counter claims in the printer market today. There are printers that have some of the features you want, but do not have others. Some features you probably don't care about, others are vitally important to you. We understand. In fact, not long ago, we were in the same position. Deluged by claims and counter claims. Overburdened by rows and rows of specifications, we decided to separate all the facts — prove or disprove all the claims to our own satisfaction. So we bought printers. We bought samples of all major brands and tested them.

Our Objective Was Simple

We wanted to find that printer which had all the features you could want and yet be sold directly to you at the lowest price. We wanted to give our customers the best printer on the market today at a bargain price.

The Results Are In

The search is over. We have reduced the field to a single printer that meets all our goals (and more). The printer is the GP-550CD from Seikosha, a division of Seiko (manufacturers of everything from wrist watches to space hardware). We ran this printer through our battery of tests and it came out shining. This printer *can* do it all. Standard draft printing up to a respectable (and honest) 86 characters per second, and with a very readable 9 (horizontal) by 8 (vertical) character matrix. At this rate, you will get an average 30 line letter printed in only 28 seconds.

"NLQ" Mode

One of our highest concerns was about print quality and readability. The GP-550CD has a print mode termed Near Letter Quality printing (NLQ mode). This is where the GP-550CD outshines all the competition. Hands down! The character matrix in NLQ mode is a very dense 9 (horizontal) by 16 (vertical). This equates to 14,400 addressable dots per square inch. Now we're talking ***quality*** printing. You can even do graphics in the high resolution mode. The results are the best we've ever seen. The only other printers currently available having resolution this high go for $500 and more *without* the interface or cable needed to hook up to your Commodore!

Features That Won't Quit

With the GP-550CD your computer can now print 40, 48, 68, 80, 96, or 136 characters per line. You can print in ANY of 18 font styles. You not only have the standard Pica, Elite, Condensed and Italics, but also true Superscripts and Subscripts. Never again will you have to worry about how to print H_2O or X^2. This fantastic machine will do it automatically, through easy software commands right from your keyboard. All fonts have true descenders.

One of the fonts we like best is "Proportional" because it looks most like typesetting. The spacing for thin characters like "i" and "l" are given less space which "tightens" the word making reading easier and faster. This is only one example of the careful planning put into the GP-550CD.

Do you sometimes want to emphasize a word? It's easy, just use **bold** (double strike) to make the words stand out. Or, if you wish to be even more emphatic, underline the words. Or do both. You may also wish to "headline" a title. Each basic font has a corresponding elongated (double-wide) version. You can combine any of these modes to make the variation almost endless. Do you want to express something that you can't do with words? Use graphics with your text — even on the same line.

You can now do virtually any line spacing you want. You may select 6, 8, 7½ or 12 lines per inch. PLUS you have variable line spacing of 1.2 lines per inch to infinity (no space at all) and ***97*** other software selectable settings in between. You control line spacing on a dot-by-dot basis. If you've ever had a letter or other document that was just a few lines too long to fit a page, you can see how handy this feature is. Simply reduce the line spacing slightly and . . . VOILA! The letter now fits on one page.

Forms? Yes! Your Letterhead? Of Course!

Do you print forms? No problem. This unit will do them all. Any form up to 10 inches wide. The tractors are adjustable from 4½ to 10 inches. Yes, you can also use single sheets. Plain typing paper, your letterhead, short memo forms, anything you choose. Any size under 10" in width. Multiple copies? **Absolutely!** Put forms or individual sheets with carbons (up to 3 deep), and the last copy will be as readable as the first. Spread sheets with many columns? **Of course!** Just go to condensed mode printing and print a full 136 columns wide. Forget expensive wide-carriage printers and changing to wide carriage paper. You can now do it all on a standard 8½" page.

Consistent Print Quality

Most printers have a continuous loop ribbon cartridge or a single spool ribbon which gives nice dark printing when new, but quickly starts to fade after a while. To keep the printers' output looking consistently dark, the ribbons must be changed more often than is healthy for the pocketbook. The GP-550CD solves this problem completely by using a replaceable, inexpensive ink cassette which is separately replaceable from the actual ribbon. It keeps the ribbon loaded with ink at all times. You only replace the ribbon when it truly wears out, not when it starts to run low on ink. Just another example of the superb engineering applied to the GP-550CD. (When you finally do wear out your ribbon, replacement cost is only $10.95. Ink cassette replacement cost is only $5.95, both postpaid.)

The Best Part

When shopping for a quality printer with all these features, you could expect to pay around $500 or more. *Not any more!* We have done our homework. You don't have to worry about interfaces or cables. Everything is included. We are now able to sell this fantastic printer for **only $259.95!** The GP-550CD is built especially for the Commodore 64, VIC-20, Plus 4 and C-16. All Commodore graphics are included. This printer does everything the Commodore printers do but has more features. **You need absolutely nothing else to start printing–just add paper.** We also have specific models for other computers. Call for details.

No Risk Offer

We give you a 15-day satisfaction guarantee. If you are not completely satisfied for any reason we will refund the full purchase price. A 1-year warranty is included with your printer. The warranty repair policy is to repair or replace and reship to the buyer within 72 hours.

The Bottom Dollar

The GP-550CD is only $259.95. Shipping and insurance is $8.00 — UPS within the continental USA. If you are in a hurry, UPS Blue (second day air) is $18.00. Canada, Alaska, Mexico are $25.00 (air). Other foreign is $60.00 (air). California residents add 6% tax. These are cash prices — VISA and MC add 3% to total. We ship the next business day on money orders, cashiers' checks, and charge cards. A 14-day clearing period is required for checks.

TO ORDER CALL TOLL FREE

1-(800) 962-5800 USA
or 1-(800) 962-3800 CALIF.

or send payment to:

APROPOS TECHNOLOGY
1071-A Avenida Acaso
Camarillo, CA 93010

Technical Info: 1-(805) 482-3604

©1984 APROPOS TECHNOLOGY



This is the setting for Ultima III, the third in the extremely popular Ultima series. The game includes a two-sided disk, a cloth map of Sosaria, two books of spells, a rule book and a reference card. No joystick is needed.

The basic premise is straightforward: You have been enlisted by Lord British to free his realm from the influence of Exodus. Accomplishing this task will take you across the breadth of Sosaria and its neighboring seas, through forests, towns and dungeons. You will have to overcome the attacks of roving monsters, garner treasure and important magical items, solve puzzles and interpret clues.

You create your own characters, with a choice of five races and eleven professions that offer a wide variety of characteristics and abilities. You may then form your adventuring party, which may include up to four characters.

The true magic of Ultima III lies in the graphics. Every game sequence is animated and in superb color. In towns, the characters stroll along cobblestone streets past dancing jesters and other assorted townspeople going about their business. The screen limits your vision to what your characters can actually see; thus, mountains and buildings block your sight so that you do not know what awaits you on the other side until your characters actually venture there. The game even contains a musical score that changes according to location.

The dungeons are displayed three-dimensionally, and this is one drawback to the game. The monsters in the dungeons do not appear on screen until you actually encounter them, so you have no opportunity to flee or somehow avoid the creatures.

Combat takes place on a special battle screen in real time, and each character can act individually. To survive and prosper in the world of Ultima III, you must quickly learn how to use your own particular strengths to your advantage in battle.

Combat is always to the death, which is another drawback of Ultima III. Characters are often forced to fight—an option to withdraw from combat after a certain amount of time would be a good alternative and would help extend the lifespan of many inexperienced or weakened characters.

In Ultima III, you will quickly learn that the game gives very little away and you must really work for your rewards. A word of caution may be helpful: Things are often not quite as they appear to be. Even the benign Lord British has his dark side.

Ultima III combines the mystery and problem-solving challenges of text adventures with arcade action. Until Ultima IV or something comparable comes along, Ultima III will remain the best on the market. *(Origin Systems, Inc., PO Box 99, 1545 Osgood St. #7, North Andover, MA 01845. C-64/$34.95 disk.)*

Jeff Seiken
Potomac, MD

Blue Moon

C

Five Screens of Arcade Action Highlight This British Import

Merlin Software's Blue Moon is a fast action British import for the C-64, available in the U.S. from 3R Import and Export Corp.

Blue Moon combines many challenges that should look familiar if you've spent any time in an arcade. There are five distinctly different screens, all of which require joystick mastery to survive.

As the pilot of an intergalactic spacecraft, your mission is to rescue a sister ship and her crew who are being held captive on a hostile planet and return with them to the Blue Moon.

You must begin your journey back to the Blue Moon by connecting the two modules of your spacecraft. This maneuver requires absolute precision; the slightest slip of the stick will destroy your ship.

The next three screens will give your trigger finger an exhausting workout. A comet storm is the first hazard you'll encounter. The comets streak across the top of your screen and occasionally plummet toward your spacecraft at the bottom. If you can survive the storm, the Blue Bouncers will harass you next. These nasty little aliens bounce across the screen in dizzying patterns, making the comet storm look serene in comparison.

The deadly Tecom Man is your final nemesis. Drifting slowly across the top of the screen, he releases droids and large yellow eggs, which

Imagine...

FOR COMMODORE 64 ATARI APPLE IIe/c AND IBM PCjr

A WORD PROCESSING PROGRAM!
AN INFORMATION MANAGEMENT PROGRAM!
A TELECOMMUNICATIONS PROGRAM!

ALL THREE PROGRAMS, ON ONE DISKETTE!, FOR ONLY $49.95*!

"Quite simply the best! The highest rating possible...the package should be part of every (computer) library." — ANALOG COMPUTING

"Russ Wetmore has done an EXCELLENT job! The program is flexible, powerful and very easy to use. $49.95 buys a heck of a lot of program." — REVIEW BY ARTHUR LEYENBERGER

"Performance: ★ ★ ★ ★ (Excellent) Value: ★ ★ ★ ★ (Excellent)
This three-in-one package is a bargain . . . one of the finest values on the market."
— FAMILY COMPUTING

HOMETEXT WORD PROCESSOR.
HOMEFIND INFORMATION MANAGER.
HOMETERM TELECOMMUNICATIONS

Together they are **HomePak**: the three most important and most useful home computer applications in one integrated system — on one diskette!

The reviewers are unanimous: any one of these programs **alone** is well worth the price. So you're getting **three times the computing power**, with this exceptionally easy to use package:

- **all commands in simple English; no complex computer jargon, no obscure instructions**
- **all key commands are immediately available on the screen menu; additional commands can be called up for the more experienced user**
- **to help you, system status is displayed right on the screen**

And it's easy to use the three programs together. For example, in the "Merge" mode, you can take data stored in HOMEFIND and print letters and labels using **HOMETEXT**. Or, use **HOMETEXT** to write reports based on information you've called up via **HOMETERM**.


BATTERIES INCLUDED
HomePak™
A Breakthrough Integrated Software System
by RUSS WETMORE FOR STRATEGIC SIMULATIONS
3 in 1 Software System
HomeText™
A computerized writing tool. A comprehensive Word Processing program.
HomeFind™
An electronic filing system which you command with natural English sentences.
HomeTerm™
A telephone communications program that allows you and your computer to talk to the world.

BATTERIES INCLUDED

"The Energized Software Company!"

WRITE FOR A FULL COLOR BROCHURE

30 Mural Street
Richmond Hill, Ontario
L4B 1B5 Canada
(416) 596-1405
Telex: 06-21-8290

17875 Sky Park North
Suite P, Irvine, California
USA 92714
Telex: 509-139

*MANUFACTURERS SUGGESTED U.S. LIST PRICE

EACH COMPUTER SYSTEM MAY REQUIRE ACCESSORY DEVICES SUCH AS MODEMS, PRINTERS OR CARDS TO UTILIZE SPECIFIC FEATURES OF HOMEPAK. SEE YOUR DEALER FOR DETAILS.

© 1984 BATTERIES INCLUDED. ATARI, APPLE, COMMODORE AND IBM ARE REGISTERED TRADEMARKS OF ATARI CORP., APPLE INC., COMMODORE BUSINESS MACHINES AND IBM BUSINESS MACHINES INC., RESPECTIVELY.

fall toward your ship. Bell birds hatch from the eggs and attack you with plasma bombs. There's little room to breathe in this cluttered screen, and you'll have to clear it completely before you can move on toward home.

Your final task is to land safely on the Blue Moon. As in the first screen, there's no margin for error as you maneuver to one of three possible landing sites. When you've landed safely, the Union Jack is raised triumphantly over the Blue Moon.

The pace is fast and furious on the easiest level; on the higher levels, it's an absolute frenzy. In fact, Blue Moon could probably be used as a quality control test for joysticks.

The game is simple and straightforward. There's no manual—everything you need to know is on the back of the package. However, Blue Moon lacks some of the features found in other C-64 games of this type: There's no two-player option and no way to save high scores or pause a game in progress.

The scenario of Blue Moon as described in the game's introduction is rather misleading. There's no hostile planet and no sister ship to rescue. The game begins with your journey back to the Blue Moon; you're simply asked to imagine that a rescue has taken place. Also, in screens two through four, your spacecraft remains at the bottom of the screen, allowing for horizontal movement only. This technique, while effective in some game scenarios, fails to create the effect of traveling. Blue Moon is a good shoot-'em-up game, but it's a poor simulation of a journey through space.

Blue Moon's fast action and simple concept could make it a popular game with younger players. The arcade-quality graphics are appealing and colorful, and the action is complemented by entertaining sound effects and music.

If you're an arcade enthusiast, you won't find anything new or unusual in this game. But if fast-paced action is what you crave, then Blue Moon won't disappoint you. *(3R Import and Export Corp., 731 James St., Suite 405, Syracuse, NY 13203. C-64/$19.95 disk or tape.)*

Shawn Laflamme
***RUN* staff**

Promal

B

A Fast and Efficient Programming Development System



Promal is a new programming development system for the C-64. Version 1.0 of Promal comes with an executive that replaces Commodore's Basic interpreter. The executive has 23 commands and facilities that allow you to load and execute programs, manage files and disks and display and modify memory.

One powerful feature of Promal is its ability to redirect input and output. A program that normally outputs data to the screen can have its output redirected to a file or device by using the > operator. In the same manner, input can be taken from a file or device instead of the keyboard by using the < operator.

The Promal language is a structured language similar in syntax to C or Pascal. It supports high-level constructs such as If...Then...Else and Repeat...Until. Procedures and functions are supported, and a library of 43 machine language subroutines is supplied. These library routines are used to handle I/O, manage files, and perform string operations, data conversions and other assorted tasks. Arguments can be passed to the main program as well as to procedures and functions.

Promal supplies a full-screen text editor to assist you in creating source files. I found the Promal editor to be very powerful, with many useful features. The meaning of each function key is conveniently displayed on the bottom of the screen, along with the current line number and editor mode.

The Promal compiler is a very fast, one-pass compiler. It takes a Promal source file as input and generates an object file as output. This object file consists of a very compact pseudo-code (p-code) that averages six bytes per source statement. You can compile to or from disk or memory.

If the compiler encounters a Syntax error, the process stops, the appropriate error message is displayed and you will have the option to edit the source file. After a successful compilation, a sign-off message appears, displaying the number of lines compiled and the number of bytes produced.

To execute your compiled program, you simply type in the name of the program and the required arguments. The executive will search for the program in memory and execute it. If not found in memory, the executive will check for the program on disk, load it and begin execution.

I have compared Promal with other languages and compilers and my results were consistent with the company's claim that Promal is 70% to 2000% faster than any other language available for the C-64.

On the whole, I'm very impressed with the Promal package. The programming environment is friendly and a welcome change from Basic. The programs are compiled and executed very quickly. The thorough documentation consists of a 200-page manual, which is divided into three parts: a tutorial, a user guide and a language manual.

Promal does have some limitations. The language does not support multi-dimensional arrays, nor does it allow you to define records or structures. Also, a library of math functions should have been included.

Taking all things into account, Promal would be a powerful enhancement to your programming capabilities. *(Systems Management Associates, 3700 Computer Drive, Dept. MP-1, Raleigh, NC 27609. C-64/$49.99 disk.)*

Edward Rowe
Randolph, NJ

NOW SHOWING

1541 FLASH!

AT COMMODORE 64™ DEALERS

FLASH! Gets the Gold at the Computer Olympics

The Skyles Electric Works *1541 FLASH!* dashed off with the gold at the Computer Olympics here.

The *1541 FLASH!* loaded programs and files *three times faster* than an unenhanced Commodore 1541 disk drive could. Faster than any other disk drive with compatible disk format.

"...faster than any other disk drive..."

Three times faster! The device delighted the home crowd, which watched the *1541 FLASH!* set a meet record, and leave its competition in the dust.

Once installed, the *1541 FLASH!* is transparent. Computer operations all remain unaffected as it speeds up every disk-related function. The *FLASH!* is a permanent installation with both a software (ROM) and a hardware component. Through keyboard commands or a hardware switch, you can even return to the old, slow loading method—if you really want to.

And there is nothing new to learn for the *FLASH!* No special tricks or techniques. Once it's in, just watch it go.

But if you're really serious about programming, the *1541 FLASH!* is a gold mine. The manual will show you how to write software allowing data transfer to and from the 1541 disk drive at speeds up to *10 times* the normal.

For programs that usually load with a " '*',8,1" command, just hit Shift/Run-Stop. A spreadsheet program like BUSICALC 3 then loads in about 25 seconds.

The *1541 FLASH!* even adds 21 extra commands for the Commodore 64 user. Some of these include editing, programming and loading commands, as well as "DOS Wedge" commands. You can ignore all these commands, though, and just enjoy the rapid disk operations.

It wowed the crowd at the Computer Olympics. Once you see its sheer speed, you'll know why. Call its coach, Skyles Electric Works, to place your order or to get more info.

NOW AVAILABLE FOR THE SX-64™ . . . $99.00*

NOW AVAILABLE FOR TWO 1541's. . . $139.95*

1541 FLASH!*, an add-on assembly for the Commodore 64/1541, costs only $89.95.

*There is an additional $3.50 US and Canada, $10.00 Europe and Asia, shipping charge per order. California residents add sales tax.

Skyles Electric Works
231E South Whisman Road
Mountain View, CA 94041
(415) 965-1735

Circle 90 on Reader Service card.

Available from your local Commodore 64 dealer or call 1-800-227-9998.

1541 FLASH! is a trademark of Skyles Electric Works. Commodore 64 and SX-64 are trademarks of Commodore.



CHRISTINE ADAMEC

This month, RUN*'s bimonthly column on educational software focuses on some programs for the unexpanded VIC-20.*

Before I describe several good educational programs for the VIC-20, I'd like to share a concern expressed by a reader, Mason Caldwell, of Chesapeake, Virginia.

Caldwell wishes that he could see a program run before buying it for his child, and says of a recent experience, "I could not try the programs for my son, and the sales people were largely unfamiliar with the software that they had on their shelves." He wonders if CompuServe or another computer service could offer short demos of programs, and he compares such a service to music videos shown on TV. He adds, "The influence of music videos...on record sales would seem to indicate that a visual representation of a product would be a strong selling point."

Your point is well taken, Caldwell. Apparently, several software manufacturers agree, because they are beginning to include short demo programs with their software. It may be a while before we see this done on a large scale, but when it does happen, computerists will have a chance to preview programs before buying them.

Now, about the VIC's educational programs. There aren't many such programs available, since most companies are concentrating heavily on the C-64, but here are a few enjoyable ones to consider. (All of them run on the unexpanded VIC.)

Think Twice

This program from Academy Software includes Memory Fun and Flashcard Quiz. Memory Fun is an entertaining game similar to the old television game, Concentration. Your child may play alone or with a friend. The computer directs your child to type in his or her name, and your child must choose either designs, pictures or words. (Words are three-letter ones, like cat and man.)

Memory tester from Academy Software.



Springboard's Draw program for preschoolers.

A gameboard appears on the screen, composed of every letter of the alphabet and numbers 1–4. Under each "tile" is a picture and a word, and the child must find as many pairs as possible.

Overall, Memory Fun is a game that encourages your child to concentrate and think, and my children enjoyed it. They were too young, however, to appreciate Flashcard Quiz. This is a program designed for drill and practice, and it includes a datafile of state capitals for all 50 states. Your child can drill himself on either states or capitals. The computer registers errors and you can work on those troublesome ones even we adults tend to forget. You can also input your own datafiles using the manual instructions. *(Academy Software, PO Box 9403, San Rafael, CA 94912; $16.95, cassette.)*

Early Games for Young Children

This program from Springboard Software is composed of nine games for preschoolers. Begin with Draw, a good motivator. Your child uses the keyboard to create colorful pictures (assuming you've got a color monitor). To change colors, the child presses the space bar.

Next is Numbers. A one-digit number appears on your screen, and the child locates it on the keyboard and types it in. Letters is a similar game, in which your child finds the letter on the keyboard matching the one displayed on the screen.

Count displays brightly colored blocks—Johnny finds the number on the keyboard corresponding to the number of shapes on the screen. The game Add reveals several blocks, the plus symbol and more blocks. How many? Count them up and type in the number. (The game Subtract is basically the same format.)

One popular game is Names. You'll type in your child's name, then the computer will ask the child to type it in. When the child does, each letter is displayed one at a time, in huge graphics that cover the entire screen. A real ego-booster.

"KENNEDY APPROACH..."

NEW SPEAKING SIMULATION
See and Hear All the Action!

"...This is UA 236...Emergency Fuel...one zero minutes!!!..."

Commodore-64 Screen Picture

Voice Communications coming in from all directions!! 20 Aircraft in the pattern, and now you have an EMERGENCY!! As "Kennedy Approach", YOU are in charge!! It's your job to get all these aircraft and passengers on the ground or on the way safely!! You'll really be glad when this shift is over!!

"Kennedy Approach" is the first "Speaking Simulation" that allows you not only to control the exciting action in the skies around some of our busiest airports but also to hear and communicate with the simulation aircraft using computer generated speech. Fast action, great aircraft control simulation, and outstanding graphics and sound make "Kennedy Approach" a must addition to your simulation software library!!

SEE YOUR LOCAL RETAILER for "Kennedy Approach". Available for Commodore-64 and Atari computers for suggested retail of only $34.95. For more information on all MicroProse products call or write.

Experience the reality of these other great simulations from MicroProse:

Challenging and Exciting Air Combat from the Modern Electronic Cockpit!!

As close to the Real Thrill of Flying as You Can Handle!!

YOU are in Command — D-Day to the Battle of the Bulge!!

MicroProse Software

The Action is Simulated — the Excitement is REAL!!

120 Lakefront Drive
Hunt Valley, MD 21030
301-667-1151

Circle 68 on Reader Service card.

Commodore-64 and Atari are registered trademarks of Commodore Business Machines, Inc. and Atari Inc. respectively.

Circle 179 on Reader Service card.

COMMODORE ACCESSORIES

VOICE SYNTHESIZER FOR APPLE AND COMMODORE

Great Educating Tool!

JE520AP

JE520CM

• Over 250 word vocabulary-affixes allow the formation of more than 500 words • Built-in amplifier, speaker, volume control, and audio jack • Recreates a clear, natural male voice • Plug-in user ready with documentation and sample software • Case size: 7¼"L x 3¼"W x 1⅜"H

Applications: • Security Warning • Telecommunication • Teaching • Handicap Aid • Instrumentation • Games

Part No.	Description	Price
JE520CM	For Comm. 64 & VIC-20.	$114.95
JE520AP	For Apple II, II+ and IIe.	$149.95

Game Paddles

JSP Atari Paddles. $2.95

GSP Commodore Paddles. $4.95

(Atari Paddles modified for VIC-20 & C-64)

RS232 ADAPTER FOR VIC-20 AND COMMODORE 64

RS232 Interface

The JE232CM allows connection of standard serial RS232 printers, modems, etc. to your VIC-20 and C-64. A 4-pole switch allows the inversion of the 4 control lines. Complete installation and operation instructions included.

• Plugs into User Port • Provides Standard RS232 signal levels • Uses 6 signals (Transmit, Receive, Clear to Send, Request to Send, Data Terminal Ready, Data Set Ready).

JE232CM. $39.95

PROTECT YOURSELF...

DATASHIELD®

Surge Protector

Eliminates voltage spikes and EMI-RFI noise before it can damage your equipment or cause data loss. 6-mo. warranty. Power dissipation (100 microseconds): 2,000,000 watts

Part No.	Description	Price
MODEL 75	4 Sockets, On/Off Switch.	$49.95
MODEL 85	6 Sockets, Super Filters, On/Off Switch.	$59.95
MODEL 100	6 Sockets, Super Filters, Low Voltage Alarm.	$69.95
MODEL 110AMS	6 Sockets, Super Filters, Auto. Master Switch.	$99.95

$10.00 Minimum Order — U.S. Funds Only
California Residents Add 6½% Sales Tax
Shipping — Add 5% plus $1.50 Insurance
Send S.A.S.E. for Monthly Sales Flyer!

Mail Order Electronics - Worldwide
Jameco ELECTRONICS

Spec Sheets — 30¢ each
Send $1.00 Postage for your *FREE 1985 JAMECO CATALOG*
Prices Subject to Change

MasterCard VISA

1355 SHOREWAY ROAD, BELMONT, CA 94002
Phone Orders Welcome (415) 592-8097 Telex: 176043

4/85

Circle 89 on Reader Service car

Required Reading for your COMMODORE 64

THE GRAPHICS BOOK FOR THE COMMODORE
SCIENCE & ENGINEERING FOR THE COMMODORE
IDEAS FOR USE ON YOUR COMMODORE
THE ADVANCED MACHINE LANGUAGE BOOK FOR THE COMMODORE 64
ADVENTURE GAMEWRITERS HANDBOOK FOR COMMODORE 64

TRICKS & TIPS Treasury of programming techniques. Advanced graphics, easy input, enhanced BASIC CP/M, character sets, more. **275 pages $19.95**

GRAPHICS BOOK Basic to advanced, best reference available. Sprite animation, Hires, Multicolor, lightpen, IRQ, 3D graphics. **350 pages $19.95**

SCIENCE & ENGINEERING Discuss variable types, computational accuracy, sort algorithms, more. Topics from chemistry, physics, biology, astronomy, electronics. **250 pages $19.95**

ANATOMY OF C-64 Insider's guide to the '64 internals. Graphics, sound, I/O, kernal, more. Complete commented ROM listings. **300 pages $19.95**

PEEKS & POKES Programming quickies that will simply amaze you. This guide is packed full of techniques for the BASIC programmer. **180 pages $14.95**

ANATOMY OF 1541 DISK DRIVE Bestselling handbook on floppy disk. Explains disk files with examples and utilities. Includes complete commented 1541 ROM listings. **320 pages $19.95**

Other titles available. Phone for name of nearest dealer Phone:(616) 332-4154

Postage & handling $4.00 ($8.00 foreign). Money order, checks, VISA, MC, AMEX. Michigan residents (incl. 4% sales tax).

CANADA: Book Center, Montreal (514) 332-4154

AMEX MasterCard VISA

You Can Count On Abacus Software

P.O. Box 7211 Grand Rapids, MI 49510 · Telex 709-101 · Phone 616/241-5510

Computer Tutor

The last game is Compare Shapes. Four shapes are shown, three are the same and one is different. Each shape has a number underneath, and your child's job is to find the different shape and type in that number.

Early Games for Young Children may sound simplistic, but just remember: What entertains and teaches a four-year-old is vastly different from what amuses or educates a 30-year-old adult. (Usually.) *(Springboard Software, Inc., 7807 Creekridge Circle, Minneapolis, MN 55435, 800-328-1223, $29.95, cassette; unexpanded version with version for 16K memory expander on other side of tape.)*

Climb Time

Climb Time from Integrity Software helps children learn or sharpen their addition and subtraction skills. A problem is depicted, let's say it's 2+3. Two little blue men then run to stand next to the 2, and three little red men run to stand next to the 3 (with sound accompanying them as they run). As a result, your child receives both pictorial and numerical symbols of what 2 and 3 really mean.

To change to subtraction, press the f1 key. The men still run over to the problem, but subtracted ones disappear.

On the left-hand side of the screen is a ladder with a man at the bottom. If the child answers correctly, the man climbs up a rung. If the child answers incorrectly, he or she will get the same problem, complete with running men, until a correct answer is given. Once the man climbs to the top of his ladder, he'll jump up and down to display his joy, then move over to the top of the screen. The child then gets another little man and starts all over again. There's also a slow-moving turtle on the upper screen. You'll have until he reaches the right side to answer the problems that push your men up that ladder of success. *(Integrity Software, PO Box 29, Bristol, VT 05443; $17.95, cassette.)*

In the Chips

A far more complex program for your teenagers (and you, too!) is In the Chips by Creative Software. It's a challenging business game in which you try to make money by selling software.

You pick out five programs to sell,



In the black with Creative Software's In the Chips.

how many units of each to make, how much money to spend on advertising and what price to charge for your product. Then you go home and find out how much money you've made! (Or, alas, lost!) This program stimulates that gray matter, which controls logical decision making.

You'll begin the game by deciding whether to play against the computer or a human opponent. (I recommend you learn on another person.) Each of you begins with $100,000, which you'll see on your company's financial statement. (No, you don't need an MBA to understand it.)

Next, you'll see your little man walking down a sidewalk, and you'll move him with your joystick to the appropriate buildings. You select which programs to sell, from Astro to Zork, by moving him to research and development. Manufacturing is next, so you'll scoot him on over to that building. (As you manufacture, you'll see a block display of each product in your warehouse.) How much should you charge for each product (with a minimum of $10 each)? What about advertising—how much should you spend? (I liked the hand that appeared as my man paid for his advertising.)

At the top of your screen is displayed your remaining cash, and after each expenditure, you can watch your working capital decrease. Your basic goal: Make a profit. (No easy task.)

After the second quarter, you can compare how you did at various prices—maybe when you dropped the price of Zork from $16 to $14, your sales skyrocketed. Watch out: Your competitor may suddenly build up his inventory and slash prices!

In the Chips is an engrossing game that teaches you about profits and losses and how a business basically operates. You must find that optimal balance between inventory, prices and advertising to succeed and, thus, win this game. *(Creative Software, 230 East Caribbean Drive, Sunnyvale, CA 94089; $29.95, cartridge.)* R

Christine Adamec (1921 Ohio St. NE, Palm Bay, FL 32907) is a professional writer, with articles in McCall's, Graduating Engineer, In Business *and* RUN *to her credit. As the mother of two children, ages five and six—who frequently serve as her guinea pigs for testing—she has become particularly intrigued with the subject of children's software. She eagerly invites readers to send in their comments on this column's content.*

Circle 63 on Reader Service card.

DI-SECTOR Version 2.0

EVERYTHING YOU EVER WANTED IN A DISK UTILITY . . . AND MORE!!
FOR THE COMMODORE 64*

★ Fully automatic back-up of almost any protected disk.
★ Copy files [PRG, SEQ, RND] with full screen editing.
★ Three minute back-up of standard disks [even many protected disks].
★ Format a disk in ten seconds. ★ View and alter sector headers.
★ Remove errors from any track/sector.
★ Edit sectors in HEX, ASCII — even assembler.
★ Create errors on any track/sector [20, 21, 22, 23, 27, 29] instantly.
★ Drive/64 MON, even lets you write programs inside your 1541.
★ All features are fully documented and easy to use.
★ None of our copy routines ever makes the drive head "kick."

Yes, you get all of this on one disk for this low price!——$39.95

. . . Continuing Customer Support and Update Policy . . .

*Commodore 64 is a registered trademark of Commodore Business Machines

. . . WRITE OR PHONE . . .
STARPOINT SOFTWARE
Star Route 10 Gazelle, CA 96034 [916] 435-2371

All orders add $3.00 shipping/handling. California residents add 6% sales tax. COD orders add an add'l $4.00 shipping. Check, Money Order, VISA, and Mastercard accepted.

Commodore Sundial

By HOWARD WITT

Telling time by the sun is an unusual application, but one ideally suited for your Commodore. This article tells you how to make a sundial, and the accompanying program gives you the necessary data.

One of my childhood memories is of a large sundial on my neighbor's lawn. The sundial, mounted on a pedestal, was made of brass, with a traditional, round clock-like face and a slender pointer. As the sun passed overhead, the shadow of the pointer moved across the face, indicating the time of day.

While beautifully decorated and of fine workmanship, the sundial had one flaw. It kept very poor time. It was not uncommon to find a difference of 30 minutes between sundial time and clock time. I remember being disturbed by this. How could such a finely crafted instrument be so wrong?

When I grew up, I eventually learned why the sundial performed the way it did. As the seasons change, the sun passes higher or lower in the sky, affecting the position of the pointer's shadow. Also, since the earth does not orbit the sun in a perfect circle, the length of a solar day varies throughout the year.

To indicate time correctly, a sundial must accommodate these phenomena. In addition, it must be specifically prepared for the exact location where it is to be used.

Would it be possible to design an improved sundial, one that would maintain the charm and simplicity of the traditional style and still keep good time? Theoretically, this was possible. The large number of calculations required, however, discouraged pursuit of the idea.

When I bought my VIC-20, my interest in the sundial rekindled. With its standard 5K memory and Basic interpreter, the VIC-20 proved equal to



Figure 1. *Sample sundial pattern, from data generated by the Solar program.*

contending with the two fundamental problems of sundial design: keeping track of the sun's apparent position throughout the year and computing the length and direction of the pointer's shadow.

The Solar program was prepared to handle all the necessary calculations and to serve as an aid to designing an improved sundial, which is, after all, a solar clock. The Solar program uses straightforward, standard Basic and will run on the C-64, Plus/4 and C-16 as well as the VIC-20 with or without expansion.

How It Works

The program (see Listing 1) works in the following way. Your sundial is a flat surface placed horizontally on the ground, with a single pointer extending straight up. You specify a time of day, a month and the sundial's exact geographic location. (The Solar program assumes north latitudes and west longitudes.)

The computer then tells you whether the sun is above the horizon and, if so, where on the flat surface the tip of the pointer's shadow will appear. By running the program for various combinations of times and months, then plotting the computed shadow locations on the flat surface, you can prepare an accurate sundial pattern.

Following is a sample run of the Solar program. All input, which you must provide for the computer, is underlined.

```
RUN
LATITUDE (DEG,MIN)      ? 41,30
LONGITUDE (DEG,MIN)     ? 73,00
G.M.T. (HOUR,MIN)       ? 14,30
MONTH (1 TO 12)         ? 8

SHADOW APPEARS,
POSITION OF END IS:
WEST          .742973688
NORTH         .348427809
```

The latitude and longitude indicate the location of the sundial. The above coordinates are for my home in Connecticut. You can find the latitude and longitude of any location by referring to an atlas or road map.

"G.M.T." stands for Greenwich Mean Time, the international time standard. Twenty-four hour notation is used, hence 14:30 is 2:30 PM in Greenwich, England. Converting to local time, this is 9:30 AM Eastern Standard Time, or 10:30 AM Eastern Daylight Time.

When making a sundial, you must use the correct time zone and, for most parts of the country, select either Standard Time or Daylight Saving Time. Conversion from G.M.T. to local time is done as follows.

Eastern Daylight Time—subtract 4 hours
Eastern Standard Time—subtract 5 hours
Central Daylight Time—subtract 5 hours
Central Standard Time—subtract 6 hours
Mountain Daylight Time—subtract 6 hours
Mountain Standard Time—subtract 7 hours
Pacific Daylight Time—subtract 7 hours
Pacific Standard Time—subtract 8 hours

The Solar program assumes that a year comprises 12 months of equal duration, which is sufficiently true for the intended purpose. Specifying month number 8 means the program will use August 1, or thereabouts.

C-64; any VIC-20; Plus/4; C-16
Disk or tape

Listing 1. *The Solar program.*

```
5 PRINT"{SHFT CLR}{3 CRSR DNs}"
1Ø INPUT "LATITUDE (DEG,MIN){2 SPACEs}";D,M
2Ø LET T=(D+M/6Ø)*.Ø174532
3Ø LET A=T
4Ø INPUT "LONGITUDE (DEG,MIN) ";D,M
5Ø LET P=(D+M/6Ø)*.Ø174532
6Ø LET B=P
7Ø GOSUB 42Ø
8Ø LET U=X
9Ø LET V=Y
1ØØ LET W=Z
11Ø INPUT "G.M.T. (HOUR,MIN){3 SPACEs}";H,M
12Ø LET G=H+M/6Ø
13Ø INPUT "MONTH (1 TO 12){5 SPACEs}";M
14Ø LET M=(M-1)*.5235987
15Ø GOSUB 46Ø
16Ø GOSUB 42Ø
17Ø LET U=U-X
18Ø LET V=V-Y
19Ø LET W=W-Z
2ØØ LET D=SQR(U*U+V*V+W*W)/2
21Ø IF D<1/SQR(2) THEN GOTO 25Ø
22Ø PRINT
23Ø PRINT "NO SHADOW APPEARS"
24Ø GOTO 4ØØ
25Ø LET L=1/TAN(1.57Ø8-2*ATN(D/SQR(1-D*D)))
26Ø GOSUB 53Ø
27Ø LET C=Z/SQR(Y*Y+Z*Z)
28Ø LET I=SGN(Y)
29Ø LET P=B
3ØØ GOSUB 42Ø
31Ø GOSUB 53Ø
32Ø LET C=Z*C/SQR(Y*Y+Z*Z)
33Ø LET S=I*SQR(1-C*C)
34Ø PRINT
35Ø PRINT "SHADOW APPEARS,":PRINT"POSITION
   OF END IS:"
36Ø IF S>Ø THEN PRINT " EAST{3 SPACEs}";L*S
37Ø IF S<Ø THEN PRINT " WEST{3 SPACEs}";-L*
   S
38Ø IF C>Ø THEN PRINT " NORTH{2 SPACEs}";L*
   C
39Ø IF C<Ø THEN PRINT " SOUTH{2 SPACEs}";-L
   *C
4ØØ PRINT
41Ø GOTO 1Ø
42Ø LET X=COS(T)*COS(P)
43Ø LET Y=COS(T)*SIN(P)
44Ø LET Z=SIN(T)
45Ø RETURN
46Ø LET T=.ØØ663
47Ø LET P=(G-12)*.2617993
48Ø LET T=T-.4ØØØ3*COS(M)+.Ø6929*SIN(M)
49Ø LET P=P+.ØØ2Ø9*COS(M)-.Ø3211*SIN(M)
5ØØ LET T=T-.ØØ663*COS(2*M)+.ØØØ7*SIN(2*M)
51Ø LET P=P-.Ø1431*COS(2*M)-.Ø4189*SIN(2*M)
52Ø RETURN
53Ø LET Z=Z*COS(A)-(X*COS(B)+Y*SIN(B))*SIN(
   A)
54Ø LET Y=Y*COS(B)-X*SIN(B)
55Ø RETURN
56Ø END
```

Specifying month number 1 implies January 1; month number 2, February 1; and so on.

The output provided by the Solar program in the example above shows that the sun is indeed visible at the specified time and location. It also shows that if the pointer is a slender post extending one foot, for example, straight up from the flat face of the sundial, the tip of the shadow cast by the pointer would appear .74 feet west and .35 feet north of its base.

Other Uses

The Solar program could be run for other times and for other months to produce a pattern of marks showing the position of the pointer's shadow throughout the year. The sample sundial (Figure 1) is such a pattern, with lines connecting the same months and hours.

Note the arrow showing the position of the pointer's base, and the scale indicating its height. Note also the four directions: north, south, east and west.

To test the pattern, I placed the sundial outside on a flat, horizontal surface, then turned it around until the north arrow pointed to true north. (Since I used a magnetic compass to align the pattern, the appropriate variation was applied.) I made a pointer of the correct height from a toothpick stuck in a button. I positioned it over the base, pointing straight up. Then I waited to see what would happen.

It was a very satisfying experience to watch the thin shadow of the pointer move slowly across the sundial during the day, showing the correct time in nearly perfect synchronization with my wristwatch.

Ultimately, you could enlarge the sundial pattern and transfer it to a surface of metal, wood or stone, then mount it permanently on your lawn. There are endless possibilities for creativity. Why not turn the lawn north of your house into a giant sundial, using the top of the TV antenna as a pointer?

The sample sundial, of course, works only in the vicinity of my hometown. For other locations, the Solar program must be run to prepare different patterns. It is especially interesting to consider locations north of the arctic circle or near the equator.

If your computer is equipped with an automatic plotting device or high-resolution graphics, you may want to expand the program to produce complete patterns automatically.

You can also use the sundial as a practical application—as an aid in the design of energy-efficient homes or to answer questions such as, "How should an overhanging roof be placed so it admits light in the winter, but provides shade in the summer?"

Use your imagination and enjoy the program. R

Address all author correspondence to Howard Witt, 199 Hoadley St., Naugatuck, CT 06770.

Circle 189 on Reader Service card.

Slik Load

Slik Load is a Kartridge for the C-64.
Slik Load is the most reliable, effective and thought out Kartridge of it's kind.
The options include:

- **5 times faster load**
- **Eliminates drive rattle when errors are encountered.**
- **Old and un-new Will restore a basic program**
- **Status key will give you information on device number, bytes free and status of the drive.**
- **Silk Load is also fully compatible with the 1541 Super Rom**



$19.95

DMS-Errors 20, 21, 22, 23, 27 & 29
Format Single Tracks
Read Disk Errors
½ Track Reader-read and select ½ track
½ Track Formatter-Format a disk with ½ tracks. This is where the next protection schemes are coming from.
Drive Mon-Disk Drive assembler/disassembler. For your 1541.
The Doc-Disk Doctor that reads code under errors.
Sync Maker-Place a sync mark on **any** track out to 41. Also used for protection.
Sync Reader-Check for Sync bits on **any** track out to 41.
Change Drive No.-Changes drive number (7-30).
Disk Logger-Finds starting track sector; start and end addresses.
Disk Match-Compare any two diskettes. Byte for byte.
New Wedge-Easier to use DOS wedge.
ID Check-Check ID's on **any** track.
Unscratch-Restore a scratched file.
View-BAM-Visual display of the free and used sectors on a diskette.
Read/Write Test-1541 performance test.
Repair a Track-Repair a track with checksum errors. Reads code under errors and restores track.
Fast Format-Format a disk in just 10 seconds (with verify!).

This is the only utility of its kind. It even has a 3 min. copy on it.

WAR GAMES AUTODIALER

1-Auto Dial will automatically dial a set of numbers you choose.
2-Review Numbers will review numbers that were answered by a computer.
3-Save Numbers will save numbers where a computer answered.
4-Hardcopy of Numbers will print out list of numbers where a computer answered.
5-LOAD Numbers will load in numbers to continue where it left off.
6-Continue will pick up dialing where it was interrupted.

$29.95

KARTRIDGE KRACKER

NOW you can own this unique and powerful tool which will allow you to dump the contents of 8K and 16K cartridges onto disk! But what's really great is that you can also RUN the cartridges programs without plugging in the cartridge! the KRACKER gets YOU INSIDE the cartridge! Put all your favorites on disk and get rid of the clutter. This package provides your with the software and hardware needed to get started. Program on disk included. (Some cartridges require use of external RAM not included)

$44.95

SOFTWARE PROTECTION HANDBOOK

3rd Edition

THIRD EDITION! NOW AVAILABLE!

If you're **tired** of being harassed by **protected software** and too many **copy** programs, then this is the book for you! This 224 page manual covers the gambit from legalities to protection methods to step-by-step back up procedures. Now you can learn both how to **protect and unprotect** software! The techniques covered include copying cartridges to tape or disk, tape protection, and disk protection. Disk protection covers error no.'s 20, 21, 22, 23, 27 and 29 **plus** single track formatting, header modification, header swapping, half track reading and writing, reading and writing modified bit densities, formatting illegal tracks/sectors, sync writing and **more!** The Third edition **explains,** tells how to **detect** and how to **write** them with included software. Eleven useful utilities and many protection listings! Our disk analysis programs reveal the protection methods used on your originals. A diskette with all software is available for a minimum extra charge. This may not be the only book your should have for the C-64, but it is certainly **the one** book you should not be **without!**

C64 Book only	$19.95 US
Book & Disk of all programs	$29.95 US
Vic 20 book . . . Cart. & Tapes only	$9.95 US

THIS MANUAL DOES NOT CONDONE PIRACY

*SHIPPING: $2.00

The Original Book of Facts

UNLOCK THE MYSTERIES OF THE COMMODORE

—Simple Instructions
—Easy step-by-step examples
—Tricks you can do your first day
—Introduction to color, sound and much more
—Includes a routine to protest your own programs
—NO MATTER what your experience, the Original Book of Facts is for everyone!

$6.99

The Advanced Book of Facts

EXPLORING YOUR COMMODORE

—How to use a machine language monitor
—Tips on how to unprotect your software
—Advanced protection for your own programs
—Full size reference charts
—How to design your own menus and more...

$6.99

Bulletin Board

Set up and operate your own bulletin board with one or two disk drives. This one has all the features and you can customize it easily yourself.

1-RUN MEGASOFT-BBS
2-CREATE MEGA FILES
3-ADD TO SYSOP'S CORNER
4-NEW SYSOP'S CORNER
5-READ MESSAGES
6-SCRATCH MESSAGE
7-CYCLE MESSAGES
8-READ SYSOP MESSAGES
9—WRITE OPENING MESSAGE
10-READ LOG
11-CYCLE LOG
12-READ DOWNLOAD FILE
13-SCRATCH DOWNLOAD FILE
14-ADD TO OTHER SYSTEMS
15-CREATE OTHER SYSTEMS



$59.95

BBS

- Leveled Access
- Private Message Base
- Up to 300 Passwords
- Expert Mode
- Open Chalk Board for Highest Level Access

Enclose Cashiers Check, Money Order, or Personal Check. Allow 14 days for delivery. 2 to 7 days for phone orders. Canada orders must be in U S Dollars. VISA — MASTER CARD — C O D

Programs for C-64 $2.00 S & H on all orders

Software Submissions Invited.

MegaSoft Limited

P.O. Box 1080, Battle Ground, Washington 98604
Phone (206) 687-5116 • BBS 687-5205 After Hours Computer to Computer

Circle 189 on Reader Service card.

A Survival Guide to the 1541 Disk Drive

This is a 40 + page book and comes complete with all commands and examples on how to use them. **$6.99**

The Complete Book on Telecommunications **$6.99**

A 40 + page book that will help you get started with your Modem. How to use it and how to access a BBS. Compuserve, Dow Jones as well as up and down load.

1541 Super ROM **$39.95**



- *Fast Save Load Verify*
- *Fast Scratch and Validate*
- *10 Second Format with Verify*
- *No more Drive Head rattling during Format or Error Reading*
- *also Save with Replace is Improved*
- *Two times faster, Eight times faster when used with Turbo 64 which is included*
- *1541 Super ROM is 100% Compatible*
- *Easily installed in Minutes*

APALLO COPIES IT ALL

APALLO Does it All. This program is the latest generation of copy programs. It will do everything the $39.00 and $49.00 programs will do and **more.** It Copies **ALL** drive errors, bad tracks and sectors, non-standard format, bad syncs, and half tracks. We feel this is the best program of its kind available...

$29.95

MSD Sure Copy

*At last a complete utility package for the MSD Dual Drive. **This is the first MSD utility program that does it all.** The main menu options include:*

- *Copy Protected Disk*
- *Copy Files*
- *Format a Disk*
- *Change Disk Name*
- *Quit*
- *Copy Unprotected Disk*
- *Scratch a File*
- *Rename a File*
- *View Directory*

$39.95

***Sure Copy** will put all errors automatically on disk: 20, 21, 22, 23, 27 and 29's.*

D-CODER

- Translates any machine language program into easy-to-read English descriptions with complete explanations of each command!
- Makes complete notations of all important memory locations accessed by the program! (SID, VIC, MOS, KERNAL, etc.)
- Gives you three ways of accessing programs:
  1) **Will read and list programs from DISK**
  2) **Will read and list programs from MEMORY!**
  3) **Direct user input** (from magazines, etc.)
- Can be used to locate and examine any machine language program's protection routines!
- Can be used to easily break apart machine language programs for study and examination!
- Printer option for complete hard copy listings!

$19.95

You no longer need to be an EGGHEAD to read Machine Language.

N-CODER **$19.95**

the machine language manipulator...

The perfect companion program to D-CODER!

Allows you to easily make changes in machine language programs... right on the disk!

- *Rewrite ability allows code to be altered and then rewritten directly to the disk!*
- *Features sector-by-sector scrolling assembly language display of machine language programs!*
- *Notation of ASCII text equibalents for easy spotting of embedded text strings!*
- *Handy reference display of all assembly language commands and their ML numerical equivelents!*
- *Byte splitter for easy splitting of decimal addresses into low byte-high byte format!*

Super Loader

Super Loader is a Kartridge that plugs into your expansion port, that allows the computor, on power up start the disk drive and load the first preselected program on the disk.

- Change colors
- Load wedge
- Works with more drive
- Takes up no memory
- Reset switch included



Only **$29.95**

Enclose Cashiers Check, Money Order, or Personal Check. Allow 14 days for delivery. 2 to 7 days for phone orders. Canada orders must be in U.S. Dollars. VISA — MASTER CARD — C.O.D.

Programs for C-64 $2.00 S & H on all orders

Software Submissions Invited.

MegaSoft Limited

P.O. Box 1080, Battle Ground, Washington 98604

Phone (206) 687-5116 • BBS 687-5205 After Hours Computer to Computer

Charting Your Future

Biorhythms can tell you a lot about your state of being. This program lets you chart them.

By ALLAN E. WHEELER



DAN COLLINS

Biorhythms are rhythmic fluctuations in a physical organism that are related to and indicative of various biological processes.

Biorhythms are based on 23-, 28- and 33-day cycles that start with 0 at birth and initially proceed in a positive direction. This program calculates your daily position on each of the biorhythm curves for any desired month and year.

Vertical bar-graph representations of the physical, emotional and intellectual levels for each day are printed to the screen.

The lowest levels, considered to be the ebb-tide rest and recovery phase, are indicated by purple bars projecting to the left of the screen. The high levels are the full-tide active phases of the biorhythms and are indicated by blue bars projecting to the right. The high and low levels are also known as the recharge and discharge phases.

Days when the transition between these periods occur are considered to be significant as critical periods of instability and times of abnormal effects of the biorhythm. Those days are indicated by printing the day, or adjacent days if the event occurs close to the midpoint, in purple.

Periods where two or three biorhythms are at very high levels during the same day are considered by some to be days of good fortune and luck. Such days are flagged by a blue star for two high levels or a yellow star for three high levels occurring in the same day. The stars appear in the day-of-the-month column.

Interesting periods to look at are your month and year of birth, 58 years, two months and approximately one week (21,252 days) from your birth and, of course, biorhythms for the present and future.

No claim is made for the validity of biorhythms. There are those who claim that they are meaningless; others use them to direct their lives. I found them to be an interesting programming exercise.

Using the Program

The input screen will ask you to enter your birthdate, the year you are interested in and the starting month for that year.

Entries are user friendly. You may enter the year as 1983 or simply 83. Months may be entered numerically or spelled out with at least the first three letters. Illogical days of the month, such as February 29th of a non-leap year, won't be accepted by the Input routine.

RUN It Right

C-64, VIC-20
Datassette or disk drive

TAKE A BREAK!

For Commodore 64



WITH NIGHT MISSION PINBALL

You deserve the best. You've earned it. Now reward yourself with a session of Night Mission PINBALL, the most realistic and challenging arcade simulation ever conceived! ■ Stunning graphics and dazzling sound effects put Night Mission PINBALL in a class by itself. Game features: multi-ball and multi-player capabilities, ten different professionally designed levels of play, and an editor that lets you create *your own* custom modes. ■ So take a break with Night Mission PINBALL from SubLOGIC. Winner of *Electronic Games* magazine's 1983 Arcade Award for Best Computer Audio/Visual Effects.

See your dealer . . .

or write or call for more information. For direct orders please add $1.50 for shipping and specify UPS or first class mail delivery. Illinois residents add 5% sales tax. American Express, Diner's Club, MasterCard, and Visa accepted.

Order Line: 800/637-4983

subLOGIC Corporation
713 Edgebrook Drive
Champaign IL 61820
(217) 359-8482 Telex: 206995

Circle 40 on Reader Service card.



10–110.	Bar graph variable assignment	490–570.	Calculate biorhythms and analyze characteristics
120–140.	Initialization	580–660.	Print them without scrolling
150–320.	Input routines	670–710.	Proceed to the next month/year and do it again
330–390.	Count days back to January of birth year	720–740.	Heading subroutine
400–430.	Find the number of days to January of current year	750–790.	Footing and Prompt subroutine
440–470.	Find number of days from January current year to desired month	800–830.	Error-checking subroutine
480.	Go to Heading subroutine	840–860.	Data

Table 1. *Program line descriptions.*

I tried to make the input routines as crash-proof as possible. An error-checking subroutine will check month and day entries against Data statements for correctness. Year entries are accepted only if they are numerical and if the current year entry is the year of your birth or later.

If an unacceptable error is made in any of these entries, the Input statement will be repeated on the same line to avoid scrolling the input screen.

The vertical bar graph has a resolution of 16 levels to the left and 16 to the right. The method I used could be applied to any program suitable for this type of graph. Scale your data from 0 to 15 for full to minimum deflection to the left of the screen, and from 16 to 31 for right-hand deflection; then enter PRINT A$(N), where N is your scaled data. Include program lines 10–110 in your program initialization.

You can experiment with these bars by temporarily adding the following lines to the Biorhythm Chart program:

```
115 PRINT"(CLR)":FORN = 0TO15:
    PRINTSPC(7)A$(N):NEXT:
    PRINT"(HOME)"
116 FORN = 16TO31:PRINTSPC(14)A$(N):
    NEXT:STOP
```

To save memory and enable this program to run on an unexpanded VIC, REM statements were not included in the program. R

Address all author correspondence to Allan E. Wheeler, 1119 Niblick Road, Paso Robles, CA 93446.

Listing 1. *Biorhythm Chart program for the C-64.*

```
5 REM C64 BIORHYTHMS CHART BY A.E.WHEELER
1Ø DIMA$(32):RV$=CHR$(18):BK$=CHR$(157):RO$
   =CHR$(146)
2Ø A$(13)=CHR$(182):A$(14)=CHR$(17Ø):A$(15)
   =CHR$(167):A$(16)=CHR$(165)
3Ø A$(17)=CHR$(18Ø):A$(18)=CHR$(181):A$(19)
   =CHR$(161)
4Ø A$(8)=RV$+CHR$(16Ø):A$(9)=RV$+A$(16):A$(
   1Ø)=RV$+A$(17):A$(11)=RV$+A$(18)
5Ø A$(12)=RV$+A$(19):A$(Ø)=BK$+A$(8)+A$(8):
   A$(1)=BK$+A$(9)+A$(8)
6Ø A$(2)=BK$+A$(1Ø)+A$(8):A$(3)=BK$+A$(11)+
   A$(8):A$(4)=BK$+A$(12)+A$(8)
7Ø A$(5)=BK$+A$(13)+A$(8):A$(6)=BK$+A$(14)+
   A$(8):A$(7)=BK$+A$(15)+A$(8)
8Ø A$(2Ø)=RV$+A$(13):A$(21)=RV$+A$(14):A$(2
   2)=RV$+A$(15):A$(23)=A$(8)
9Ø A$(24)=A$(8)+RO$+A$(16):A$(25)=A$(8)+RO$
   +A$(17):A$(26)=A$(8)+RO$+A$(18)
1ØØ A$(27)=A$(8)+RO$+A$(19):A$(28)=A$(8)+A$
    (13):A$(29)=A$(8)+A$(14)
11Ø A$(3Ø)=A$(8)+A$(15):A$(31)=A$(8)+A$(8):
   GC$=RV$+CHR$(144)+CHR$(96)+CHR$(146)
12Ø DEFFNA(X)=INT(((SIN((X-INT(X))*6.2832)+
   1.Ø5))*15.2)
13Ø TL$="{1Ø SPACEs}{CTRL 9}{CTRL 1} DAY PH
   YS EMOT INTL {CTRL Ø}"
135 BM$="{1Ø SPACEs}{CTRL 9}{CTRL 1}{5 SPAC
   Es}-{2 SPACEs}+ -{2 SPACEs}+ -{2 SPACEs
   }+ {CTRL Ø}"
137 TD$="{SHFT CLR}{CTRL 9}{CTRL 7}{4 SPACE
   s}BIORHYTHMS CHART{2 SPACEs}{CTRL Ø}{CT
   RL 1}"
14Ø CB$="{2 SPACEs}{CTRL 7}":CP$=" {CTRL 3}
   ":POKE53281,1:POKE5328Ø,6
145 PRINT"{SHFT CLR}{CTRL 9}{CTRL 7}{12 SPA
   CEs}BIORHYTHMS CHART{12 SPACEs}{CTRL 1}
   {CTRL Ø}"
15Ø INPUT"{COMD 4}{9 SPACEs}YEAR OF BIRTH";
   YB$:YB=VAL(YB$)
155 IFYB=ØTHENPRINT"{2 CRSR UPs}";:GOTO15Ø
16Ø IFYB<1ØØTHENYB=YB+19ØØ
17Ø YR=YB:YB$=RIGHT$(STR$(YB),4)
18Ø INPUT"{CRSR DN}{9 SPACEs}MONTH OF BIRTH
   ";MB$:B$=MB$:MO=VAL(MB$):GOSUB8ØØ:MB$=A
   $:MB=C
```

Listing 1 continued.




```
19Ø IFLB=1THEN18Ø
2ØØ INPUT"{CRSR DN}{9 SPACEs}DAY OF BIRTH";
    DB$:DB=VAL(DB$):B$=MB$:GOSUB81Ø:DB$=DB$
    +","
21Ø IFDB<1ØTHENSP$=" "
22Ø IFDB=29ANDMB=2ANDINT(YB/4)=YB/4THEN24Ø
23Ø IFDB>BORDB=ØTHENPRINT"{2 CRSR UPs}";:GO
    TO2ØØ
24Ø INPUT"{CRSR DN}{9 SPACEs}CURRENT YEAR";
    YC$:YC=VAL(YC$):IFYC>ØANDYC<1ØØTHENYC=Y
    C+19ØØ
25Ø IFYC=ØORYC<YBTHENPRINT"{2 CRSR UPs}";:G
    OTO24Ø
26Ø INPUT"{CRSR DN}{9 SPACEs}START AT MONTH
    ";MW$:B$=MW$:MO=VAL(MW$):GOSUB8ØØ:MW$=A
    $:MW=C
27Ø IFLB=1THEN26Ø
28Ø PRINTTAB(16)"{CRSR DN}{CTRL 5}LEGEND:":
    PRINTTAB(1Ø)"{CRSR DN}{CTRL 9}{CTRL 7}{
    3 SPACEs}{CTRL Ø}{CTRL 5} = ACTIVE DAYS
    "
29Ø PRINTTAB(1Ø)"{CRSR DN}{CTRL 9}{CTRL 3}{
    3 SPACEs}{CTRL Ø}{CTRL 5} = RECOVERY DA
    YS"
295 PRINTTAB(5)"{CRSR DN}{CTRL 7}DBLE MAX{C
    TRL 5} = DOUBLE ACTIVE DAY"
3ØØ PRINTTAB(5)"{CTRL 8}{CRSR DN}TRIP MAX{C
    TRL 5} = TRIPLE ACTIVE DAY"
3Ø5 PRINTTAB(5)"{CTRL 3}{CRSR DN}CRITICAL{C
    TRL 5} = UNSTABLE DAY":PRINTTAB(14)"{CR
    SR DN}{COMD 4}HIT ANY KEY";
31Ø GETA$:IFA$=""THEN31Ø
32Ø PRINT"{CTRL 3}{CRSR UP}{31 SPACEs}WORKI
    NG{CTRL 1}{2 SPACEs}";
33Ø DA=DA-DB
34Ø MB=MB-1:IFMB=ØTHEN4ØØ
35Ø ONMBGOTO39Ø,36Ø,39Ø,38Ø,39Ø,38Ø,39Ø,39Ø
    ,38Ø,39Ø,38Ø,39Ø
36Ø DA=DA-28:IFINT(YR/4)=YR/4THENDA=DA-1
37Ø GOTO34Ø
38Ø DA=DA-3Ø:GOTO34Ø
39Ø DA=DA-31:GOTO34Ø
4ØØ IFYR=YCTHEN44Ø
41Ø DA=DA+365:IFINT(YR/4)=YR/4THENDA=DA+1
42Ø YR=YR+1:IFYR=YCTHEN44Ø
43Ø GOTO41Ø
44Ø READMO$:READDC:READC
45Ø IFMO$="FEB"ANDINT(YR/4)=YR/4THENDC=DC+1
46Ø IFMO$=LEFT$(MW$,3)THEN48Ø
47Ø DA=DA+DC:GOTO44Ø
48Ø GOSUB72Ø
49Ø FORN=1TODC:DA=DA+1
5ØØ BP=FNA(DA/23):BE=FNA(DA/28):BI=FNA(DA/3
    3)
51Ø CD$=""
515 IFBP>12ANDBP<19ORBE>12ANDBE<19ORBI>13AN
    DBI<18THENCD$=" {CTRL 3}CRITICAL{CTRL 1
    }"
52Ø PF$=CP$:IFBP>15THENPF$=CB$
53Ø IFBP>29THENFL=1
54Ø PE$=CP$:IFBE>15THENPE$=
55Ø IFBE>29THENFL=FL+1
56Ø PI$=CP$:IFBI>15THENPI$=CB$
57Ø IFBI>29THENFL=FL+1
58Ø FL$="{1Ø SPACEs}"
585 IFFL=2THENFL$="{CTRL 7} DBLE MAX {CTRL
    1}"
59Ø IFFL=3THENFL$="{CTRL 8} TRIP MAX {CTRL
    1}"
6ØØ FL=Ø:N$=MID$(STR$(N),2):L=2-LEN(N$)
61Ø PRINTFL$;GC$;" ";SPC(L)"{COMD 4}"N$;
62Ø PRINTTAB(14)GC$;PF$;A$(BP);TAB(19)GC$;
63Ø PRINTTAB(2Ø)PE$;A$(BE);TAB(24)GC$;
64Ø PRINTTAB(25)PI$;A$(BI);TAB(29)GC$;CD$
65Ø LC=LC+1:IFLC=16THENPRINTBM$:GOSUB75Ø:GO
    SUB72Ø
66Ø NEXT
67Ø PRINTBM$:GOSUB75Ø
68Ø READMO$
69Ø IFMO$="X"THENRESTORE:YR=YR+1:GOTO68Ø
7ØØ READDC:READC:MW$=MO$
71Ø GOTO45Ø
72Ø PRINTTD$"{CTRL 9}{CTRL 7}{7 SPACEs}"MO$
    ;YR"{CRSR LF}{3 SPACEs}{CTRL Ø}"
73Ø PRINTTAB(9)"{COMD 4}BIRTHDATE: "SP$;MB$
    " "DB$" ";YB$
74Ø PRINTTAB(9)"DAYS ALIVE: ";INT(DA+.5):PR
    INT"{CRSR DN}"TL$:RETURN
75Ø PRINT"{HOME}":FORAW=1TO22:PRINT:NEXT:PR
    INTTAB(9)"{COMD 4}{CTRL 9}C{CTRL Ø}ONTI
    NUE{6 SPACEs}{CTRL 9}N{CTRL Ø}EW DATA";
76Ø GETA$:IFA$=""THEN76Ø
77Ø IFA$="C"THENLC=Ø:RETURN
78Ø IFA$="N"THENRUN
79Ø GOTO76Ø
8ØØ LB=Ø:B$=LEFT$(B$,3)
```


SCREEN DUMPER 64™
COPYRIGHT 1984 BY MICRO-W DISTRIBUTING INC.

How would you like to have a copy of all of the text or graphics that appear on your monitor screen? Well SCREEN DUMPER 64™ may be what you are looking for. This program will transfer to your printer* a copy of what you see on your monitor screen including hi-resolution graphics, text, and multicolor sprite, etc. It even works with the KOALA PAD™. You can load this program into your computer in a hidden location so that it shouldn't interfere with your programs. This means that you can use your Commodore 64 normally and then call up this routine to dump what is on the screen. Colors are represented by 16 shades of gray for faithful reproductions.



ALL THIS FOR ONLY
$29.95

Call: (201) 838-9027 To Order

MasterCard VISA

Circle 172 on Reader Service card.

Micro-W. DISTRIBUTING, INC
1342 B Route 23
Butler, N.J. 07405

Listing 1 continued.

```
81Ø READA$,B,C:IFA$=B$ORC=MOTHENRESTORE:RET
    URN
82Ø IFC=-1THENRESTORE:PRINT"{2 CRSR UPs}";:
    LB=1:RETURN
83Ø GOTO81Ø
84Ø DATA"JAN",31,1,"FEB",28,2,"MAR",31,3,"A
    PR",3Ø,4,"MAY",31,5
85Ø DATA"JUN",3Ø,6,"JUL",31,7,"AUG",31,8,"S
    EP",3Ø,9,"OCT",31,1Ø
86Ø DATA"NOV",3Ø,11,"DEC",31,12,"X",Ø,-1
```

Listing 2. *Biorhythm Chart program for the VIC-20.*

```
1Ø DIMA$(32):RV$=CHR$(18):BK$=CHR$(157):RO$
   =CHR$(146)
2Ø A$(13)=CHR$(182):A$(14)=CHR$(17Ø):A$(15)
   =CHR$(167):A$(16)=CHR$(165)
3Ø A$(17)=CHR$(18Ø):A$(18)=CHR$(181):A$(19)
   =CHR$(161)
4Ø A$(8)=RV$+CHR$(16Ø):A$(9)=RV$+A$(16):A$(
   1Ø)=RV$+A$(17):A$(11)=RV$+A$(18)
5Ø A$(12)=RV$+A$(19):A$(Ø)=BK$+A$(8)+A$(8):
   A$(1)=BK$+A$(9)+A$(8)
6Ø A$(2)=BK$+A$(1Ø)+A$(8):A$(3)=BK$+A$(11)+
   A$(8):A$(4)=BK$+A$(12)+A$(8)
7Ø A$(5)=BK$+A$(13)+A$(8):A$(6)=BK$+A$(14)+
   A$(8):A$(7)=BK$+A$(15)+A$(8)
8Ø A$(2Ø)=RV$+A$(13):A$(21)=RV$+A$(14):A$(2
   2)=RV$+A$(15):A$(23)=A$(8)
9Ø A$(24)=A$(8)+RO$+A$(16):A$(25)=A$(8)+RO$
   +A$(17):A$(26)=A$(8)+RO$+A$(18)
1ØØ A$(27)=A$(8)+RO$+A$(19):A$(28)=A$(8)+A$
    (13):A$(29)=A$(8)+A$(14)
11Ø A$(3Ø)=A$(8)+A$(15):A$(31)=A$(8)+A$(8):
   GC$=RV$+CHR$(144)+CHR$(96)+CHR$(146)
12Ø DEFFNA(X)=INT((SIN((X-INT(X))*6.2832)+
   1.Ø5))*15.2)
13Ø TL$=" {CTRL 9}{CTRL 1} DAY PHYS EMOT IN
   TL {CTRL Ø}":BM$=" {CTRL 9}{CTRL 1}{5 S
   PACEs}-{2 SPACEs}+ -{2 SPACEs}+ -{2 SPA
   CEs}+ {CTRL Ø}"
14Ø CB$="{2 SPACEs}{CTRL 7}":CP$=" {CTRL 5}
   ":TD$="{SHFT CLR}{CTRL 9}{CTRL 7}{3 SPA
   CEs}BIORHYTHMS CHART{3 SPACEs}{CTRL Ø}{
   CTRL 1}":POKE36879,3Ø:PRINTTD$
15Ø INPUT"{CRSR DN} YEAR OF BIRTH";YB$:YB=V
   AL(YB$):IFYB=ØTHENPRINT"{2 CRSR UPs}";:
   GOTO15Ø
16Ø IFYB<1ØØTHENYB=YB+19ØØ
17Ø YR=YB:YB$=RIGHT$(STR$(YB),4)
18Ø INPUT"{CRSR DN} MONTH OF BIRTH";MB$:B$=
   MB$:MO=VAL(MB$):GOSUB8ØØ:MB$=A$:MB=C
19Ø IFLB=1THEN18Ø
2ØØ INPUT"{CRSR DN} DAY OF BIRTH";DB$:DB=VA
   L(DB$):B$=MB$:GOSUB81Ø:DB$=DB$+","
21Ø IFDB<1ØTHENSP$=" "
22Ø IFDB=29ANDMB=2ANDINT(YB/4)=YB/4THEN24Ø
23Ø IFDB>BORDB=ØTHENPRINT"{2 CRSR UPs}";:GO
   TO2ØØ
24Ø INPUT"{CRSR DN} CURRENT YEAR";YC$:YC=VA
   L(YC$):IFYC>ØANDYC<1ØØTHENYC=YC+19ØØ
25Ø IFYC=ØORYC<YBTHENPRINT"{2 CRSR UPs}";:G
   OTO24Ø
26Ø INPUT"{CRSR DN} START AT MONTH";MW$:B$=
   MW$:MO=VAL(MW$):GOSUB8ØØ:MW$=A$:MW=C
27Ø IFLB=1THEN26Ø
28Ø PRINTTAB(3Ø)"{CTRL 1}LEGEND:":PRINT"{CR
   SR DN}{2 SPACEs}{CTRL 9}{CTRL 7} {CTRL
   Ø}{CTRL 1} ACTIVE DAYS"
29Ø PRINT"{2 SPACEs}{CTRL 9}{CTRL 5} {CTRL
   Ø}{CTRL 1} RECOVERY DAYS":PRINT"{2 SPAC
   Es}{CTRL 7}*{CTRL 1} DOUBLE ACTIVE DAY"
3ØØ PRINT"{2 SPACEs}{CTRL 8}*{CTRL 1} TRIPL
   E ACTIVE DAY":PRINTSPC(5)"{CRSR DN}HIT
   ANY KEY"
31Ø GETA$:IFA$=""THEN31Ø
32Ø PRINTTAB(29)"{CTRL 3}WORKING{CTRL 1}";
33Ø DA=DA-DB
34Ø MB=MB-1:IFMB=ØTHEN4ØØ
35Ø ONMBGOTO39Ø,36Ø,39Ø,38Ø,39Ø,38Ø,39Ø,39Ø
   ,38Ø,39Ø,38Ø,39Ø
36Ø DA=DA-28:IFINT(YR/4)=YR/4THENDA=DA-1
37Ø GOTO34Ø
38Ø DA=DA-3Ø:GOTO34Ø
39Ø DA=DA-31:GOTO34Ø
4ØØ IFYR=YCTHEN44Ø
41Ø DA=DA+365:IFINT(YR/4)=YR/4THENDA=DA+1
42Ø YR=YR+1:IFYR=YCTHEN44Ø
43Ø GOTO41Ø
44Ø READMO$:READDC:READC
45Ø IFMO$="FEB"ANDINT(YR/4)=YR/4THENDC=DC+1
46Ø IFMO$=LEFT$(MW$,3)THEN48Ø
47Ø DA=DA+DC:GOTO44Ø
48Ø GOSUB72Ø
49Ø FORN=1TODC:DA=DA+1
5ØØ BP=FNA(DA/23):BE=FNA(DA/28):BI=FNA(DA/3
   3)
51Ø CD$="{CTRL 1}":IFBP>12ANDBP<19ORBE>12AN
   DBE<19ORBI>13ANDBI<18THENCD$="{CTRL 5}"
52Ø PF$=CP$:IFBP>15THENPF$=CB$
53Ø IFBP>29THENFL=1
54Ø PE$=CP$:IFBE>15THENPE$=CB$
55Ø IFBE>29THENFL=FL+1
56Ø PI$=CP$:IFBI>15THENPI$=CB$
57Ø IFBI>29THENFL=FL+1
58Ø FL$=" ":IFFL=2THENFL$="{CTRL 7}*{CTRL 1
   }"
59Ø IFFL=3THENFL$="{CTRL 8}*{CTRL 1}"
6ØØ FL=Ø:N$=MID$(STR$(N),2):L=2-LEN(N$)
61Ø PRINT" ";GC$;FL$;CD$;SPC(L)N$;
62Ø PRINTTAB(5)GC$;PF$;A$(BP);TAB(1Ø)GC$;
63Ø PRINTTAB(11)PE$;A$(BE);TAB(15)GC$;
64Ø PRINTTAB(16)PI$;A$(BI);TAB(2Ø)GC$
65Ø LC=LC+1:IFLC=16THENPRINTBM$:GOSUB75Ø:GO
   SUB72Ø
66Ø NEXT
67Ø PRINTBM$:GOSUB75Ø
68Ø READMO$
69Ø IFMO$="X"THENRESTORE:YR=YR+1:GOTO68Ø
7ØØ READDC:READC:MW$=MO$
71Ø GOTO45Ø
72Ø PRINTTD$;:PRINT"{CTRL 9}{CTRL 7}{7 SPAC
   Es}"MO$;YR"{CRSR LF}{7 SPACEs}{CTRL Ø}"
   ;
73Ø PRINT"{CTRL 1}BIRTHDATE: "SP$;MB$" "DB$
   ;YB$;
74Ø PRINT"{2 SPACEs}DAYS ALIVE:";INT(DA+.5)
   :PRINTTL$:RETURN
75Ø PRINT"{HOME}":PRINTTAB(255)TAB(154)"{CT
   RL 1}{2 SPACEs}{CTRL 9}C{CTRL Ø}ONTINUE
   {2 SPACEs}{CTRL 9}N{CTRL Ø}EW DATA";
76Ø GETA$:IFA$=""THEN76Ø
77Ø IFA$="C"THENLC=Ø:RETURN
78Ø IFA$="N"THENRUN
79Ø GOTO76Ø
8ØØ LB=Ø:B$=LEFT$(B$,3)
81Ø READA$,B,C:IFA$=B$ORC=MOTHENRESTORE:RET
   URN
82Ø IFC=-1THENRESTORE:PRINT"{2 CRSR UPs}";:
   LB=1:RETURN
83Ø GOTO81Ø
84Ø DATA"JAN",31,1,"FEB",28,2,"MAR",31,3,"A
   PR",3Ø,4,"MAY",31,5
85Ø DATA"JUN",3Ø,6,"JUL",31,7,"AUG",31,8,"S
   EP",3Ø,9,"OCT",31,1Ø
86Ø DATA"NOV",3Ø,11,"DEC",31,12,"X",Ø,-1
```

You can look into the future as often as you dare, with this program that unleashes mysterious, mystical forces hidden deep in your C-64's ROM.



Celestial Swami

By JIM BERNARD

If you are old enough to remember the penny fortune-telling machines, in which you placed a coin, pushed in a lever and pulled out a response that was worded vaguely enough to fit just about any question, then you have a fair idea of what Celestial Swami is all about.

After you have loaded and run Listing 1, load and run Listing 2. From then on, just type in your questions about the future, press the return key and know the future!

Naturally, if you are too young to type, Swami will accept questions from the mental concentration, or Oral, mode, as long as you finish with a tap of the return key. But Swami has one important rule—any one question may be asked only once!

The graphics in Celestial Swami are simple, yet elegant, with a nighttime moon and stars combination that never, ever repeats itself—you will have your own unique juxtaposition for each question. Not only do my kids like it a lot, but it is a great attraction with our guests. R

Address all author correspondence to Jim Bernard, 8018 Sunset Path Court, Springfield, VA 22153.



Listing 1. *Celestial Swami Loader program.*

```
10 REM CELESTIAL SWAMI (PART 1)
20 REM BY JIM BERNARD
30 REM LOAD, RUN & NEW THIS PART
40 REM THEN LOAD PART 2 AND RUN
50 FORX=49152TO49415:READA:POKEX,A:N=N+A:NE
   XT
60 FORY=51712TO51933:READA:POKEY,A:N=N+A:NE
   XT
70 IFN<>49034THENPRINT"CHECK DATA FOR ERROR
   "
80 IFN=49034THENPRINT"DATA O.K.! ---NOW NEW
   AND LOAD PART 2"
100 DATA 24,162,23,160,9,32,240,255
110 DATA 162,72,189,24,192,32,210,255
120 DATA 201,146,240,3,232,208,243,96
130 DATA 18,32,84,72,69,32,83,84
140 DATA 65,82,83,32,83,65,89,32
150 DATA 39,78,79,39,32,32,32,146
160 DATA 18,32,32,39,89,69,83,39
170 DATA 32,83,65,89,32,84,72,69
180 DATA 32,83,84,65,82,83,32,146
190 DATA 18,73,84,39,83,32,84,79
200 DATA 79,32,69,65,82,76,89,32
210 DATA 84,79,32,84,69,76,76,146
220 DATA 18,84,72,65,84,39,83,32
230 DATA 81,85,73,84,69,32,80,79
240 DATA 83,83,73,66,76,69,33,146
250 DATA 18,73,70,32,89,79,85,32
260 DATA 82,69,65,76,76,89,32,87
270 DATA 65,78,84,32,73,84,33,146
280 DATA 18,84,72,69,82,69,39,83
290 DATA 32,82,69,65,83,79,78,32
300 DATA 84,79,32,72,79,80,69,146
310 DATA 18,67,79,78,68,73,84,73
320 DATA 79,78,83,32,83,69,69,77
330 DATA 32,82,73,71,72,84,32,146
340 DATA 18,84,72,65,84,39,83,32
350 DATA 81,85,73,84,69,32,85,78
360 DATA 76,73,75,69,76,89,32,146
370 DATA 18,32,67,76,85,69,83,32
380 DATA 65,82,69,32,65,76,76,32
390 DATA 65,82,79,85,78,68,32,146
400 DATA 18,32,89,79,85,39,68,32
410 DATA 82,65,84,72,69,82,32,78
420 DATA 79,84,32,75,78,79,87,146
500 DATA 169,19,32,210,255,169,18,32
510 DATA 210,255,169,6,141,134,2,169
520 DATA 15,141,32,208,141,33,208,162
530 DATA 0,169,32,32,210,255,232,224
540 DATA 255,208,246,240,0,162,0,169
550 DATA 32,32,210,255,232,224,225,208
560 DATA 246,240,0,169,146,32,210,255
570 DATA 162,0,169,58,32,210,255,232
580 DATA 224,40,208,246,240,0,162,0
590 DATA 189,176,202,32,210,255,232,224
600 DATA 40,208,245,240,0,162,0,169
610 DATA 58,32,210,255,232,224,40,208
620 DATA 246,240,0,162,0,169,32,32
630 DATA 210,255,232,224,240,208,246,240
640 DATA 0,162,0,169,32,32,210,255
650 DATA 232,224,40,208,246,240,0,169
660 DATA 18,32,210,255,162,0,169,32
670 DATA 32,210,255,232,224,119,208,246
680 DATA 240,0,162,0,169,146,32,210
690 DATA 255,162,16,160,0,32,240,255
700 DATA 162,0,189,216,202,32,210,255
710 DATA 232,224,6,208,245,240,0,96
720 DATA 67,69,76,69,83,84,73,65
730 DATA 76,32,83,87,65,77,73,32
740 DATA 87,73,76,76,32,84,69,76
750 DATA 76,32,89,79,85,32,84,72
760 DATA 69,32,70,85,84,85,82,69
770 DATA 87,73,76,76,32,0
```

Listing 2. *Celestial Swami program.*

```
10 FORK=12288TO12350:READA:POKEK,A:NEXT:FOR
   K=12352TO12414:READA:POKEK,A:NEXT
20 GOSUB100:REM TITLE SCREEN
30 POKEV+21,0:POKEV+16,0:SYS51712:POKE2023,
   224:POKE56295,6:REM ML GAME SCREEN
```

Circle 327 on Reader Service card

kyan

PASCAL

for the Commodore 64

kyan pascal is a full implementation. With a single disk drive and C64, you can learn Pascal and develop sophisticated programs.

kyan pascal is perfect for classroom or home use. It's Menu-Driven, User-Friendly operating environment helps students learn quickly and lets advanced programmers develop programs 4 to 40 times faster than Commodore Basic.

kyan pascal features:

- Full Screen Editor with Powerful Text Editing Functions.
- MERGE and Other Convenient File Management Functions.
- Fully Resident Software to Eliminate Disk Swapping.
- HELP Screens to Speed Learning.
- Stand-Alone Runtime Environment.
- AND, A Comprehensive Tutorial Manual with Sample Programs.

15 DAY TRIAL

Try *kyan pascal*. If you are not completely satisfied, return diskette and manual in 15 days for a full refund.

kyan pascal with tutorial manual *$49.95*

(Add $4.50/copy for postage and handling. $9.50 outside North America. California residents add 6.5% sales tax)

Call: (415) 775-2923

Send Check/Money Order to:
kyan software, Dept. A
1850 Union St., Ste. 183
San Francisco, CA 94123

Accepted

EASTCOAST SOFTWARE

ecs...inflation-fighting prices.

No hidden charges! No credit card fees!

COMMODORE

CAT #		LIST	SALE
2741	Acct Pav Mgmt/Checks D	59.95	41.50
1914	Advanced Mach. Lang. C64	14.95	11.50
1350	Adventure Constr'n Set (D)	50.00	38.50
1443	Adventure Writer (D)	60.00	42.35
0770	Agent USA (D)	29.95	23.00
1895	Air Rescue One (D)	34.95	24.20
0064	Alien Addition D	34.00	23.55
0064	Alien Addition D	34.00	23.55
0335	Alligator Mix D	34.00	23.55
2713	Alphabet Zoo D	29.95	20.75
1289	Amazon (D)	39.95	27.65
1742	Anatomy of 1541 Disk Drive	19.95	15.35
2913	Archon D	40.00	30.75
1342	Archon II — Acept (D)	40.00	30.75
1739	Assembler 64 (D)	49.95	39.10
1733	Assembler/Monitor-64 (D)	39.95	30.75
3042	Astro-Grover	44.95	29.95
2914	Axis Assasin D	35.00	26.95
1750	B-1 Nuclear Bomber C	16.00	11.10
0181	Back Basics Acct. Sys.	195.00	123.75
1764	Bank Street Writer D	69.95	48.35
1737	Basic-64	39.95	30.75
1355	B.I.-80/80 Column Display	169.95	115.05
0820	Barron's Study for SAT (D)	89.95	62.30
0262	Beachhead D	34.95	24.20
0087	Beyond Castle Wolfen (D)	34.95	24.20
0358	Boulder Dash (D)	34.95	25.55
2959	Cardco Cardprint/+G	109.95	83.75
0201	Carrier Force (B)	59.95	41.50
2835	Castle Wolfenstein D	29.95	20.70
0527	Chartpak 64 (D)	42.95	33.05
2701	Chess D	69.95	48.45
1761	Choplifter R	44.95	31.05
2223	Combat Leader (D)	39.95	27.65
0443	Comm 64 User Encylcopedia	14.95	10.50
1624	Comm. Prog. Reference Guide	19.95	13.85
0416	Compuserve Starter Kit	39.95	24.35
2337	Computer Sat D-Harcourt	79.95	62.85
2917	Cut & Paste D	50.00	38.50
1080	Dallas Quest (D)	34.95	25.55
1880	Deadline D	49.95	34.60
2204	Death In The Caribbean D	35.00	24.25
2716	Delta Drawing R	39.95	27.65
0103	Demolition Division D	34.00	23.55
1722	Disk Boxes (5 Color Coded)	25.00	12.50
2254	Doodle D	49.95	30.75
2179	Dragonriders Of Pern D	40.00	27.70
1752	Dust Cover - 1541 Disk Drv	7.99	5.75
1749	Dust Cover - Commodore 64	7.99	5.75
1759	Dust Cover - 1526 Printer	7.99	5.75
2029	Dust Cover - 1702 Monitor	14.95	10.25
0128	Dust Cover - 801 Printer	7.99	5.75
2340	Early Games Children D	29.95	20.75
2670	Early Games Piece Cake D	29.95	20.75
0546	Elementary Commodore	14.95	11.50
0092	Elephant Disks SS/DD (10)	37.00	17.65
1337	Elephant Disks SS/SD (10)	34.00	16.35
0107	Epson MX-80 Ribbon	14.00	6.30
1535	F-15 Strike Eagle (D)	34.95	24.20
1287	Farenheit 451 (D)	39.95	27.65
1918	Fast Load (R)	39.95	29.20
2973	Flight Simulator 2 D	49.95	38.05
2918	Flip & File W/Lock (50)	39.95	23.85
1440	Flip-N-File (50 Disks)	19.95	11.30
1905	Frogger D	34.95	24.15
1260	Fuji SS/DD Disks (10)	46.00	19.25
1811	Games Commodore 64 Play	14.95	10.35
0842	Game Show (D)	39.95	27.65
0933	Gemstone	34.95	25.55
2739	General Ledger D	59.95	41.50
0905	Geopolitique D	39.95	27.65
1117	Ghost Busters (D)	39.95	30.75
1098	Graphic Basic (D)	29.95	21.90
2911	Hardhat Mac D	35.00	26.95
1437	Head Cleaning Kit	29.95	17.30
2137	Hellcat Ace D	29.95	20.75
0334	Hesmodem 2 (D)	119.97	97.40
1936	Hey Diddle Diddle D	29.95	20.70
0896	Hitchhikers Guide to Galaxy	34.95	23.65
1782	Home Accountant D	74.95	48.05
1085	Home Organ/Checkbook (D)	29.95	20.70
1088	Home Organ/Mail List (D)	29.95	20.70
2297	Homeword D	69.95	48.30
3044	Honey Factory	49.95	33.30
2789	How To Use Commodore 64	3.95	3.30
2868	In Search Of/Amazing D	39.95	27.65
2953	Infidel (D)	39.95	26.65
1786	Infocom Sampler (D)	7.95	5.50
1119	Inside C64 DOS	19.95	15.35
0812	Karateka (D)	29.95	20.25
1320	Kids And The Commodore 64	19.95	15.05
2712	Kids On Keys D	29.95	20.75
2315	Kidwriter D	34.95	24.20
2222	Knights Of The Desert D	39.95	27.65
1333	Koala Graphic Table-CMD64	99.95	65.00
1883	Kraft Joystick (At. Type)	12.95	9.00
0633	Kwik-Load (D)	19.95	13.85
2972	Labels - 1" White (1000)	9.95	6.75
0828	Learning Bridge-Goren (D)	79.95	55.35
2989	Lode Runner D	34.95	24.20
1607	Lode Runner-Champion (D)	34.95	23.30
3038	Lucky's Magic Hat	39.95	26.65
1343	Mail Order Monsters (D)	35.00	26.95
1886	Master Type D	39.95	27.65
2970	Math Blaster D	49.95	34.60
0089	Maxell MD1 Disks-SS/DD (10)	46.50	21.55
1744	Micro Cookbook (D)	34.95	26.25
0080	Microleague Baseball	39.95	29.20
0692	Microline 92-P Printer	499.00	CALL
1509	Microline Ribbon	3.20	2.20
2601	Millionaire (D)	49.95	34.60
1383	Mind Prober (D)	29.95	20.75
1967	Missing Links (Home)	39.95	30.75
1697	Mirage Data Base/RPT Gen.	99.95	69.20
0666	Mirage Word Processor D	89.95	63.70
2735	Money Manager D	24.95	17.30
0897	Monty Plays Scrabble (D)	39.95	29.20
2916	Mule D	40.00	30.75
2870	Multiplan D	99.95	69.20
0763	Murder By The Dozen D	34.95	24.20
2912	Music Const. Set D	40.00	30.75
2134	Nato Commander D	34.95	24.20
1216	NEC 1205 Amber Mntr w/Aud	190.00	168.15
0101	NEC 1215 Color Monitor	399.00	333.35
1469	Net Worth (D)	79.95	55.35
1756	Nukewar C	15.00	10.40
1361	Omniwriter/Omnispell (D)	69.95	51.15
0327	One On One (D)	40.00	30.75
2844	Oxford Pascal (D)	50.00	41.70
0821	Paper Clip w/Spell Pak (D)	119.95	83.05
2893	Parallel Printer Ext. Cable 6'	34.95	21.80
2820	Practicalc D	55.95	38.05
0576	Pascal-64 (D)	39.95	30.75
1627	PFS File (D)	79.95	54.05
1421	PFS Report (D)	69.95	47.35
2834	Pinball D	29.95	20.70
2915	Pinball Const. Set D	40.00	30.75
0381	Pitfall II (D)	34.95	26.90
2184	Pitstop R	40.00	27.70
1975	Pitstop 2 (D)	40.00	29.20
2201	Planetfall D	34.95	23.30
1344	Racing Destruction Set (D)	35.00	26.95
1392	Raid on Bungeling Bay (D)	29.95	20.75
1297	Raid Over Moscow (D)	39.95	27.65
1348	Realm of Impossiblity (D)	35.00	26.95
2711	Rhymes & Riddles D	29.95	20.75
2993	Sargon 2 D	19.95	12.70
0221	Scooter Surge Prot Strip-6	48.35	37.20
1416	Smith Corona TP1 Ribbon	7.95	6.35
2837	Software Automouth D	59.95	41.45
2952	Solo Flight D	34.95	24.20
1790	Spy Hunter (R)	44.95	31.10
2935	Star Trek R	39.95	27.60
1881	Starcross D	39.95	27.65
1277	Starwriter Film Ribbon	5.50	4.50
1278	Starwriter Nylon Ribbon	5.75	4.65
2316	Step By Step (D)	59.95	41.50
1109	Summer Games (D)	39.95	27.70
1188	Superbase 64 (D)	99.95	76.90
0759	Superclonse w/Unguard (D)	49.95	38.45
2250	Supertext Pro D	99.00	66.00
1952	Survivor D	34.95	24.20
1877	Suspended D	49.95	34.50
0248	T.A.C. (D)	40.00	27.70
1857	Tapper (R)	44.95	31.10
0346	Tax Advantage D	69.95	44.85
1259	Taxan 12 in Amber Monitor	189.00	138.65
1258	Taxan 12 in Green Monitor	179.00	131.60
1528	Taxan Color Mntr W/Audio	399.00	305.50
0444	Telengard D	28.00	19.40
2874	The Consultant (D)	99.95	69.20
1148	The Pond (D)-School	55.00	42.30
0859	Tic Tac Show (D)	39.95	27.65
0766	Tigers In The Snow (D)	39.95	27.65
1788	Total Modem	129.95	75.60
0507	Tracer Sanction (D)	34.95	26.90
1702	Trivia Fever (D)	39.95	27.65
2195	Turtle Graphics II R	39.95	30.75
0679	Type Tutor/Word Invade D	24.95	17.30
0884	Ultima 3 D	54.95	38.05
0541	Ultrabasic - 64 (D)	27.95	21.50
1721	Verbatim SS/DD Hardpack	35.00	23.35
0093	Verbatim SS/DD Softpack	34.00	19.00
1072	VIP Terminal D	59.95	46.10
1529	Visible Computer 6502 (D)	40.00	25.65
0002	Wico Joystick	29.95	21.95
0015	Wico Redball Joystick	34.95	24.40
0008	Wico The Boss Joystick	19.95	14.10
1885	Witness D	34.95	23.30
2889	Wordpro 3+ W/Spell D	99.95	75.00
0264	Worms D	40.00	30.75
2871	Your Commodore 64	14.95	12.50
0577	Zaxxon D	34.95	20.75
1741	Zork I D	39.95	31.25
1879	Zork II D	39.95	27.65
1882	Zork III D	39.95	27.65

Key
(D) Disk Program
(R) Rom Cartridge
(C) Cassette Program

Many More Titles Available!

Commodore® is a registered trademark of COMMODORE ELECTRONICS, LTD.

VISA®

master charge THE INTERBANK CARD

EASTCOAST SOFTWARE

49 Derrytown Mall
Hershey, PA 17033

MAIL YOUR ORDER OR CALL
(717) 533-8125
800-233-3237

We Ship UPS—Shipping 1% ($2.50 min.)
C.O.D. Add An Additional $2.50
Hardware (Printers/Monitors)
Shipping is $2.50 +4% (U.P.S.)
For Air Mail, Canadian, APO/FPO Orders,
Shipping $2.50 +4% of Total Order (US Funds)
PA Residents Add 6% Tax

No Minimum Order
Visa-Mastercard-C.O.D.-Check

Prices Subject To Change
Sorry, No Foreign Orders

800-233-3237
In PA 717-533-8125

This Ad Prepared January 1985

CHECK ONE: ☐ VISA ☐ MASTERCARD

Card#_____ Exp. _____

Telephone _____

Name _____

Address _____

City _____

State _____ Zip _____

Please enter my order for: _____

_____

_____

Please specify machine: _____

☐ *Please send free catalog.*

Listing 2 continued.

```
4Ø GOSUB3ØØ:REM SPRITE SET-UP
5Ø GOSUB2ØØ:REM RANDOM CELESTIAL DESIGN
55 OPEN1,Ø:INPUT#1,Q$:CLOSE1
57 FORK=1TO1ØØØ:NEXT
6Ø X=INT(RND(.)*1Ø):X=X*24:POKE49161,X:REM
   HELP SWAMI CHOOSE REPLY
7Ø SYS49152:POKE214,15:REM ML REPLIES
75 GETY$:IFY$<>""THEN75
8Ø GETZ$:IFZ$=CHR$(13)THEN3Ø
9Ø IFZ$=CHR$(133)THENPOKEV+21,Ø:END
99 GOTO8Ø
1ØØ REM TITLE PAGE SUBROUTINE
11Ø PRINTCHR$(147):POKE5328Ø,15:POKE53281,1
   5:POKE646,6
12Ø PRINTSPC(12)"CELESTIAL SWAMI"
13Ø PRINT"{3 CRSR DNs}{SHFT Q}QUESTIONS MUS
   T ADDRESS FUTURE EVENTS!"
14Ø PRINT"{3 CRSR DNs}{SHFT Q}ASK ANY QUEST
   ION ONLY ONCE!"
15Ø PRINT"{3 CRSR DNs}{SHFT Q}PRESS 'RETURN
   ' AFTER TYPING A QUESTION."
16Ø PRINT"{2 CRSR DNs}{SHFT Q}PRESS 'RETURN
   ' TO ASK ANOTHER QUESTION";
17Ø PRINT"{2 SPACEs}OR PRESS 'F-1' TO END T
   HE GAME."
18Ø PRINT"{3 CRSR DNs}{SHFT Q}NOW PRESS 'RE
   TURN' TO CONTINUE."
19Ø GETC$:IFC$<>CHR$(13)THEN19Ø
199 RETURN
2ØØ REM CELESTIAL SUBROUTINE
21Ø SC=1Ø24:CL=55296
22Ø FORD=1TO6Ø:N1=INT(RND(TI)*48Ø):POKESC+N
   1,174:POKECL+N1,6:NEXT
23Ø FORD=1TO8:N2=INT(RND(TI)*48Ø):POKESC+N2
   ,17Ø:POKECL+N2,6:NEXT
24Ø FORD=1TO8:N3=INT(RND(TI)*48Ø):POKESC+N3
   ,2Ø9:POKECL+N3,6:NEXT
25Ø FORD=1TO8:N4=INT(RND(TI)*48Ø):POKESC+N4
   ,218:POKECL+N4,6:NEXT
299 RETURN
3ØØ REM SPRITES ON
31Ø POKE2Ø4Ø,192:POKE2Ø41,193:V=53248
32Ø POKEV+28,3:POKEV+37,Ø:POKEV+38,7
33Ø AA=INT(RND(1)*275)+4Ø:IFAA>255THENAA=AA
   -255:POKEV+16,1
34Ø BB=INT(RND(1)*75)+5Ø
35Ø POKEV+Ø,AA:POKEV+1,BB:POKEV+2,AA:POKEV+
   3,BB
36Ø CC=INT(RND(TI)*2)+1
37Ø IFCC=1THENPOKEV+21,1
38Ø IFCC=2THENPOKEV+21,2
39Ø RETURN
5ØØ REM SPRITE #1 DATA
51Ø DATA Ø,252,Ø,3,255,Ø,7,255,128,15,{2 SP
   ACEs}255,192
52Ø DATA 31,255,224,63,255,24Ø,127,255, 248
   ,127,255,248
53Ø DATA 255,255,252,255,255,252,255,255,25
   2,255,255,252
54Ø DATA 127,255,248,127,255,248,63,255,24Ø
   ,31,255,224
55Ø DATA 15,255,192,7,255,128,3,255,Ø,Ø,252
   ,Ø,Ø,Ø,Ø
6ØØ REM SPRITE #2 DATA
61Ø DATA Ø,252,Ø,3,252,Ø,7,248,Ø,15,24Ø,Ø
62Ø DATA 31,24Ø,Ø,63,224,Ø,127,224,Ø,127,19
   2,Ø
63Ø DATA 255,128,Ø,255,128,Ø,255,128,Ø, 255
   ,128,Ø
64Ø DATA 127,192,Ø,127,224,Ø,63,224,Ø,31,24
   Ø,Ø
65Ø DATA 15,24Ø,Ø,7,248,Ø,3,252,Ø,Ø,252,Ø,Ø
   ,Ø,Ø
```


ON-LINE IS FUN . . .

BUT THE COSTS ARE NO GAME!

Telephone costs, interconnect charges and connect costs can make communications an EXPENSIVE activity.

YOU NEED A TERMINAL PROGRAM THAT'S *SERIOUS* ABOUT SAVING YOU MONEY!

YOU NEED . . . ONE-KEY LOG-ON * ONE-KEY TEXT TRANSMISSION
DIRECT UPLOAD FROM DISK * AUTO DIAL & RE-DIAL
LARGE BUFFER THAT EMPTIES FAST WHEN FULL
FAST TRANSFER PROTOCOL

SMART 64 Terminal

APPROVED BY THE UNITED STATES COMMODORE USERS GROUP

Circle 27 on Reader Service card.

$39.95

MICROTECHNIC SOLUTIONS, INC.
P.O. BOX 2940 NEW HAVEN CT. 06515 (203) 389-8383

TALKING VERSION ALSO AVAILABLE

Circle 209 on Reader Service card.

at TUSSEY COMPUTER PRODUCTS*. . .

WE KNOW WHAT YOU WANT!

We take a bite out of prices!

WE VALUE YOUR BUSINESS. IN ORDER TO EARN IT, WE ARE GOING TO GIVE YOU THE THINGS YOU WANT MOST FROM A MAIL ORDER COMPUTER STORE.

1) **Low Prices!** We try to have the lowest prices around. If you do find a lower price, please give us a chance to beat it.

2) **Fast, dependable service** - Our shipping department works hard to get your orders out quickly, usually within one business day.

3) **Straight talk** - We will give you accurate information as to our stocking condition

4) **Personnel who care** - The people at TCP sincerely want you to be happy with the way your order is handled. We all know our jobs depend on having a happy customer.

ORDERS ONLY PLEASE: 800-468-9044

INFORMATION & PA ORDERS: 814-234-2236

PHONE LINES OPEN 10-8 MON-FRI, 10-5 SAT

THE PANASONIC KXP 1091 PRINTER

Near letter quality at the flick of a switch

The 1091 zips along at 120 cps and has a 1k buffer. It also has all the print modes of the Gemini 10X and Epson RX-80, plus a BIG difference. The 1091 has a near letter quality switch. Flip it and you get a super tight 12 by 18 matrix with characters that rival a daisy wheel! The 1091 has both friction and tractor feed.

Our price $279.00

Panasonic KXP 1090 ..... $199.00
(does not have near-letter quality)

SG 10, NLQ Dot Matrix from Star ..... Call



PRINTERS

Gemini 10X $234.00*
SG-15 ..... Call
Delta 10, 160 cps, 8k buffer $389.00*
Delta 15 ..... $580.00*
Powertype, 18 cps, letter quality $329.00*

PRINTER INTERFACES

Xetec GPI ..... $ 76.99
Xetec SPI/B ..... $ 59.99
Xetec SPI ..... $ 43.99
Cardco 7+G ..... $ 67.00
Cardco 7/B ..... $ 44.00
Cardco PS Interface ..... Call

DATABASES

The Consultant ..... $ 63.99
Mirage Database Manager/ Report Generator ..... $ 69.99
Superbase 64(d) ..... $ 56.99
Data Manager II by Timeworks ..... $ 32.99
Practifile by MS(d) ..... $ 37.00

MODEMS

Total Telecom (1650 compatible) ..... $ 76.95
Commodore 1660 New! ..... Call
Compuserve starter kit ..... $ 26.95
Westridge modem ..... $ 76.95
Mighty Mo, new modem from USI ..... $ 78.99
VIP terminal package by Softlaw ..... $ 39.95
Vidtex Terminal ..... $ 30.00
Vidtex plus Compuserve Starter ..... $ 49.99

WORD PROCESSORS

Word Processor by Proline(d) ..... $ 39.99
Wordpro 3+/64 w/spellright(d) ..... $ 59.00
Paperclip(d) ..... $ 59.00
Paperclip w/spellpack(d) ..... $ 76.99
Cardco Write Now/64 (cart) ..... $ 37.00
Mirage Professional W.P.(d) ..... $ 59.00
Omni Writer/Speller(d) ..... $ 45.00
Word Writer(d) by Timeworks ..... $ 32.99
Script 64 ..... $ 39.99

CARDCO

Light pen ..... $ 29.00
Numeric keypad ..... $ 35.00
5 slot exp. interface CB-5 ..... $ 58.00
Mail Now/64 ..... $ 32.00
Spell Now ..... $ 31.99
File Now ..... Call
Graph Now ..... Call

Cardco LQ1 letter quality printer $429.00
Cardco LQ3 ..... $319.00
Epson RX-80 ..... $244.00
Epson Printers ..... Call
Okidata Printers ..... Call
Hush 80 ..... $109.00
*Star Micronics printers come with a 1 year warranty!

HARDWARE

1541 Express by RTC ..... $ 73.99
Smart Cable ..... $ 49.95
BI-80 Batteries Including 80 column card with Basic 4.0 built in $137.99
BusCard II by Batteries Included ..... Call

SPREADSHEETS

Calc Result Adv. (d, cart) ..... $ 67.00
Calc Result Easy (cart) ..... $ 33.99
P.S. (Prog. Spreadsheet)(d) ..... $ 49.99
Practicalc 64(d) ..... $ 36.00
Practicalc 64(t) ..... $ 34.00

MONITORS

Zenith 12" Amber ..... $ 97.00
Zenith 12" Green ..... $ 92.00
Sakata SC-100 Color Monitor $239.00
Amdek Color 1 Plus $259.00
Cable for monitors ..... $ 9.95
1702 ..... Call

UTILITIES

Pal 64 assembler by Proline(d) ..... $ 39.99
Power 64 Basic by Proline(d) ..... $ 39.99
Toolbox 64, both Pal 64 and Power 64(d) $ 69.99
Canada A/M backup program ..... $ 39.95
Simon's Basic ..... $ 39.95
CSM 1541 Alignment ..... $ 32.99

MISCELLANEOUS

Koalpad w/painter(d) ..... $ 65.00
Spellpro 64(d) by Proline ..... $ 39.99
Mailpro 64 ..... $ 39.99
Complete Personal Accountant(d) ..... $ 54.00
The Home Accountant ..... $ 36.95
Timeworks Inventory, A/P, A/R, Cash Flow Management, General Ledger, Payroll Management ..... $40.95 each
64 Doctor ..... $ 24.95
FCM, First Class Mail ..... $ 36.95
Super Sketch ..... $ 39.99

DISK DRIVES

MSD SDI $249.00
MSD SDII ..... Call
Indus GT Disk Drive ..... Call
1541 ..... Call

★ NEW PRODUCTS ★

Trio from Softsync, Integrated W.P., Database, Spreadsheet ..... Call
Homepak from Bat Incl., Integrated W.P., Database, Telecommunications ..... Call
Vizastar Int. Spreadsheet, Database, Business Graphics ..... Call
Epyx Fast Load ..... Call
Broderbund Print Shop ..... $ 31.99

Please Note: When we ask you to call for a price it's because prices on those items are volatile, and we want to be sure we can give you the lowest prices we can.

To Order By Mail: Send personal check, money order, or certified check. Allow 2 weeks for personal checks to clear.

Shipping: Software and accessories: add $2.50 per order—COD order: add $6.00 (cod's not accepted on printers, monitors, and disk drives.)—Printers: add $10.00. Disk Drives and Monitors add $8.00. Call for other shipping charges. Additional shipping required on APO, FPO, AK, HI, and foreign orders.

Terms: Orders shipped UPS unless noted otherwise. All prices reflect cash discount. Add 3% for Visa and Mastercard. Manufacturer's warranty honored with our invoice and original packaging. PA residents add 6% sales tax. Prices subject to change. All sales final. Defective products replaced or repaired at our descretion.

"DEALER INQUIRIES INVITED"

Other product lines available! Call for prices.

commodore 64

NEW PRICES!
Commodore 64 is $147.00*

*With the purchase of any printer, disk drive, monitor, or modem

1541 Disk Drive $195.00
1702 Color Monitor $195.00
1660 Modem ..... Call
Plus 4, C-16, others ..... Call
SX 64 ..... $495.00

NEW PRINTER FROM STAR!

The SG-10 is an upgrade of the popular Gemini 10X. It runs at 120 CPS, and has all the print modes of the 10X. What makes this printer different is a near letter quality mode at 60 CPS, with a 17 by 11 matrix! With this mode the printer does double duty, eliminating a need for a letter quality printer. It also includes a built in 2k buffer, and a 1 year warranty.

PLEASE CALL FOR OUR LOW PRICE!

BUY A BUNDLE— $AVE A BUNDLE

Order one of these popular packages of products by number for super savings!

Package #5
WORD PROCESSOR 64 and SPELLPRO 64
The word processor and spelling checker from Proline Software
$73.99

Package #6
1541 EXPRESS and the FAST CABLE
Everything you need to speed up your disk drive
$119.99

Package #7
CONSULTANT and PAPERCLIP W/SPELLPACK
These are the popular Database and Word Processor from Batteries Included
$129.99

Package #9
MIRAGE DATABASE/ADVANCED REPORT GENERATOR and MIRAGE PROFESSIONAL WORD PROCESSOR
A powerful package that integrates together
$124.95

Package #10
BI-80 and PAPERCLIP W/SPELLPACK
The 80 column card with the Basic 4.0 built in, and the Paperclip w/spellpack both from Batteries Included. Paperclip works with the 80 column card to give you a powerful word processor
$209.95

TUSSEY COMPUTER PRODUCTS
*** (formerly Tussey Mountain Software)**
BOX 1006
STATE COLLEGE, PA 16804

Circle 92 on Reader Service card.

STAR'S NEW PRINTERS WORK 20% FASTER. COST 20% LESS. ARE 100% CERTAIN TO CHANGE YOUR MIND ABOUT PRINTERS.



This new dual-mode SG-10 is only $299.

No printer could be more appealing than one you design yourself.

And, in effect, that's what you've done.

The new "S" series printers from Star Micronics have been designed not to our specifications, but to yours. With values that confound our accountants but will make great sense to you.

These printers are faster than ever. More compatible and reliable. With more added in and fewer add-ons.

And yet they cost *less*.

Don't try to figure it out. Just enjoy.

NLQ IS 1 OF 2


Mr. Stephen B. Cowles
142 Centerwood Road
San Francisco, CA 94122
Dear Mr. Cowles,
In response to your letter of
pleased to be able to inform you
near letter quality is standard

Because we've increased our printing throughput by 20%, you can now finish 6 pages in the time it used to take to print 5. And even though we've upped our speed, we've kept up our quality.

In fact, on three of our new models, both draft *and near-letter-quality* are standard (no extra charge). A fourth model, the SB-10, prints draft *and letter-quality* standard (again, not extra).

So now, with just *one* printer, you're ready for data processing and word processing. That's like owning two printers for the price of just one.

GET ON LINE BY JUST PLUGGING IN

The new Star "S" series printers are fully compatible with even the most fickle of personal computers.

And they're especially friendly with IBM®-PC, Apple,® Commodore,® and all compatibles.

In most cases, hooking up is no more complicated than putting a square peg in a square hole. But it's a lot more rewarding.

READY FOR ANY SOFTWARE



The new "S" series printers make printing as easy as 1-2-3.™ Which is just one example of the many spreadsheet programs they're ready for.

The new Stars can work with word processing programs like WordStar.® Educational software like Dr. Logo.™ And even the new integrated formats like Framework™ and Symphony.™

So Star printers match hardware to software without disk-driving you crazy.

They handle many functions faster. They're more compatible. Less expensive. More reliable. And have a full year warranty. "S" series printers have been designed with so many of your needs in mind, it's as if you'd done it yourself.

And what a great job you did.

For a free demonstration, visit your local Star dealer.

SD-10 types draft and NLQ, just $449.

SR-10 prints 200 cps for only $649.

SR-15 includes 16K memory for spreadsheets, $799.

star™

THE POWER BEHIND THE PRINTED WORD®

200 Park Avenue, New York, NY 10166
Chicago, IL (312) 773-3717 • Boston, MA (617) 329-8560
Irvine, CA (714) 586-8850

Prices shown are manufacturer's suggested retail prices.

The Plus/4's File Manager

By MARGARET MORABITO

This article reviews the Plus/4's built-in File Manager. This command-driven database program can accommodate an impressive 999 records per file and can be integrated with the built-in Word Processor to create customized mailing labels, form letters and more.

This article, covering the File Manager, is the third in a series of reviews on the Plus/4's built-in programs. (See *RUN*'s December 1984 issue for a review of the Plus/4 Word Processor and the February 1985 issue for a review of its Spreadsheet and Graph programs.)

The File Manager allows you to create individualized file formats for storing, updating and retrieving information. Your data files can be integrated with the Word Processor, so you can display and print your records within letters or reports. This integration capability also lets you merge your Plus/4 Spreadsheet files and accompanying graphs so that your printed documents are truly a cooperative blend of all four of the Plus/4's programs.

Like its companion programs, the File Manager requires a monitor or television, a disk drive and a printer for full usage. *The Plus/4 Integrated Software Manual* devotes a 40-page section to instruction on the File Manager.

This database program offers random access to its files with a maximum of 999 records per file. Each file can have 17 fields, with 38 characters per field. Because of the great number of records that can be managed and the variety of data-handling features, the File Manager imposes a limit of one file to a disk.

Starting Up

To access the File Manager, you must be in the Word Processor. Once there, simultaneously press the CMD with the C key (always used to initiate Command mode), then type tf and press the return key. You are now in the File Manager.

You will first see a prompt to insert a separate disk, which will serve as your datafile disk. It is important not to insert a disk that has your word processing or spreadsheet files on it, as these files will all be erased when the disk is formatted to accept File Manager records.

Once the data file disk is in place, you may either type newtf, to format the disk to accept a new file, or tf, if you have already formatted the disk and just want to update its information. If you are simply accessing a previous file, tf will display your filename, the number of records used and the cursor prompt for Command mode.

When starting a new file, you will be prompted for filename, number of fields, field names and field lengths. After entering your file parameters, you can modify them before your disk undergoes formatting.

For those of you who are familiar with database setup, these procedures are not difficult. Those who are newcomers to database creation will need to practice creating file formats. The Plus/4 documentation provides ample opportunity for this practice.

Entering and Editing

Unlike some database programs, the File Manager lets you enter records in either nonsequential or sequential order. This is accomplished with the rc# (record number) or nr (next record) command. Entering data is easily accomplished by following the screen prompts.

At the bottom of the screen, you will see two status lines showing the filename and the current field name. At the upper left corner, you will see a cursor where you will type your information for each field; press the return key after each line. After a record has been completed, you will always save it on disk by entering the ud (update) or nr command.

Changing information is a simple matter because of this computer's full screen-editing capability, which lets you move your cursor to the desired location and retype. With your record displayed, as a result of the rc#

or nr command, you will use the insert, delete and cursor movement keys to make any changes. After editing a record, you will use the ud or nr command to save to disk. The ud command can also be used to save duplicate records, thus eliminating the need for retyping material.

As with most command-driven programs, it seems difficult at first to try to remember which commands do what. However, by the time you get into the File Manager, you will have used the commands necessary for the other three built-in programs, thereby making the learning of these few new commands quite easy.

Review, Search and Sort

Databases offer you the opportunity to review records, search specific fields and sort records. The review feature on the File Manager lets you sequentially view your file, starting at any record number. This feature is useful for browsing for specific information, as it automatically advances through each record. You can also temporarily or permanently halt the display by pressing the S or Q keys, and you can return to any record for rereading or editing.

The ability to locate information quickly is of the utmost importance, and this is where a database earns its keep. The File Manager has an extremely powerful search feature that allows you to request all or any part of a field's data. You are not limited by left-to-right character matching. In addition, when you do ask for a search, all fields of each record in your file will be analyzed, resulting in a display of each record that contains your request.

Furthermore, the highrc and the pick commands let you limit the number of records in a search. This is a useful feature when you have a very large file and need to scrutinize a specific section.

One of the benefits of a database

C-64 Versions of Plus/4 Software

C-64 owners will be pleased to hear that David Johnson (from Tri Micro, 1010 N. Batavia St., Suite G, Orange, CA 92667), the creator of the Plus/4 built-in software, has written versions of these integrated programs to run on the C-64.

The Write File combines the Word Processor and the File Manager onto one disk, while Your Home Office offers the Word Processor and the Spreadsheet on another disk. Each disk will be selling for $29.

The Word Processor offers double spacing. Also, this File Manager sorts records much faster than the Plus/4's. (It does not need the accompanying fix.) Plus/4 owners can get a utility disk with these enhancements from Tri Micro ($14).

I have tested these new C-64 programs and have successfully transferred files to and from the Plus/4. Be aware that to load a Plus/4 Word Processor file into your C-64, you will need to use the Merge command, rather than the Load command that you use to load Spreadsheet and File Manager files. Use the Load command, however, to load all C-64 files into your Plus/4.

MM

Plus/4 File Manager Fix

Tri-Micro's David Johnson, the creator of the built-in Plus/4 software, has informed me of two slight problems that aren't often seen, but do exist in the Plus/4 File Manager program. Here is a brief description of them and a fix that has been developed to alleviate any difficulties they may cause.

When, through the Word Processor, you are trying to merge over 255 records for printing, your printer might stop, early in your file, on one particular record, and repeatedly print this record. Less often encountered is a second problem of one record overwriting another when entering records, again when you have over 255 records in a file.

To offset the possibility of these bugs creeping into your File Manager handling, type in Listing 1 and save it to a disk on which you won't be storing your File Manager records. Before using the File Manager with over 255 records, load and run this short program right after powering up and before accessing the Word Processor through which you enter the File Manager.

MM

Listing 1. *File Manager Fix program.*

```
10 REM FILE MANAGER FIX 10/30/84
20 REM LOAD AND RUN
30 FOR I=32571 TO 32765
40 READ A:POKE(I),A:NEXT I
50 SYS32571
100 DATA 169, 75,133,218,169,129,133
110 DATA 219,169, 51,141,171,127,169
120 DATA 218,141,172,127,120,174,255
130 DATA 127,138,134,251,157,208,253
140 DATA{2 SPACEs}88,173,{2 SPACEs}6,255, 4
    1,239,141
150 DATA{3 SPACEs}6,255,169,{2 SPACEs}0,133
    ,216,169
160 DATA{2 SPACEs}16,133,217,160,{2 SPACEs}
    0,177,218
170 DATA 145,216,230,218,208,{2 SPACEs}2,23
    0
180 DATA 219,230,216,208,{2 SPACEs}2,230,21
    7
190 DATA 165,219,205,172,127,144,233
200 DATA 165,218,205,171,127,144,226
210 DATA 240,224,120,162,{2 SPACEs}0,134,25
    1
220 DATA 142,208,253, 88,173,{2 SPACEs}6,25
    5
230 DATA{3 SPACEs}9, 16,141,{2 SPACEs}6,255
    ,160,{2 SPACEs}0
240 DATA 185,173,127,153, 49, 49,200
250 DATA 192,{2 SPACEs}3,144,245, 76,192, 1
    7
260 DATA 247,{2 SPACEs}0, 76,199,127,162,{2
     SPACEs}1
270 DATA 165, 43, 24,105,{2 SPACEs}2,133, 4
    3
280 DATA 144,{2 SPACEs}1,232,138, 24,101, 4
    5
290 DATA 133, 45,144,{2 SPACEs}2,230, 46, 9
    6
300 DATA 141,{2 SPACEs}6,125, 32, 52, 49,16
    0
310 DATA{3 SPACEs}0,185,231,127,153,157, 82
320 DATA 185,246,127,153,227, 86,185
330 DATA 250,127,153,162, 88,200,192
340 DATA{3 SPACEs}4,144,233, 96,208, 10,234
350 DATA 234,144,{2 SPACEs}6,230, 45,208,{2
     SPACEs}2
360 DATA 230, 46, 76,179, 86, 76,235
370 DATA 127,165, 76,176,127,123
```

Circle 177 on Reader Service card.

NEW!
Universal Parallel Graphics Interface

- Built-in self-test with status report
- Optional RAM printer buffer
- Provides virtually total emulation of Commodore printers for compatibility with popular software
- ASCII conversion, total test, Emulate & transparent mode
- Fully intelligent interface that plugs into standard Commodore printer socket
- Exclusive graphic key-match function
- Switch selectable Commodore graphics mode for Epson, StarMicronics, C.Itoh, Prowriter, Okidata, Seikosha, Banana, BMC, Panasonic, Mannesman Talley & others.

Micrografix MW-350 . . . . . $129.00
MW-302C Printer Interface also available at $79.95

Universal Input/Output Board for VIC-20/64

- 16 channel 8-bit A/D converter with 100 microsecond sampling time.
- 1 D/A output.
- 16 high voltage/high current discrete outputs.
- 1 EROM socket.
- Use multiple boards for additional channels up to 6 boards

VIC-20 uses MW-311V $205.00
CBM-64 uses MW-311C $225.00



Dealer Inquiries invited

VISA MasterCard

Micro World Electronix, Inc.
3333 S. Wadsworth Blvd., # C105,
Lakewood, CO 80227

(303) 987-9532
or 987-2671

Circle 35 on Reader Service card.

All this...

ACCESS	
Scrolls of Abadon(D)	$27.95
ACTIVISION	
Mind Shadow(D)	27.95
ADDISON WESLEY	
Cave Girl Clair(D)	29.95
ARTWORK	
Slap Shot(D)	16.95
AVALON HILL	
Tournament Golf(D)	23.95
BATTERIES INCLUDED	
Home Pak(D)	37.95
BLUE CHIP SOFTWARE	
Tycoon (D)	37.95
BLUE SKY	
Script/Scratch 64(D)	58.95
BRODERBUND	
The Print Shop(D)	35.95
The Serpent Star(D)	27.95
CARDCO	
Write Now(C)	37.95
CBS	
Big Bird's Fun House(D)	33.95
CITY SOFTWARE	
Doodle(D)	29.95
COMMODORE	
Nevada Fortran(D)	43.95
CREATIVE	
I Am The 64(Vol.1-6)(D)	23.95
CSM	
Disk Drive Alignment Kit(D)	30.95
CYMBAL	
English/Spanish(D)	29.95
DAVIDSON ASSOC.	
Speed Reader II(D)	52.75
ELECTRONIC ARTS	
Adventure Const. Set(D)	37.95
EPYX	
Fast Load(D)	29.95
HAYDEN	
Sargon III(D)	39.95
King Cribbage(D)	9.95
HES	
Omni Writer/Speller/ Multiplan(D)	95.95
HUMAN EDGE	
Communication Edge(D)	156.00
INFOCOM	
Hitch Hiker's Guide(D)	$27.95
INFODESIGNS	
General Ledger(D)	59.95
KOALA	
Koala Printer(D)	19.95
MICROPROSE	
F-15 Strike Eagle(D)	27.95
MINDSCAPE	
Indiana Jones(D)	23.95
MUSE	
Super Text Pro(D)	57.95
ODESTA	
Chess 7.0(D)	49.95
ORBYTE	
Stock Analizer(D)	47.95
PARKER BROS.	
Montezuma's Revenge(D)	27.95
PROFESSIONAL SOFTWARE	
Fleet System II(D)(W.P.)	57.95
PROGRESSIVE PERIPHERALS	
Wizard(D)	29.95
SIERRA/ON LINE	
Homeword Speller(D)	39.95
SOFTSYNC	
Trio(D)	49.95
SUBLOGIC	
Flight Simulator II(D)	37.95
TALORMADE	
Touch Typing Tutor(D)	18.95
HARDWARE	
CARDCO	
Cardboard 5 Slot	56.95
MODEMS	
Westridge	79.95
Mitey Mo	79.95
Total	79.95
Endus Disc Dr	299.00

...and there's a whole lot more! send for our free catalog. Over 1000 programs in stock.

TO ORDER: Send Certified checks, money orders, or use your Master or Visa Card and CALL **1-800-343-8019**. From inside New Hampshire call **(603) 542-6175**.
Personal or company checks require two to three weeks to clear. All prices are subject to change without notice. SHIPPING CHARGES... U.S. orders please add $2.00 (for 1-100 pcs.) For C.O.D. add $4.00 CANADIAN ORDERS: $5.00. ALL OTHER COUNTRIES: 15% of total sale. Air Mail only. ALL ORDERS OVER $100.00 MUST BE INSURED @ .85¢ per $100.00. Customer must pay all duty taxes.
Hours: Monday thru Saturday 8:00 to 10:00 Eastern Time.

UNIVERSAL SOFTWARE
The Best Software for Less
P.O. Box 955 • Claremont, N.H. 03743
Call Now 1-800-343-8019 Toll Free

is its ease of manipulating information. You will want to call up categories of information in a particular order. This is the job of a sort routine. The Disk Sort command lets you sort three fields at once and save your sorted file for future use. In addition, you can negate a sort—any time after it has been saved to disk—and return to your original entry order. You will use this when you need to print out your data in more than one order.

Integration with Word Processor

The integration of the File Manager with its three companion programs is what makes the Plus/4 such a good value. You can create a document that merges data from all four programs by using special instructions entered in reverse video inside the Word Processor. All word-processing instructions can be used as well.

You can achieve a wide variety of print formats when coordinating the File Manager with the Word Processor. This variety ranges from the ability to create printed lists of all your records in any field order to a selective report feature that lets you access a certain group of records from your file for printing.

Furthermore, the Plus/4 enables you to print form letters with accompanying mailing labels, using your file. The Plus/4 documentation will provide clear explanations with plenty of pictures and directed exercises for you to perform. These will lead you into advanced datafile handling within a very short time. The form that your data can take is only limited by your needs and creativity.

The four software programs inside the Plus/4 make this computer immediately valuable to someone who knows nothing about actual computer programming. These programs will more than pay for the cost of your Plus/4 as they aid you in home, small business and even educational applications.

Over the next few months, those of you who are interested in computer programming can look forward to in-depth reviews of the outstanding programming capabilities of the Plus/4: enhanced Basic 3.5, high-resolution and multicolor graphics, sound and the machine language monitor. R

Address all author correspondence to Margaret Morabito, c/o RUN *editorial, 80 Pine St., Peterborough, NH 03458.*

BEFORE LOADING YOUR SOFTWARE
MAKE A PERFECT BACKUP WITH

NEW! Version 2.2

DiskMaker

99% EFFECTIVE

THE AUTOMATIC DISK BACKUP SYSTEM FOR YOUR 64 & 1541 DRIVE!

- **Actually copies a FULL disk in only 4 MINUTES!**
- **Easiest to use – TOTALLY automatic copy utility**
- **State of the "ARTS" copy capability!**
- **UNLOCKS protected disks for backup copying**
- **Breaks through LATEST protection schemes**
- **Includes FAST copier, "ARTS" copier and TRUE Nibbler: you get 3 copiers for the price of 1**
- **HALF-TRACKING up to & including track 40!**
- **100% machine code for fast, RELIABLE operation**
- **4 min. copier AUTOMATICALLY puts "errors" on copy**
- **Fastest & most advanced copier you can buy**
- **Writes errors 20,21,22,23,27,& 29 WHILE COPYING!**
- **Transforms your 1541 into a SUPER-FAST copy drive!**
- **NO analysis required, just swap disks & NO damaging drive knock during errors or format**
- **Formats AS IT COPIES, detects & reproduces NON-STANDARD formats & I.D. mismatch, DOS flags**
- **PRODUCT SUPPORT tel. #, revisions, & upgrades**

OVER 500% FASTER THAN OTHER COPIERS!

MasterCard VISA

ONLY $49.95 for entire system

To order CALL **805-687-1541 ext. 84**
Technical line 805-682-4000 ext. 66

AMERICAN EXPRESS

For rush service call 24 hr. order line or send cashiers check/money order. Visa, MasterCard, & American Express include card# and exp. date. CA residents add 6% tax. Allow 2 weeks for clearance of personal & co. checks. Add $3.50 shipping & handling for continental U.S./$5.50 for UPS air. AK, HI, APO, FPO, CANADA add $7.50. Other Foreign orders add $8.50. All APO, FPO, & orders outside 48 states must be paid by certified U.S. funds. C.O.D.'s shipped to U.S. addresses only, add $4.00. School orders welcome.

DISKMAKER PAYS FOR ITSELF THE FIRST TIME YOU USE IT!

basix

1984

3463 State Street • Suite 1541S • Santa Barbara • CA 93105
Circle 301 on Reader Service card.

By JOE W. ROCKE

Video Jukebox

A rhapsody of color accompanied by a rinky-tinky tune can help drive your cares away when you play the C-64 Jukebox.

When you run the C-64 Jukebox, be prepared to relax. Colorful graphics characters begin filling each corner of the black display area. The first note of an easily recognizable theme song sounds. The background color changes, again and again, while the display continues to fill toward center screen, providing an ever-changing kaleidoscope of color and pattern.

In the screen's center, a message flashes, one word at a time—your C-64 is making like a jukebox of the near past.

The display continues changing even after it has filled the screen. New color patterns dance across the screen in perfect symmetry. No pattern will be repeated, no matter how long you let the program run! And the music continues playing in the background until you tire of it and turn the volume down.

Jukebox Program

The Jukebox program consists of an initializing subroutine, a routine that Pokes the color pattern to the display and a sound routine. In present form, the program provides hundreds of pattern changes without repetition. With minor changes, it would be possible to modify the program to provide a near-infinite number of patterns and color changes.

Upon execution, the program branches to the initialization subroutine. Following this, program flow jumps to the main program beginning at line 80. The subroutine for reading sound data has been placed near the beginning of the program to speed up program flow.

Regardless of where a subroutine is called from within a program, the flow jumps to the first line to begin the count to the subroutine. Although the time delay may be very small, it can cause a noticeable effect in programs of this type.

The initialization subroutine (lines 420–540) sets the variables used to produce the display and sound. Subscripted variables CL(0) through CL(7) provide the basis for the pattern display. All but two ASC subscript characters must be typed in as shifted characters.

Note that all but one ASC subscript variable has an attendant numerical value added to or subtracted from it. The numerical value provides a true lowercase character during program execution. This convention is necessary due to the manner in which the C-64 handles upper- and lowercase characters—just the reverse of most computers.

The SID (Sound Interface Device) registers are cleared in line 490. Values used to produce the musical tones are Poked to the primary sound registers in lines 500–530. The sound-producing routine is included in the main program.

Pattern Routine

Three loops are used to draw the kaleidoscope-like patterns on the display (lines 100–120). The loop values contribute to the constant changes in the pattern displayed.

The formula in line 130 is the heart of the program. This formula establishes the basis for all display-pattern character and color Pokes. Variable C becomes the character Poked to screen memory and is based on subscripted variables CL(n) plus current value of the loop variables.

Negative values for variable C can result if you make an error in typing in the ASC character values in lines 450–480. As a negative value will result in an error message, line 140 has been included to change a negative to a positive value, and thus avoid an error during program operation.

The four screen Poke locations are in lines 150–180. The color (variable X) to be Poked to color memory is established by the formula at the end of line 180. This formula uses character variable C and color variable T. As the value of variable C is constantly changing, so will the value of color variable X, which is Poked to color memory.

Pattern characters and their related color are Poked to screen and color memory in lines 190–260. You will notice that eight locations are Poked in sequence. The Pokes occur so rapidly that a character appears at the top, bottom, right and left side of the display almost simultaneously. The pattern begins at the four outer margins and fills toward the center of the display.

Line 360 accounts for the change in display background color during the startup cycle. If you are partial

RUN It Right

Commodore 64

KATHERINE MAHONEY

to a particular background color, lines 350 and 360 may be deleted. Be sure to include the background color of your choice in the initializing Poke of line 430.

Music Routine

The music routine used in the program is based on an example given in the *Commodore Programmer's Reference Guide*. The routine uses two voices and produces a "rinky-tinky" tune.

Sound Voice 1 provides the basis for the tune, with Voice 3 used for the tonal frequency. Filtering is used to cut off audio output of Voice 3 by Poking 143 to volume register 24.

The working portion of the sound routine (lines 270–330) follows the screen Pokes. A musical note is played after each series of screen Pokes. The musical note and its duration is based on the data beginning at line 550. Audio output is muted (line 330) after each note is played. The effect is musical accompaniment to each change in the display.



Data for the musical notes is read via the subroutine in lines 30–60 during each iteration of the loops in lines 100–120. While the display can continue until you hit the stop key, it would be impractical to include music data for a like period. Therefore, line 70 has been added to the subroutine to restore the data and replay it.

The Flashing Message

The flashing commercial-like message displayed center screen is purely optional. It does, however, demonstrate another facet of the program's potential for enhancement.

Words for the message are included with the music data and are read in at the same time via the sound subroutine. I am the first to admit that the words are pretty corny. But they demonstrate interesting possi-

Listing 1. *C-64 Jukebox program.*

```
1 REM ********************************
2 REM{1Ø SPACEs}C64 JUKEBOX
3 REM{15 SPACEs}BY
4 REM{11 SPACEs}JOE ROCKE
5 REM{9 SPACEs}RIDGECREST, CA
6 REM ********************************
1Ø GOSUB 42Ø
2Ø GOTO 8Ø
29 REM ****** SUBRINE ******
3Ø READ FR,DR,Z$
4Ø IF FR=-1THEN 7Ø
5Ø PRINT"{HOME}":POKE214,11:PRINT:PRINTTAB(
   18)"{CTRL 9}"Z$
6Ø RETURN
7Ø POKES+4,64:FOR Q=ØTO2ØØ:NEXT:RESTORE:GOT
   O 3Ø
79 REM ***** MAIN PROGRAM *****
8Ø PRINT"{SHFT CLR}":N1=1Ø24:N2=4Ø:N3=.625
9Ø N4=39.9999:T=Ø
1ØØ FOR W=3 TO 5Ø:GOSUB 3Ø
11Ø FOR I=1 TO 19:GOSUB 3Ø
12Ø FOR J=Ø TO 19:GOSUB 3Ø
13Ø K=I+J:C=CL((J*3/(I+3)+I*W/12)AND7)
14Ø IFC<ØTHENC=C*-1
15Ø Y1=N1+N2*INT(N3*I)
16Ø Y2=N1+N2*INT(N3*K)
17Ø Y3=N1+N2*INT(N3*(N4-I))
18Ø Y4=N1+N2*INT(N3*(N4-K)):X=C-(3Ø-T)
19Ø POKE I+Y2,C{3 SPACEs}:POKE (I+Y2)+CS,X
2ØØ POKE K+Y1,C{3 SPACEs}:POKE (K+Y1)+CS,X
21Ø POKE N2-I+Y4,C:POKE (N2-I+Y4)+CS,X
22Ø POKE N2-K+Y3,C:POKE (N2-K+Y3)+CS,X
23Ø POKE K+Y3,C{3 SPACEs}:POKE (K+Y3)+CS,X
24Ø POKE N2-I+Y2,C:POKE (N2-I+Y2)+CS,X
25Ø POKE I+Y4,C{3 SPACEs}:POKE (I+Y4)+CS,X
26Ø POKE N2-K+Y1,C:POKE (N2-K+Y1)+CS,X
269 REM ***** SOUND RINE *****
27Ø POKES+24,143:{2 SPACEs}REM- VOLUME
28Ø POKES+4,65:{4 SPACEs}REM- PULSE WF,VOIC
   E 1
29Ø FOR Q=1TODR*2: REM- DURATION LOOP
3ØØ FQ=FR+PEEK(S+27)/2
31Ø HF=INT(FQ/256):LF=FQ AND 255
32Ø POKES,LF:POKES+1,HF:NEXT
33Ø POKES+4,64:{4 SPACEs}REM- MUTE TONE
34Ø NEXT J
35Ø IF Z=Ø THEN 37Ø
36Ø POKE53281,Z:Z=Z+1:IF Z>15 THEN Z=Ø:POKE
    53281,Z
37Ø NEXT I
38Ø FOR Q=ØTO1ØØØ:NEXT:PRINT"{SHFT CLR}"
39Ø T=T+1:IF T=8 THEN T=Ø
4ØØ NEXT W
41Ø END
419 REM ***** INITIALIZATION *****
42Ø PRINT"{SHFT CLR}{2 CRSR DNs}"TAB(255)"C
   64 JUKEBOX":FORQ=ØTO15ØØ:NEXT
43Ø POKE5328Ø,Ø:POKE53281,Ø:DIM CL(7)
44Ø CS=54272:S=CS:Z=1
45Ø CL(Ø)=ASC(" ")+128:CL(1)=ASC("{COMD B}"
   )-64
46Ø CL(2)=ASC("{COMD +}")-64 :CL(3)=ASC("{S
   HFT V}")-128
47Ø CL(4)=ASC("+")-128:CL(5)=ASC("{SHFT B}"
   )-128
48Ø CL(6)=ASC("{SHFT C}")-128:CL(7)=ASC(" "
   )
49Ø FOR Q=S TO S+24:POKES,Ø:NEXT
5ØØ POKES+3,8 :{4 SPACEs}REM - HI PULSE VOI
   CE 1
51Ø POKES+5,41:POKES+6,89:{3 SPACEs}REM- AT
   K/SUS
52Ø POKES+14,117:{2 SPACEs}REM- LF VOICE 3
53Ø POKES+18,16 :{2 SPACEs}REM- WF VOICE 3
54Ø RETURN
549 REM ****** SOUND DATA ******
55Ø DATA 4817, 2,"{COMD +} {COMD +} {COMD +
   }",51Ø3, 2,"PLAY "
56Ø DATA 54Ø7, 2,"{2 SPACEs}A{2 SPACEs}",85
   83, 4,"RINKY"
57Ø DATA 54Ø7, 4,"D", 8583,12,"B",9634,2,"T
   "
58Ø DATA 1Ø2Ø7,2,"TUNE ",1Ø814,2,"{SHFT V}
   {SHFT V} {SHFT V}",8583,2,"{5 SPACEs}"
59Ø DATA 9634, 4," AND ",1Ø814,2,"PLACE",85
   83,2,"YOUR "
6ØØ DATA 9634, 4,"NOTES",8583,12,"HERE ",85
   83,Ø,"HERE{SHFT SPACE}"
61Ø DATA -1,-1,-1,"{SHFT A}{SHFT S}{SHFT W}
   {SHFT S}{SHFT A}"
```

bilities in coining words by just changing one letter.

I used quote marks to identify each word or graphics display group simply because I wanted to maintain the same print location for each combination.

Customizing Encouraged

You can easily personalize your version of the C-64 Jukebox. But first, type in the program and save it to tape or disk. From that point on, you can customize the program to provide a variety of effects in the display and attendant music. You can create a new flashing message or leave out that feature altogether.

For example, you can change the display effects by using different graphics symbols (or even letters) in variable CL ASC subscripts. A word of caution in doing so: Be sure to include the proper lowercase numerical value if you use an unshifted character.

For a tune of your choice, substitute your own data for the data included in the program listing. Refer to the *Commodore Programmer's Reference Guide* for details on converting a musical score to numerical data for the notes. If you can read music, simply translate the notes to data using the decimal data in Appendix M of the *User's Guide.*

To eliminate the flashing message, delete variable Z$ in line 40 and delete line 50. And, of course, leave the words out of the music data group. Should you elect to include a personalized commercial, just make sure there is a word, or equivalent string data, for each musical note.

To get started on customizing ideas, how about a Happy Birthday theme? Background screen color can be of your choice. The musical score could be the tried and true "Happy Birthday," with a personalized flashing birthday message.

The ideas for customizing the C-64 Jukebox are limited only by your imagination. While I am the first to admit this is a do-nothing program, it is also one of the most peaceful I have ever run. It makes no demands on you and provides a thoroughly enjoyable visual experience. Type it in and let it become your programming break! R

Address all author correspondence to Joe W. Rocke, 224 W. Benson Road, Ridgecrest, CA 93555.

Circle 162 on Reader Service card.

Wordlearn $14.95 PSAT, SAT, GRE

* A great way to study for the SAT, PSAT, or GRE vocabulary sections. * Over 4,000 words. * True Computer Aided Instruction; if you put the time in, you will be confident about maximizing test scores. * Much cheaper than most classroom preparations. * 24 hr nationwide service hotline. * Returnable up to 30 days after purchase. * A set of 5 double sided disks (worth nearly $14.95 for the disks alone). * Extensive online help. * Changing. Speech upgrades will be available this summer for $16.95 (plus S&H; no accessories required). * From the Consumer Software Division of Franklin Engineering.

Send $14.95 (plus $2.50 S&H, Maryland Residents add 5% sales tax of $.75) to Consumer Software Division, Franklin Engineering, P.O. Box 22661, Baltimore, Md 21203. COD orders: (301) 889-6366, add $2.00. 2nd Day Air add $2.00.

New Technological Breakthrough!

ULTRABYTE DISK NIBBLER

The Ultimate Bit by Bit Disk Duplicator
For The Commodore 64 and 1541 Disk Drive

ULTRABYTE DISK NIBBLER COPIES ALL SOFTWARE EXCEPT ITSELF

SATISFACTION GUARANTEED

Return for refund within 10 days
if not completely satisfied

$ 39.95
Introductory Price

plus $ 3.00 Shipping and Handling
MASTERCARD, VISA, CHECK, or M.O.,
Foreign Orders or COD Add $ 2.00
Calif. Add 6.5 % ($ 2.60) Sales Tax
BACKUP COPIES $ 20.00 PLUS $ 3.00 SHIPPING

Based on new proprietary Disk Operating System (DOS) that reads and writes bits on the disk independent of format. This process, called nibbling, treats disk errors, extra sectors, renumbered tracks and other protection schemes exactly the same as ordinary data.

- Simple to use. Just load and run
- Fast. Copies entire disk on single 1541 in 8 minutes
- One easy step. No separate analysis or error production
- Uses revolutionary Track Scan Technology to make an exact replica of the original disk.

Write or Call 24 Hour Order Line

ULTRABYTE (818) 796 - 0576
P.O. Box 789 La Canada, CA 91011

SOFTWARE AUTHORS PLEASE WRITE

This program helps you keep your guitar in tune. But it's up to you to strum the right strings.

Picking the Right Sounds

By MICHAEL and JEFFREY GOLLER

Many different ways have been developed to tune the guitar, but most involve expensive tone generators or inaccurate pitch pipes.

This program, Guitar Tuner-64, turns your Commodore 64 computer into a sophisticated guitar tuner. The program uses the SID (sound interface device) chip, found deep in the heart of the C-64, to produce a perfect pitch every time. This is one guitar tuner that will never go out of tune.

The guitar's strings (in order from thickest to thinnest string) are named E, A, D, G, B and E (octave). These strings must be tuned to the following frequencies (in cycles per second) to be considered in tune: 82.407(E), 110.00 (A), 146.83(D), 196.00(G), 246.94(B), 329.63(E octave). Because of the way that the Commodore 64 produces music, you can get these tones perfect every time without ever having to readjust the computer.

To use the program, carefully type in the program and, before running it, save it. When you are finished, type RUN and press the return key.

The screen on your monitor will clear and you will see the title "Guitar Tuner" and the message "Please Stand By." In a few moments, you will see the neck of a guitar being drawn on the screen. At the top of the neck is the head of the guitar with the tuning pegs. Above each string is displayed the string's name. At the bottom of the string is a set of instructions for using the tuner.

Before you tune the guitar, tighten all six strings to a medium tightness. Do not change any of your strings once you've begun the tuning process or you'll throw off the pitch of those already tuned.

To tune your guitar, first make sure that the volume on your monitor or television set is turned up. Now press the E key on the keyboard. If you typed in the program correctly, you will now hear the pitch to which you should tune your thickest string. Simply tighten or loosen the string so that the tones match. There will be an arrow under the string that you are tuning, to remind you which string you are working on. Also, the letter at the top of the string will be highlighted.

After the first string is tuned, simply hit the A key, and the pitch will now change so that you can tune the second string. If at any time you wish the program to be silent, hit the space bar. The sound will stop until you hit another key. Also, by pressing the space bar, you can go to any string in any order, even if you have already silenced the program.

To produce the tone for the sixth (and thinnest) string, you must hold down the shift key and then press the E key. This tone will be exactly one octave above the low E (first) string.

To exit and end the program at any time, simply hold down the CTRL key and press the X key.

If you would rather not type in the program by hand, mail us $3, a blank cassette or disk and an appropriate self-addressed stamped mailer, and we'll send you a copy of the program. We'd also like to hear your comments and suggestions about the program. R

Address all author correspondence to Jeffrey Goller, 3431 Telford #2, Cincinnati, OH 45220.

RUN It Right

Commodore 64
Datassette



PHIL GERACI



Listing 1. *Guitar Tuner-64 program.*

```
1 REM{5 SPACEs}"GUITAR TUNER"
2 REM{4 SPACEs}"BY JEFFREY AND MICHAEL GOLL
  ER"
3 REM{3 SPACEs}"JUNE, 1984 "
5 PRINT"{CTRL 8}{SHFT CLR}"
8 PRINT"{5 CRSR DNs}{26 CRSR RTs}GUITAR TUN
  ER"
9 REM{4 SPACEs}LINE 8 = DOWN 5, RIGHT 26
6Ø POKE 5328Ø,Ø:POKE 53281,Ø
61 FOR A = 1224 TO 1238
62 READ A8:POKE A ,A8
63 NEXT
7Ø REM SET VALUES
71 B =1Ø24:I=66
72 V=53248:PV=1964
78 :
81 :
82 :
83 REM DRAW STRINGS
84 E=Ø
85 FOR W=55296TO 56Ø96:POKEW,7:NEXT
9Ø FORJ=1 TO 11
95 FOR L= 1356 TO 1361
97 POKE L+E ,I
1ØØ NEXT L
1Ø1 E=E+4Ø
1Ø2 NEXTJ
12Ø :
14Ø :
15Ø :
151 REM{3 SPACEs}DRAW HEAD OF GUITAR
2ØØ FOR A5= 1224 TO 1238:POKE A5,32:NEXT
2Ø8 BB=Ø
21Ø FOR T=1 TO 6
214 FOR AA= 1115 TO 1122
216 POKE AA + BB,224
218 NEXT AA
22Ø BB=BB+4Ø
222 NEXT T
225 FOR HH=1 TO 2Ø
227 READ H1:READ H2:POKEH1,H2
229 NEXT HH
26Ø FORT=1Ø75TO1Ø82:POKET,224:NEXTT
29Ø FOR C2= 56Ø56 TO 56Ø96:POKEC2,1:NEXT
3ØØ FOR W= 55558 TO 55575:POKEW,14:NEXT
3Ø1 FOR X= 56236 TO 56255:POKEX,1:NEXT
3Ø2 :
3Ø3 :
3Ø4 :
4Ø3 REM BEGIN MUSIC
5ØØ FOR L=54272 TO 54296:POKEL,Ø:NEXT:{2 SP
    ACEs}POKE 54296,15
51Ø POKE 54277,Ø:POKE 54278,128:REM ADSR
511 POKE 54284,Ø:POKE 54285,128:REM ADSR
514 PRINT"{12 CRSR DNs}":REM (12 DOWN)
52Ø PRINT"{CTRL 6}PRESS KEYS FOR NOTES{2 SP
    ACEs}E,A,D,G,B,E(SHIFT)"
53Ø PRINT"PRESS SPACE BAR TO STOP NOTE"
531 PRINT"{CTRL 3}CONTROL X TO EXIT"
545 FOR X= 1 TO 6:READ X2:READX3:POKEX2,X3:
    NEXT
55Ø :
56Ø :
57Ø :
571 C=55599
6ØØ GET A$:IF A$=""THEN 6ØØ
6Ø1 POKE PV,96:POKEC,7
61Ø IF A$="E"THEN LF=5:HF=71 :PV=1796:C= 55
    588
62Ø IF A$="A"THEN LF=7:HF=12 :PV=1797:C= 55
    589
63Ø IF A$="D"THEN LF=9:HF=1Ø4:PV=1798:C= 55
    59Ø
64Ø IF A$="G"THEN LF=12:HF=143:PV=1799:C= 5
    5591
65Ø IF A$="B"THEN LF=15:HF=21Ø:PV=18ØØ:C= 5
    5592
66Ø IF A$="{SHFT E}"THEN LF=21:HF=31 :PV= 1
    8Ø1:C= 55593:REM SHIFT E
67Ø IF A$=" "THEN LF=Ø:HF=Ø:PV=1964:{4 SPAC
    Es}C=55599
671 IFA$="{CTRL X}"THEN8ØØ:REM "CONTROL X"
68Ø POKEPV,3Ø
681 POKEC,14
7ØØ POKE 54272,HF:POKE 54273,LF
7Ø1 POKE 54279,HF:POKE5428Ø,LF
7Ø9 POKE 54282,15:POKE 54281,1
71Ø POKE 54276,33 :POKE 54283,65
75Ø GOTO 6ØØ
8ØØ PRINT"{SHFT CLR}":FORL = 54272 TO 54296
    :POKEL,O:NEXT
9ØØ :
9Ø1 :
9Ø2 :
99Ø DATA 16,12,5,1,19,5,32,19,2Ø,1,14,4, 32
    ,2,25
1ØØØ DATA 1315,95,1322,1Ø5,1116,215,1196,21
    5,1276,215,1121,215,12Ø1,215
1Ø1Ø DATA 1281,215,1114,67,1194,67,1274, 67
    ,1123,67,12Ø3,67
1Ø2Ø DATA 1283,67,1113,224,1193,224,1273,22
    4,1124,224,12Ø4,224,1284,224
2ØØØ DATA 1316,133,1317,129,1318,132,1319
2Ø1Ø DATA 135,132Ø,13Ø,1321,133
```

WE'RE PROUD OF OUR PRICES!

commodore
NEW
1101 LETTER QUALITY PRINTER
274.95



NEW
commodore
128
IN STOCK
279.95



commodore
1702 MONITOR
174.95

commodore
1541 DISC DRIVE
159.95

ALL CARDCO PRODUCTS IN STOCK & ON SALE!

commodore 64
149.95



NEW! MSD SUPER DISC II NOW ON SALE
459.95
Single Drive 249.00





Modems

Comm 1660	99
Mighty Mo	Call
Telesonic	Call
Hes II	Call

Interfaces

Cardco G +	Call
Microworld	Call

Cassette Recorders

Comm CN-2	59.95
Third Party	39.95

Monitors

BMC Color	169.95
Pan 1300 RGB & Comp.	289.95
BMC Green	69.95

Printers

Gemini SG 10/15 New!	209.95
Gemini SD 10/15 New!	Call
Gemini SR 10/15 New!	Call
Gemini SB 10 New!	Call
Gemini 15X	399.95
Silver Reed 400	249.95
Silver Reed 500	379.95
Brother 15X	379.95
Brother 25X	514.95
Juki 6100	399.95
Blue Chip with Interface	219.95

Diskettes

BASF	13.95
Scotch	14.95
Maxell	14.95
Polaroid	13.95

TOUCH TABLETS

Koala Touch Tablet–D	64.95
Koala Touch Tablet–Cart	69.95
Muppet Learning Keys	Call

ACCESS

Neutral Zone–D/T	20.95
Spritemaster–D/T	20.95
Beachhead–D/T	20.95
Master Composer–D	23.95

SPINNAKER

Adventure Creator–Cart	21.95
Aerobics–D	25.95
Aegean Voyage–Cart	21.95
All in the Color Caves–C	21.95
Alphabet Zoo–Cart	20.95
Bubble Burst–Cart	21.95
Cosmic Life–Cart	20.95
Delta Drawing–Cart	21.95
Facemaker–Cart	20.95
Fraction Fever–Cart	20.95
Grandma's House–D	20.95
Jukebox–Cart	20.95
Kids on Keys–Cart	20.95
Kidwriter–D	20.95
Kindercomp–Cart	17.95
Ranch–Cart	20.95
Rhymes/Riddles–D	17.95
Search/Amazing Thing–D	24.95
Snooper #1–D	24.95
Snooper #2–D	24.95
Story Machine–Cart	20.95
Trains–D	24.95
Up For Grabs–Cart	20.95

COMMODORE

Program Ref. Guide	19.95
Assembler–D	17.95
Easy Finance I,II,III,IV–D	19.95
Easy Calc–D	64.95
Easy Mail–D	17.95
Easy Script–D	39.95
Easy Spell–D	19.95
Logo–D	49.95
The Manager–D	37.95

NEW!

commodore
Products

801 MCS Color Printer	269.95
C-16 Computer	79.95
C+4 Computer	189.95
801 Printer	149.95
802 Printer	179.95
803 Printer	174.95

General Ledger–D	37.95
Acct. Rec–D	37.95
Accts. Pay–D	37.95
Magic Desk–D	52.95
Zork I, II or III–D	29.95
Suspended–D	29.95
Starcross–D	29.95
Deadline–D	29.95

CBS SOFTWARE

Argos Expedition–D	29.95
Charles Goren's Bridge–D	49.95
Coco Notes–D	19.95
Ducks Ahoy–D	23.95
Ernie's Magic Shapes–D	23.95
Mastering the SAT–D	104.95
Movie Musical Madness–D	24.95
Murder by the Dozen–D	23.95
Peanut Butter Panic–D	24.95
Sea Horse Hide 'n Seek	24.95
Success Decimals (Add/Subt)–D/T	14.95
Success Decimals (Mult/Div)–D/T	14.95
Success Fractions (Add/Subt)–D/T	14.95
Success Fractions (Mult/Div)–D/T	14.95
Timebound–D	24.95
Webster Word Game–D	24.95

ACCESSORIES

WICO Joysticks	Call
Flip 'n' File–D	20.95
Flip 'n' File–Cart	20.95
Joysensor	Call
WICO Trakball	37.95
KRAFT Joystick	15.95

18 years of reliable service in:
Plainview, Syosset, New Hyde Park, West Hempstead, Huntington, Patchogue

TO ORDER CALL TOLL FREE
IN NY STATE CALL TOLL FREE
1-800-221-2760 OR 516-249-2120

1-800-631-1003

Check, Money Order, MC or VISA accepted / No additional charge for MasterCard and Visa / Call for shipping and handling information / NYS residents add applicable sales tax / Prices and availability are subject to change without notice / All factory fresh merchandise with manufacturer's warranty / Prices & policy may vary in retail stores. Dealers Welcome.

Price reductions may have been made since this ad was placed. Call us for our latest price quotes.

*Call for recent price reductions and new rebate information

VISA
MasterCard

COMPUTER CENTERS OF AMERICA

31 East Mall Plainview NY 11803

Teacher's Pet

By FRANK COLOSIMO

This educational program generates worksheets that parents and teachers can use to help students practice their basic arithmetic skills.

This program produces math worksheets with one- to three-digit addition or subtraction problems or one- or two-digit multiplication problems. Six rows of seven problems each are placed on a standard 8½- × 11-inch sheet of paper. The answers are printed near the bottom of the sheet in six closely spaced rows.

For addition and subtraction, you must specify whether you want carrying or borrowing in the problems. Numbers are generated randomly, but for single-digit problems, you may specify the maximum number to appear in the problems. These options have been selected to allow worksheets to be produced with varying levels of difficulty for kindergarten through grade three.

Equipment Requirements

The program works with the Commodore 64, the VIC-20 (any memory), the Plus/4 and the C-16. I developed the program using a Star Gemini 10X printer with Tymax's The Connection interface in the Commodore 1525 Emulation mode. It also works with the Commodore 1525, 1526, the Smith-Corona TP-1 (daisywheel) and the Epson MX-80. Although double-width printing is not supported on a daisywheel printer, acceptable worksheets are produced.

Since it is impossible to test a program like this on all printers, I used features that would ensure compatibility with a variety of equipment. For instance, to locate the numbers on the paper, I used only the SPC function, since the Tab function differs from one printer to another.

If you do not have a Commodore printer (or another printer that simulates one), try the program anyway. If it does not work, the suggestions given below should provide the information you need to get it working properly.

For Non-Commodore Printers

If the program is not producing nicely formatted worksheets on your printer, you may need to make changes in lines 30, 50 and 60.

Line 30 contains the Open statement. Modify this if your interface requires a non-zero secondary address to simulate a Commodore printer (for example: OPEN 1,4,2).

Lines 50 and 60 contain the commands to turn double-width characters on and off. This produces characters of ideal size for young people to work with. Use the appropriate values for your printer, as found in the printer manual.

For the Gemini 10X, with a standard serial-to-parallel interface where there is no emulation of the Commodore printer, use CHR$(14) for UN$ (double-width on) and CHR$(20) for OFF$ (double-width off). If your machine does not support double-width characters, you may need to use null values (UN$ = "" and OFF$ = "").

With these null values, the worksheet will not be spaced as nicely across the paper, but will be completely usable. The rest of the program shouldn't require any modification if your printer is working properly with your computer.

How to Use It

There are five screen prompts you must answer before producing a worksheet:

1. *Operation*—Select addition, subtraction or multiplication.
2. *Number of digits*—Select 1–3 for addition or subtraction or 1 or 2 for multiplication.
3. *Carrying/borrowing*—For addition

RUN It Right

C-64, VIC-20, Plus/4, C-16; printer

NAME: _____

MATH WORKSHEET

87	59	88	36	52	64	73
+11	+10	+11	+62	+25	+33	+16
37	63	46	48	29	97	66
+11	+24	+31	+11	+10	+ 1	+13

or subtraction, you must specify whether you desire carrying or borrowing in the problems.

4. *Highest digit*—For single-digit problems, this prompt will appear. Select the largest number that you want in the problem digits.

5. *Answers*—If you want answers printed on the bottom of the worksheet, enter Y in response to this question. The answers are positioned so that they can be easily torn off (or folded over, if you trust your student).

Program Description

Several program features are worth mentioning.

I used the random-number function (RND) to generate the digits for the problems. It is employed in such a way as to avoid the selection of the numbers 1 and 0 where possible. This results in fewer overly simple problems appearing on the worksheet.

I adjusted the vertical spacing to provide exactly 11 inches of paper travel per worksheet. If your printer uses the standard $^1/_6$ of an inch linefeeds, you will be able to produce a continuous series of worksheets on fanfold paper, with the horizontal perforations properly spaced between the worksheets.

I tried to document the program with plenty of REM statements and to make use of subroutines for most functions. This should allow easy customization of the program, if desired. You may omit the REM statements if you want to save a little typing time.

If you would like a copy of the program and do not want to do the typing, send me $5 with your name and address and specify whether you want VIC, 64, Plus/4 or C-16, and whether you want disk (1541 format) or tape (VIC/64 format). R

Address all author correspondence to Frank Colosimo, 112 Shoreway Drive, Rochester, NY 14612.

Listing 1. *Commodore Math Worksheet program.*

```
10 REM MATH WORKSHEET BY F. COLOSIMO
30 OPEN1,4{3 SPACEs}:REM USE APPROP. CMD FO
   R YOUR PRINTER/INTERFACE
50 UN$=CHR$(14):REM THIS CMD TURNS ON DBL W
   IDTH
60 OFF$=CHR$(15): REM THIS TURNS OFF DBL WI
   D.
70 DI$="(1-3)":X=0:POKE53280,0:POKE53281,12
80 DIMA%(28),B%(28),A$(7),B$(7),N1%(28),N2%
   (28),AN%(42)
90 PRINT"{CTRL 1}{SHFT CLR}{CRSR DN}{4 SPAC
   Es}******* MATH WORKSHEET *******":PRINT
   "{2 CRSR DNs}{2 SPACEs}POSITION PAPER NO
   W "
100 PRINT"{4 SPACEs}WITH PERF AT PRINTHEAD.
    ..{CRSR DN}"
120 PRINT"{CRSR DN}{3 SPACEs}DO YOU WANT AD
```

Circle 274 on Reader Service card.

Re-ink any fabric ribbon AUTOMATICALLY for less than

5¢

Mac Inker

Extremely simple operation, with built in electric motor. We support over 750 types of printers - cartridge, spool, harmonica, or zip pack type. Most MAC INKER(s) cost less than $60.00. (Add $3.00 for UPS shippping anywhere in the US).

Use your MAC INKER to re-ink your dry cartridges (for less than 5 cents in ink) and watch the improvement in print-out quality. Our residue-less, lubricated, dot-matrix ink yields a darker print than most new ribbons. Or get any of our 6 basic ink colors: brown, blue, red, green, yellow, purple and use MAC INKER to CREATE YOUR OWN COLORED CARTRIDGES. We have uninked cartridges. Load the cartridge on MAC INKER, ink in the desired color, and re-ink when appropriate.

Most cartridges can be used almost indefinitely, if ribbon is regularly re-inked, kept moist and lubricated so that the fabric does not fray. Some customers have reported 80 re-inkings of the same cartridge.

As of February 85, we have over 30,000 MAC INKER(s) in the field, in 5 continents (220V motors available). MAC INKER has been reviewed, approved and flattered in most magazines and even in the NEW YORK TIMES and the CHICAGO SUN TIMES.

Order toll free 1-800-547-3303
or ask for free, detailed brochure. Dealers inquiries welcome.

Computer Friends
6415 SW Canyon Court
Suite #10
Portland, Oregon 97221
(503) 297-2321 (24 hour line)

Listing 1 continued.

```
    DITION,SUBTRACTION{8 SPACEs}OR MULTIPLI
    CATION?(+,-,X)
130 GETO$:IFO$=""THEN130
140 PRINTSPC(6)"{CTRL 3} OPERATION = {CTRL
    1}"O$
150 IFO$="X"THEND1$="(1-2)":GOTO170
160 IFO$<>"+"ANDO$<>"-"THEN120
170 PRINT"{CRSR DN}{2 SPACEs}HOW MANY DIGIT
    S DO YOU WANT?"D1$
180 GETD$:IFD$=""THEN180
190 D=VAL(D$):IFD<1ORD>3THEN170
200 IFD>2ANDO$="X"THEN170
210 PRINTSPC(6)"{CTRL 3} PROBLEMS WILL HAVE
     "D"DIGITS{CTRL 1}"
220 IFD=1ORO$="X"THENCA$="Y":GOTO270
230 PRINT"{CRSR DN}{2 SPACEs}DO YOU WANT CA
    RRYING/BORROWING? (Y/N)"
240 GETCA$:IFCA$=""THEN240
250 IFCA$<>"Y"ANDCA$<>"N"THEN230
260 PRINTSPC(7)"{CTRL 2} CARRY/BORROW = {CT
    RL 1}"CA$
270 IFD>1THENAA=9:GOTO310
280 PRINT"{CRSR DN} WHAT IS THE HIGHEST NUM
    BER YOU WANT IN{2 SPACEs}THE PROBLEMS?
    (1-9)"
290 GETAA$:IFAA$=""THEN290
300 AA=VAL(AA$):IFAA<1THEN280
310 PRINTSPC(4)"{CTRL 3} HIGHEST NUMBER IN
    PROBLEMS ={CTRL 1}"AA
320 PRINT"{CRSR DN} DO YOU WANT ANSWERS ON
    WKSHT? (Y/N)"
330 GETAN$:IFAN$=""THEN330
340 GOSUB960:REM{2 SPACEs}PRINT TITLE
360 FORM=1TO6
370 GOSUB490:GOSUB810:NEXTM:AS=D
380 IFAN$<>"N"THEN410
390 FORN=1TO3:PRINT#1,CHR$(13):NEXT:GOTO430
410 FORN=1TO6:PRINT#1,OFF$SPC(1+AS);:FORM=1
    TO7:DU=AN%((N-1)*7+M):D=10:GOSUB920
420 PRINT#1,DU$;:NEXT:PRINT#1:NEXT
430 PRINT#1,CHR$(13)CHR$(13):CLOSE1
440 PRINT"{SHFT CLR}{CRSR DN}WOULD YOU LIKE
     TO MAKE ANOTHER WORKSHEET?(Y/N)"
450 GETC$:IFC$=""THEN450
460 IFC$="Y"THENRUN
470 END
490 FORN=1TOD*7:A%(N)=(AA-1)*RND(0)+2:NEXT
500 IFCA$="N"ANDO$="+"THEN570
510 FORN=1TOD*7:B%(N)=AA*RND(0)+1:NEXT
520 IFO$<>"-"THEN630
540 FORN=1TOD*7:IFA%(N)<B%(N)THENC%=A%(N):A
    %(N)=B%(N):B%(N)=C%
550 NEXT:GOTO580
570 FORN=1TOD*7:B%(N)=RND(0)*(9-A%(N))+1+(A
    %(N)=9):NEXT
580 IFCA$="N"THEN630
600 FORN=1TOD*7STEPD:C%=A%(N):A%(N)=B%(N):B
    %(N)=C%
610 NEXT
630 FORN=1TO7:PL=0:N1%(N)=0:N2%(N)=0
640 FORNN=D*(N-1)+1TO(N-1)*D+D
650 N1%(N)=N1%(N)+A%(NN)*10{UP ARROW}PL
660 N2%(N)=N2%(N)+B%(NN)*10{UP ARROW}PL:PL=
    PL+1:NEXT
670 IFO$<>"-"THEN710
690 IFN1%(N)<N2%(N)THENC%=N1%(N):N1%(N)=N2%
    (N):N2%(N)=C%
710 X=X+1
720 IFO$="+"THENAN%(X)=N1%(N)+N2%(N)
730 IFO$="-"THENAN%(X)=N1%(N)-N2%(N)
740 IFO$="X"THENAN%(X)=N1%(N)*N2%(N)
750 NEXT
770 FORN=1TO7:DU=N1%(N):GOSUB920:A$(N)=DU$
780 DU=N2%(N):GOSUB920:B$(N)=DU$:NEXT:RETUR
    N
810 L=LEN(A$(1)):PRINT#1,UN$SPC(4);:FORN=1T
    O7
820 PRINT#1,UN$" "A$(N)SPC(4-L);:NEXT
840 PRINT#1,CHR$(10):PRINT#1,UN$SPC(4);
850 FORN=1TO7:PRINT#1,UN$O$B$(N)SPC(4-L);:N
    EXT
870 PRINT#1:PRINT#1,UN$SPC(4);:FORN=1TO7
880 FORNN=0TOL:PRINT#1,"-";:NEXT:PRINT#1,UN
    $SPC(4-L);:NEXT
890 PRINT#1,CHR$(10)CHR$(10)CHR$(10)CHR$(10
    )
900 RETURN
920 DU$=STR$(DU)
930 IFLEN(DU$)<D+1THENDU$=" "+DU$:GOTO930
940 DU$=RIGHT$(DU$,D):RETURN
960 PRINT#1,CHR$(13)CHR$(13)
970 PRINT#1,UN$SPC(18)"NAME:":PRINT#1,UN$SP
    C(23)"----------"
980 PRINT#1,CHR$(10)UN$SPC(12)"MATH WORKSHE
    ET"CHR$(13)CHR$(13):RETURN
```

Circle 8 on Reader Service card.

Break the BASIC language barrier

VIDEO BASIC-64 — add 50+ graphic and sound commands to your programs with this super development package. You can distribute free RUNTIME version without paying royalties! **$59.95**

BASIC COMPILER-64 — compiles the complete BASIC language into either fast 6510 machine language and/or compact speedcode. Get your programs into high gear and protect them by compiling. **$39.95**

MASTER-64 — professional development package for serious applicants. Indexed file system, full screen management, programmer's aid, BASIC extensions, 100 commands. **$39.95**

PASCAL-64 — full Pascal with extensions for graphics, sprites, file management, more. Compiles to 6510 machine code and can link to Assembler/Monitor routines. **$39.95**

ADA TRAINING COURSE — teaches you the language of the future. Comprehensive subset of the language, editor, syntax checker/compiler, assembler, disassembler, 120+ page guide. **$59.95**

FORTRAN-64 — based on Fortran 77. Common, Data, Dimension, Equivalence, External, Implicit, Goto, Else If, Do, Continue, Stop, Subroutine, Call, Write, Read, Format, more. April 1985 **$39.95**

C-LANGUAGE COMPILER — a full C language compiler. Conforms to the Kernighan & Ritchie standard, but without bit fields. Package includes editor, compiler and linker. April 1985 **$79.95**

Other titles available: Write or call:

PHONE: (616) 241-5510

For postage and handling include $4.00 ($8.00 foreign) per order. Money order and checks in U.S. dollars only. mastercard, VISA and American Express accepted. Michigan residents incl 4% sales tax.

Abacus Software

P.O. Box 7211 Grand Rapids, MI 49510

FAST DELIVERY

Call Us For
Fast Service, Experience
and Affordable Prices

Software

SPRING SPECIAL

SUBLOGIC
Flight Simulator
$31.95
MICROPROSE
F-15 EAGLE
$21.95

MICROLEAGUE
Baseball.....29.95

INFOCOM
Zork I, II, III...ea. $25
Suspended $25
Starcross..... $25
Deadline..... $25
Sea Stalker..... $25

WORD PROCESSING

Special of the Month
FLEET SYSTEM 2
Great Buy $55

Easy Script $45
Paper Clip w/speller..... $69
EZ Spell..... $17

PROGRAMMING SERIES

Assembler 64 ..... $36
Logo $52
Simon Basic $27
Borland Pascal..... $42
Nevada Fortran..... $39
Nevada Cobol..... $39

ACCOUNTING

Home Accountant..... $44
Tax Advantage..... $45
General Ledger..... $35
A/R, A/P, Payroll..... $35
The Manager..... $35

DATA BASES

Consultant..... $64
Mirage Database Mgr. $79
Super Base 64 ..... $54

Special of the Month
PFS FILE
$59.00

SPREAD SHEET

Multiplan..... $63
Practicalc $38

Hardware

1541 $189

Special of the Month
MSD DISK DRIVE
SD1 Disk Drive $244
SD2 Disk Drive $444

Introductory Offer
INDUS GT
DISK DRIVE
$269

ELEPHANT DISK
SS/SD $15.50 SS/DD $16.50

Special of the Month
LORAN SS/DD
$12.95 Box of 10

NEW.....FAST
1660 MODEM
$84

SX-64 Computer..... $459
MPS 802..... $214
1530 Datasette..... $59
Magic Voice Speech..... $49.95
1011 RS 232 Interface..... $49

1702 Monitor
$189

ZENITH MONITORS
122 Amber $84
123 Green $84

COMPUTER COVERS



Features heavy duty canvas with vinyl interior - waterproof.

Reg. $15.95
$6.99

CMD 64 ..... $6.99
VIC 20 ..... $6.99
Disk Drive..... $6.99
Espon MX 80.... $7.99
Espon MX 80 FT $7.99
Okidata 92 ..... $7.99

Printers

GEMINI 10X
$219



15X..... $339

Number one selling dot matrix printer, Gemini 10X, prints 120 cps bi-directionally, with logic-seeking printerhead control. There's both friction and tractor paper feed. Prints high resolution graphics.

Letter Quality Powertype $325

NEW SG-10, SG-15, SR-10, SR-15 IN STOCK, CALL FOR PRICES

EPSON RX80
$219



LX80..... $299

Dot matrix printer with NLQ mode, prints 100 cps, bi-directionally. Call for RX-100, FX-80 and FX-100 prices.

Special Offer
MW-350..... $69
4K Buffer..... $29

Digital Devices
U Print Interface $59
16K Printer Buffer.. $99
64K Printer Buffer $169
Epson 80 Ribbon..... $5

Okidata 92..... $349
Okidata 93..... $579
Okidata 84..... $649
Okidata 182 ..... Call
Okidata Ribbons $3
Juki 6100..... $389
Silver Reed 400... $249
Silver Reed 500... $379

PRINTER INTERFACES
Micrografix MW350 ..... $69
Tymac Connection $79
Cardco + G Interface $64
Cardco B Interface $39
Grappler CD $102

SURGE PROTECTORS
1 Outlet $14
4 Outlet $38
6 Outlet $69
6 Outlet &
Noise Filter..... $88

Ordering & Payment Policy

Prices reflect a cash discount. For Visa, and Mastercard add 3% Immediate delivery with certified check or wired funds. N.J. resident add 6%. Prices subject to change.

Shipping

For shipping and handling add 3%. ($3 minimum) Larger shipments require additional charge. C.O.D. add $3.50

PANASONIC

1090 ..... $199
1091 ..... $269
1092 ..... $Call

Printer Specials

Doodle..... $26
Print Shop..... $29
Paper 1000 sheets $19.95
Paper 2500 sheets $34.95

FOR INFORMATION CALL (609) 596-1944

ORDER TOLL FREE (800) 992-3300

PC GALLERY

P.O. Box 3354
Cherry Hill, N.J. 08034

Easy Assembly

By WILLIAM B. SANDERS

Finally, here's an easy-to-understand tutorial on assembly language. By the end of this series, you'll be programming with consummate skill.

One of the most intimidating, yet fascinating, challenges in programming your Commodore 64 is tackling assembly language. However, once you understand it, you'll not only find it to be fun, you'll find it a lot simpler than you imagined. (Remember how difficult Basic seemed when you first ventured into it?)

The best way to get started is to jump right in. Using a Basic program, we'll write an assembly language program. It will be simple and direct, and it will do something you can see immediately.

```
10 FOR X = 49152 TO 49157
20 READ OP : POKE X, OP
30 NEXT X
40 DATA 169,2,141,33,208,96
```

Leaving your Basic program in memory, enter SYS 49152. Your background color should have turned red, but you should have no idea why.

Now, let's see what happened. You know you Poked the values in line 40 into the consecutive addresses of 49152–49157. Here's what those addresses would look like if you Peeked into them:

49152	169
49153	2
49154	141
49155	33
49156	208
49157	96

That's a lot clearer, right? Wrong! Unless you already know machine language, that list looks like a random collection of numbers. Let's see what they mean.

First of all, the values from 49152–49157 are consecutive addresses in memory. For the moment, think of them as line numbers in Basic. The values next to the "line numbers" are either commands, values or addresses.

Secondly, let's translate the encoded command values into something clearer.

49152	LDA
49153	2
49154	STA
49155	33
49156	208
49157	RTS

The fundamental ingredients in assembly language are opcodes and operands. The alphabetic codes (opcodes) in the above example are mnemonics, designed to make it easier to remember their meanings. The three in the example have the following meanings:

LDA means LoaD the Accumulator
STA means STore the Accumulator
RTS means ReTurn from Subroutine

In Basic, the same thing might look like this:

```
10 A=2
20 POKE 53281,A: REM BACKGROUND
   COLOR
30 END
```

Specifically, the Basic equivalents of the assembly code mnemonics are as follows:

	Assembly code	Basic
49152	LDA	A=
49153	2	2
49154	STA	POKE
49155	33	???
49156	208	???
49157	RTS	END or RETURN

Everything in the example has a Basic equivalent except for the command values at addresses 49155 and 49156. The explanation lies in the way the C-64 stores numbers.

The largest number that can be stored in one byte is 255 (decimal). Its binary form (11111111) requires all eight bits of the byte. The next larger number, 256, requires *nine* binary digits (100000000), so one byte will not suffice. The two-byte method of storing numbers larger than 255 is called low-byte/high-byte sequence. Furthermore, the values are stored, not as decimal, but as hexadecimal numbers, indicated by the $ symbol. Using hexadecimal values, the two addresses would look like this:

49155	$21
49156	$D0

To read the full hex number, you reverse the order, getting $D021, which equals the decimal number 53281. You achieve the same thing in Basic by: PRINT 33 + (208*256).

If you rearrange the listing (using decimal values) to look like the following, you can see the relationship between the commands (the opcodes) and the numbers (the operands).

Circle 86 on Reader Service card.

Total Telecommunications™

Tremendous Value

Total Telecommunications regular price $124.95

now only $59.95

A complete telecommunications package

Modem



- 300 baud auto dial-auto answer modem

Communications Software

- Advanced telecommunications software
- Sends, receives and stores information
- Easy-to-use
- Automates connections and log-on sequences

THE INFO CENTER™

Over 60 Popular Data Bases and Services with no subscription fee.



- Electronic Mail
- Official Airline Guide
- Catalog Shopping
- Movie Reviews
- UPI world news and sports
- Stock quotations
- Journals and magazines in all career arenas
- Teleconferencing
- And much more!

Limited time offer.

800-22LEARN or **800-44LEARN** in California

For Commodore 64®

Total Telecommunications and The Info Center are trademarks of TeleLearning Systems, Inc.
Commodore 64 is a registered trademark of Commodore Electronics, Ltd.

TOTAL TELECOMMUNICATIONS
TeleLearning Systems, Inc.
505 Beach Street
San Francisco, California 94133
415/928-2800

Circle 74 on Reader Service card.

The
Master Handicapper™
Series by Professor Jones

EVALUATES FROM RACING FORM!

Age	Gender	Post (Today)
Class	Jockey (Today)	Post (Last)
Condition	Jockey (Last)	Speed
Consistency	Length	Trainer
Earnings	Time of Year	Workouts

And gives you GRAPHIC REPRESENTATION of finish

PROGRAM

GLD. Thoroughbred "Gold" Edition™
A "Full" featured thoroughbred analysis designed for the professional and serious novice.
$159.95 complete

EGLD. Enhanced "Gold" Edition™
"Gold" Edition with complete Master Bettor™ system integrated onto the same disk. This powerful program will transfer all horses and scores to the bet analysis with a "single keystroke."
(Master Bettor™ included) **$199.95** complete

GLTD. Limited "Gold"™
Enables **Professional Handicappers** to assign specific values to the racing variables "they" feel are important.

PROFESSIONAL HANDICAPPING SYSTEMS

%	%	%
Age 5	Consistency 15	Speed 10
Class 15	Jockey 15	Workouts 0
Condition 10	Trainer 5	Time of Year 0
Earnings 5	Post 10	Consistency 5
100%	Is Everything OK (Y/N)	

Create program weight based on a particular track and fine tune it for **maximum** win percentage. This program is designed for "ease of use". The user needs **no programming experience.**
(contains Integrated Bettor™) **$299.95** complete

GD. Gold Dog Analysis™
The only professional dog handicapper on the market, includes:

1) Speed	6) Condition
2) Post Today	7) Running Style
3) Kennel	8) Weight
4) Post Last	9) All new internal weighting
5) Distance	10) NEW class indicator

If you are near a greyhound track, *you can't afford not to use this program.*
$149.95 complete
(with integrated Master Bettor™) **$199.95**

Limited Dog™ $299.95

MHH. Master Harness Handicapper™
Professional software designed to provide a thorough analysis of all trotter and pacer races in North America and Canada. Features:

Class	Post Positions	Time Finish
Driver	Track Conditions	Time Last Quarter
Days Since Last	Trainer	Track Rating
Gender	Time ¼	Temp Allowance

$159.95 complete w/integrated Master Bettor™ **$199.95**

PPX. Professor Jones' Football Predictor, Prof. Pix™
Complete Football Analysis with **Data-Base.**

1) Overlays	4) "Over/Under" bets
2) Point Spreads	5) Data Base Stats
3) "Super Plays"	6) Holds "100" teams

Highest percentage of winners 1983

$39.95 complete
$99.95 with Data Base Management

NBA. Basketball™
This data base managed analysis will provide the user with "ALL" betting situations while storing relevant information on the disk.
$79.95 complete with Manual

LOT. Lottery Analysis™
Statistical comparison program designed to detect subtle patterns in winning lottery numbers.
$49.95 complete with Manual

BROCHURE AVAILABLE

Send check / money order / VISA / Mastercharge (Include expiration date) to:

Prof. Jones
1114 N. 24th St.
Boise, ID 83702

TELEPHONE
(208) 342-6939

VISA MasterCard

TERMS: FREE SHIPPING ALL SOFTWARE.
Add $6.00 hardware / C.O.D. Add $6.00 / Add 3 weeks personal checks / Add 4.5% ID residents / Add $6.00 outside U.S.A. / Prices subject to change.

IBM, APPLE, TRS-80, C-64 AND OTHERS

```
49152   LDA   #2
49154   STA   53281
49157   RTS
```

Assembly language is a simpler way of putting machine language into your computer. When you enter the assembly language opcode LDA, your assembler puts the machine language opcode (with the correct addressing mode) into a given memory location. Looking at the original listing and comparing it with the assembly listing, you can see the assembly listing makes a lot more sense.

Machine Code		Assembly Code
49152	169	LDA #2
49153	2	
49154	141	STA 53281
49155	33	
49156	208	
49157	96	RTS

Simple Monitor

To begin exploring what's in your computer's memory, let's take a look at a simple "monitor" that will allow you to look at and enter machine code.

From Basic, you know that Peek lets you look at something in memory and Poke lets you put something into memory. To keep it clear, I'll make an idiot-proof monitor; one that you can write *and* understand using Peek to see things and Poke to enter things.

```
10 REM **************
20 REM SIMPLE MONITOR
30 REM **************
40 PRINT CHR$(147)
50 INPUT "ADDRESS";A$
60 IF A$="A" THEN GOSUB 140
70 IF A$="A" THEN GOTO 50
80 IF A$="Q" THEN END
90 A=VAL(A$)
100 FOR X=A TO A+20
110 PRINT X;" = ";PEEK(X)
120 NEXT X
130 GOTO 50
140 PRINT CHR$(147)
150 INPUT "ADDRESS TO BEGIN";BA
160 PRINT BA;: INPUT"VALUE";V$
170 IF V$="Q" THEN RETURN
180 V=VAL(V$)
190 POKE BA,V
200 BA=BA+1
210 GOTO 160
220 REM <--WATCH THIS LINE
    NUMBER
```

To work your monitor, just enter the address you wish to view. That address and the next 20 will be listed on your screen. Look around to see if you can find some zeroes. This is "free RAM," where you can put your machine code. Try looking at addresses 828 and 49152, a couple of good areas with some free space. When you're finished looking around, press Q to quit.

To enter code, press A (for add) and the starting address. Don't try any number larger than 255 and be careful where you add your code. Put it up in 49152 or down in 828. Try entering the little program that turned the background color red.

If you want to do something weird, have the program look at itself. Basic programs begin in address 2048. Look around there and see if you can find the line numbers. In your monitor program, they are all followed by zeroes; so look for a zero and then back up to see the line number. If you put the spaces in just right, when you look up around 2392 you will see something that looks like this:

```
2392=220
2393=  0
2394=143
```

The 220 is line 220, the 0 is the high byte of the line number and the 143 is the Basic token for REM. Press A for add and enter the value 255 in 2392 and 2393 (or whatever addresses are the two just before the 143). Use Q to get out of the program and then list your monitor program.

Your last line number is now 65535. Try removing that line number from Basic. You can't do it. If you run your monitor again, you can re-Poke those addresses where you added those 255s.

An Easier Language

Playing with the monitor is a lot of fun, but it is not going to help you really start programming in assembly language. It will help you understand something about the way in which code is stored, and how your Basic program is tokenized, but the main purpose is to show you how much more difficult it is to program in machine language than assembly language.

With the mnemonic opcodes used in assembly language instead of the numeric opcodes in machine language, you can better understand the logic of what you're doing.

In future columns, we'll start working on an assembler for you to use if you don't already have one. For the time being, start looking at how your computer stores numbers; especially look for those empty places where you can store your own code. R

William B. Sanders (8982 Stimson Court, San Diego, CA 92129) is the author of Assembly Language for Kids: Commodore 64 and *Elementary Commodore 64.*

Circle 109 on Reader Service card.

UNLOCK YOUR CREATIVITY!

DOODLE! the most powerful, versatile graphics program ever created for a popular computer.

DOODLE!™

COMMODORE 64 COLOR SKETCH PAD

By Mark R. Rubin

DOODLE! the exciting graphic program acclaimed by thousands of Commodore 64 users!

DOODLE! turns your computer into a tool for unlimited design and artistic creativity! Regardless of your age or artistic skill, create anything you can imagine. . . from sketches to houseplans, to fine art, to business forms or letterheads that you can run off on your printer! Precise trackball or joystick operation, high-resolution graphics, program flexibility, and super ease of use add up to the friendliest, most versatile graphics program ever created for the Commodore 64.

DOODLE! will sketch, color, fill, zoom, line, box, circle, and more. Plus things no other software will do.

PRINT.

DOODLE! prints copies at the touch of a key. Print designs, charts, forms, text, anything! Works with most popular printers.

STAMP.

Create up to 9 of your own "rubber stamps"—great for plan drawing or graphic design!

LETTER.

DOODLE! lets you type in keyboard graphics, letters and numbers in any size and any direction!

COPY.

Duplicate, squeeze, rotate, reduce, enlarge, stretch, or reposition your DOODLE! (or any part of it) onscreen.

OKIMATE 10™ compatible.

Print your DOODLE! in 16 colors with Okidata's new color printer.

SAVE.

Store your DOODLE! on disk for later recall or revisions.

$39.95 on disk

For information, to order, or for the name of your nearest dealer, call 1-800-558-1008. In Wisconsin, call collect 414-291-5125. Dealer and Distributor inquiries invited.

City Software

735 W. Wisconsin Ave., Milwaukee, WI 53233

©1984 City Software Software ©1984 Mark R. Rubin & OMNI Unlimited

Commodore 64 is a registered trademark of Commodore Electronics, Ltd.

Circle 59 on Reader Service card.

Take The Heat Off Your 64 Disk Drive!

Overheating and line surges are a major cause of frustrating program malfunctions and permanent damage to your Commodore 64 disk drive.

Now, for the first time, you can protect your investment with the COM-COOL PLUS™ Cooling Fan/Surge Protector for your Commodore 1541 disk drive.

1. Two large, washable filters remove dust BEFORE forcing air through your disk drive.
2. Quiet fan has enough power to cool two stacked disk drives.
3. Foam base holds unit firmly in place without assembly or hardware.
4. Two surge protected outlets clip spikes at a safe 130V. Replaceable fuse.
5. Front panel pilot lights monitor POWER, GROUND, and SURGE protection.

Two models for use with Commodore 64 and VIC disk drives:

COM-COOL PLUS™ $79.95
Cooling Fan/Surge Protector

COM-COOL™ $54.95
Economical cooling unit
(does not include surge suppression and line filter)



City Software Distributors, Inc.
735 W. Wisconsin Avenue
Milwaukee, WI 53233

For information, your nearest dealer or to order direct, CALL TOLL FREE:

1-800-558-1008

In Wisconsin, call collect 414-291-5125

COM-COOL and COM-COOL PLUS guard are trademarks of AIER Products. Commodore 64 is a registered trademark of Commodore Electronics, Ltd.

Circle 155 on Reader Service card.

Sensational Prices!
. . . On Our Most Popular Items!

COLOR DISPLAY MONITOR

BMC USA

Enjoy the brilliant, vivid color graphics and text possible with this superb quality solid-state, composite video monitor from BMC. The large 13" non-glare screen offers resolution of 350 by 350 lines. The sturdy and attractively styled light beige cabinet also houses a build-in speaker. Convenient front panel houses controls for horizontal, vertical, brightness, contrast, tint, color, and volume. Easily connects to your Commodore computer.

Dimensions: 14.7"(W) x 13.4"(H) x 16.5(D), 24 pounds.

23231 ONLY **$229**

MONITOR CABLE

Connects above monitor to your Commodore computer.

21082 **$7.99**

COMPUTERFACTS™ from SAMS

Technical Service Data for Your Computer and Peripherals

Sams introduces COMPUTERFACTS™ . . . packets of information that reveal the inner workings of major brand micros, monitors, printers and disk drives. Includes schematic wiring diagrams, parts lists, disassembly instructions, troubleshooting techniques, and other repair data.

33477	Commodore 64 Computer	$17.95
33513	VIC-20 Computer	$17.95
33551	Commodore Plus/4 Computer	$17.95
33481	Commodore 1541 and VIC 1541 Disk Drives	$17.95
33496	Commodore 1525 Printer	$17.95
33508	Commodore C16 Printer	$17.95
33546	Commodore 1701 Monitor	$17.95
33527	Epson MX-80 FT Printer	$17.95
33458	Atari 400 Computer	$17.95
33462	Atari 800 Computer	$17.95
33532	TI 99/4A Computer	$17.95

Introducing . . .

THE 99¢ DISKETTE

Are you paying too much for diskettes? Try our first quality, prime, 5¼" diskettes (no rejects, no seconds) at these fantastic sale prices and save, save, SAVE! Disks are packaged in boxes of 50; each box contains 5 shrink-wrapped 10-packs that include diskettes in sleeves, labels, and write-protect tabs.

Each diskette is certified to be 100% error free and comes with a lifetime warranty (if you have a problem, we'll replace the diskette). All diskettes include hub reinforcement rings and write-protect notch.

All diskettes are double density and work in either single or double density drives.

32391 SS, DD Diskettes, Box of 50 $49.50-99¢ ea.!
32403 DS, DD Diskettes, Box of 50 $74.50-$1.49 ea.!

GRAPHICS PRINTER INTERFACE

PPI *with graphics*

The PPI (Parallel Printer Interface) from DSI is a high-performance graphics printer interface for your Commodore 64 or VIC-20, offered at an unbelievable price! The PPI fully emulates a Commodore printer so that all software written for Commodore computers and printers can be run with the PPI and most any parallel printer. Print true Commodore graphics and alpha-numerics as well as any special character sets offered by your specific printer. Works with Star, Epson, BMC, and many more. Comes complete with all necessary cables for quick installation and includes easy-to-follow user's manual.

33565 Parallel Printer Interface **$44.95**

NEW!

CARTRIDGE EXPANDER FROM Navarone!!!

NAVARONE

STOP CARTRIDGE SWAPPING!!

This Cartridge Expander plugs into the cartridge port on your Commodore 64 and lets you plug in up to three cartridges at a time. Select the program you want. Even reset the computer independently of the power switch!!

Save wear and tear on your cartridge and computer contacts. Handy and convenient!

33227 **$34.95**

SPACE SAVING PRINTER STAND

At last a printer stand priced for homes and small offices! We've always liked the convenience and organization of an elevated printer stand - you can put your paper underneath the stand to save valuable table space and make feeding easier. The problem, up until now, has been price. Stands sold to the office market often cost $40, $50, $60 or even more! These great new stands from Suncom, a leader in microcomputer accessories, solve the price problem and offer features not found on models costing more than twice as much. The stands feature heavy duty welded steel wire construction and have a heavy vinyl coating to reduce noise and vibration and provide an attractive appearance that will blend with your computer decor. Another plus that the designers of many more expensive stands left out: our Suncom stand holds the printer at an angle that makes it much easier to see your output as it is being printed.

We use one in our office and agree that this much convenience at such a low price is a real value. Available in two widths: 12" for most 80 column printers (Gemini 10X, RX-80, BX-80, 1526, etc.), and 18" for most 132 column printers (Gemini 15X, FX-100, etc.).

33232 12" Printer Stand $14.95
33246 18" Printer Stand $22.95

USE SINGLE SHEETS IN YOUR TRACTOR FEED PRINTER WITH

PAPER TRACTOR®

Paper Tractor carries ordinary sheet paper through your tractor-feed printer!

Simply place your letterhead, checks, invoices, forms, even legal-size sheets into the durable flexible plastic carrier and feed into your adjustable tractor-drive printer. Works with any printer, carries any paper.

22084 **$11.95**

From Your Friends At

TENEX Computer Express™

We gladly accept mail orders!

P.O. Box 6578
South Bend, IN 46660

Questions? Call 219/259-7051

Ad R1D

SHIPPING CHARGES

ORDER AMOUNT	CHARGE
less than $20.00	$2.75
$20.00-$39.99	3.75
$40.00-$74.99	4.75
$75.00-$149.99	5.75
$150.00-$299.99	6.75
$300 & up	7.75

MasterCard · AMERICAN EXPRESS · VISA

NO EXTRA FEE FOR CHARGES

ORDER TOLL FREE
1-800-348-2778

Sensational Prices!
. . . On Our Most Popular Items!

DUST COVER and "EVERYTHING BOOK" INTRODUCTORY SPECIAL

Get to know us by ordering this great dust cover for your VIC-20 or Commodore 64 and our catalog, "The Everything Book for the Commodore C-64 and VIC-20 Home Computers," for $2.95 (no extra shipping or handling charges). Cover is antistatic, transluscent, 8 gauge vinyl sewn to our exacting standards with reinforced seams. Discover the savings and easy shopping available from Tenex Computer Express!

$2.95

31627 Dust Cover and Catalog

SG-10 PRINTER

NEW!

$CALL for best price

Star Micronics proudly introduces its successor to the best selling Gemini 10X! In addition to the features that made the 10X famous (120 character per second print speed, tractor **and** friction feed, great graphics capability), the SG-10 features a **2K print buffer** and a new **NEAR LETTER QUALITY** mode. Requires one of the parallel interfaces listed below, or PPI with graphics on opposite page, to use with C-64 or VIC-20. **33251**

CARDPRINT B PRINTER INTERFACE
Quality standard parallel printer interface for VIC-20 and C-64. Includes all cables. From Cardco. Lifetime guarantee.
28603 ONLY **$39.95**

CARDPRINT +G INTERFACE with GRAPHICS
Top of the line from Cardco. Parallel printer interface with full graphics capability for VIC-20 and C-64. Lifetime guarantee.
20623 ONLY **$69.95**

OTHER GREAT PRINTER BUYS!

19179 Epson RX-80 ONLY **$249**

23564 BMC BX-80 ONLY **$259**
Friction & tractor; carbon ribbon!

33265 SG-15 ONLY **$429**
Wide platen plus new **16K Buffer**

The Most Complete Disk Drive You Can Buy

INDUS GT ONLY $259

State-of-the-art disk drive for C-64 and VIC-20 features LED sector indicator, electronic write-protect, built-in wedge, and operating speeds up to 400% faster. Package includes cables and power supply, carrying case that doubles as a disk storage file AND software starter package featuring word processor, spreadsheet, and database manager program!
FULL YEAR PARTS AND LABOR WARRANTY!!

33443 Indus GT Disk Drive ONLY **$259**
32672 MSD Dual Disk Drive ONLY **$489**

6420 MODEM
from Anchor Automation

Check out these features - auto-answer, auto-dial and re-dial! This 300 baud direct-connect modem comes with terminal emulator software on disk. (Auto features not available on VIC-20).

31613 ONLY **$79.95**

2 PRINTERS?

dsi

Now it's easy to switch from one printer to another with the Multiport Data Switch from DSI! This time saving device allows you to hook up two parallel printers to a single parallel output. Features three 36 pin female connectors (one incoming, two outgoing.) Switch from one to the other with the turn of a dial . . . no need to bother plugging and unplugging cables ever again! Also allows two computers to share one printer.

33602 Multiport Data Switch **$99.00**
33570 Parallel Cable (36 pin to 36 pin) **$24.95**

NEW: GATE CONTROL JOYSTICK FROM WICO

Famous WICO quality is now available with Gatelock Control for 8-way or 4-way action (great for the precise action required by maze games). Also features 3-way handle. Choose the bathandle, redball or pistol grip control for your favorite action. You can't get more options on a joystick!

31173 ONLY **$24.95**

FREE CATALOG

Enjoy "The Everything Book" for the C-64 and VIC-20 at NO CHARGE! Filled with over 500 software descriptions, peripherals and accessories, and how-to information on expanding your system. Includes discounts and easy order information! Request part no. **25997**. Write to your friends at Tenex Computer Express at the address below!

From Your Friends At

TENEX Computer Express

We gladly accept mail orders!

P.O. Box 6578
South Bend, IN 46660

Ad R1D

Questions? Call 219/259-7051

SHIPPING CHARGES

ORDER AMOUNT	CHARGE
less than $20.00	$2.75
$20.00-$39.99	3.75
$40.00-$74.99	4.75
$75.00-$149.99	5.75
$150.00-$299.99	6.75
$300 & up	7.75

MasterCard · AMERICAN EXPRESS · VISA

NO EXTRA FEE FOR CHARGES

ORDER TOLL FREE
1-800-348-2778

"My purchase of RUN *is a better investment than my computer—I get a much higher return on a much smaller investment!"—*

D. Suggs, Tallahassee, Fla.

Join the thousands of C-64, Plus/4, and VIC-20 users around the world who enjoy subscribing to **RUN** every month. They've found **RUN** to be an unrivaled Commodore resource. And they're right—**RUN** is one of the fastest-growing Commodore magazines on earth!

The convenience of personal delivery, plus a savings of **44% off** the newsstand price are yours when you subscribe to **RUN**—the year-round Commodore companion.

You get **12 great issues for just $19.97,** plus special announcements and offers available only to **RUN** subscribers!

Each month, you'll learn the fun of computing while exploring the limitless possibilities of your Commodore.

The Home User's Guide to Commodore Computing
RUN
EXERCISE!
Shape Up with Your C-64
MAKING FACES With Your C-64 & VIC-20
MONITORS or TV? See the Difference

Here's what satisfied readers are saying:

"I read many magazines after I bought my 64, but I think that yours is the best. I now have a subscription and look forward to every new issue."—Eric D. Stolen, Manistee, MI

"In a remarkably short time, **RUN** has become the best journal for Commodore computer users...I appreciate the coverage you devote to reader comments and questions (Magic, Mail RUN, and Commodore Clinic), as there is nearly always an interesting hint or tip in one of these columns!"—J. O'Hare, Victoria, B.C. Canada.

Throughout the year, you'll find:

- Exciting tips, Commodore tricks, and programming ideas in **RUN**'s most popular column, "Magic".
- Challenging, fun, and educational software.
- A rundown of the products best suited for the new C-16 and Plus/4.

The benefits roll on...time-saving programming ideas, no-punches-pulled product reviews, applications to broaden your computing horizon, tutorials and assistance from reknowned authors in the Commodore field, and of course, great ideas and tricks that have worked for fellow Commodore users.

Act today—and **save 44%**—joining the thousands of subscribers who've found that **RUN** is their best computing companion. Just send in the coupon or insert card, or call **TOLL-FREE 1-800-258-5473.** In NH, dial 1-924-9471.

Commodore 64, VIC-20 and PLUS/4 are registered trademarks of Commodore Business Machines, Inc.

YES! I want to make a great investment.

Send me 12 issues of **RUN** for the low subscription price of $19.97. I'll save 44% off the newsstand price.

☐ Payment enclosed ☐ Bill me

Name _____

Address _____

City _____ State _____ Zip _____

Canada & Mexico $22.97; Foreign Surface $39.97, 1 year only, US funds drawn on US bank. Foreign airmail, please inquire. Please allow 6 to 8 weeks for delivery.

RUN • Box 954 • Farmingdale, NY 11737

354B3

RUN

MICRO-SYS DISTRIBUTORS.

commodore

SOFTWARE FOR C-64

Business

Multiplan (Spreadsheet)	$ 63.00
Calc Result (Advanced)	$ 79.95
Superbase 64	$ 75.00
Mirage Concepts (Data Base)	$ 89.00
Mirage Concepts (Word Processor) (40/80 column & 30K Dictionary)	$ 89.00
B.I. Paperclip W/Spellpac (W/P)	$ 85.00
Home Accountant (Continental)	$ 45.00
Tax Advantage (Continental)	$ 35.00
Info Designs G/L	$ 19.95
Southern Solutions Accounting G/L, A/R, A/P, P/R, I/M ....each	$ 49.95
Tri Micro Accounting C64 & Plus 4 G/L, A/R, A/P, P/R, I/M ..each	$ 49.95
Smart64 Term +3	$ 39.95
Hellcat Ace (game)	$ 25.00
Solo Flight (game)	$ 25.00

Utilities

Printer Utility Program (Cardco)	$ 19.95
Disk Utility Program (Fast copy, File copy, Disassembler, For 1541)	$ 49.95
Bits and Pieces (Backup & Utility, Screen Dump & More for MSD Drive)	$ 49.95
Simon's Basic	$ 39.95
80 Column Expander (Cartridge)	$ 60.00
64 Relay Cartridge	$ 45.00
Oxford Pascal	$ 69.95
Tool 64 (Handic)	$ 39.95
Graf 64 (Handic)	$ 39.95
Stat 64 (Handic)	$ 39.95
Forth 64 (Handic)	$ 39.95

ACCESSORIES

MSD Super Disk Drive (single)	$ 349.00
MSD Super Disk Drive (dual)	$ 575.00
Hayes Smart 300 Modem	$ 229.00
Vic 1530 Datasette	$ 65.00
Cardco Datasette	$ 55.00
Cardco Numeric Key Pad	$ 39.95
Alien Voice Box	$ 95.00
When I'm 64 (Voice Box Sings)	$ 25.00
Voice Box Dictionary	$ 25.00
B.I. 80 Column Display	$ 159.95
1541/Flash	$ 89.95
Sock It To Me (For 8032)	$ 29.00
6420 Westridge Modem (Auto Answer/Auto Dial)	$ 89.95
Telearning (Auto Answer/Auto Dial) Modem With software	$ 95.00
CBM 4023 Ribbons	$ 10.95
CBM 1526 Ribbons	$ 10.95
CBM 8023P Ribbons	$ 8.75
CBM 6400 Ribbons	$ 8.75
LQ1 Ribbons	$ 8.75
Diablo Daisy Wheel	$ 13.95
Abati Daisy Wheel	$ 13.95
Flip N' File 10, 15, 25, 50	Call
Power Strips (Surge Protector)	$ 49.95
Computer Glow Care Kit	$ 10.95
Disk Drive Cleaning Kit	$ 10.95

MONITORS

Panasonic TR120 (Amber) For Apple or IBM Computers	$ 156.00
Green & Amber (For Apple & IBM)	$ 85.00
RGB Monitor Cable: ET-101C (Apple)	$ 33.80

INTERFACES

BussCard II (Batteries Included) IEEE, Cartridge Slot, Basic 4.0	$ 159.95
BussCard Printer Cable	$ 29.95
SuperBox 64 (Handic) IEEE, Reset, 3-Slot	$ 139.95
Interpod (Intelligent IEEE & RS-232)	$ 139.95
Cardco +G Parallel Interface	$ 79.95
Cardco B Parallel Interface	$ 49.95
The Connection (by Tymac) (Commodore Graphics + 2K Buffer) Epson, Gemini, Okidata, Panasonic	$ 95.00
Turbo/GT (Telesys) With optional 16K or 32K Buffer	$ 89.95
Vic Switch (Handic)	$ 149.95
ADA1800 IEEE to Centronics	$ 149.95
Pet to IEEE Cable	$ 39.00
IEEE to IEEE Cable	$ 49.00
Networking For C-64 & CBM	Call

LETTER QUALITY PRINTERS

Abati (20 CPS) W/Interface	$ 475.00

DOT MATRIX PRINTERS

Smith Corona Fastex 80 (80 CPS)	$ 259.00
Smith Corona 100 (120 CPS)	$ 315.00
Smith Corona 200 (140 CPS)	$ 456.00
Smith Corona 300 (140 CPS, 15in)	$ 589.00

BUSINESS SOFTWARE — B128

Superscript II (40K Dictionary)	$ 199.00
Superbase (Data Base)	$ 199.00
Calc Result	$ 199.00
Complete Accounting System From Software Design (G/L, A/R, A/P, P/R, I/M) .....each	$ 375.00

BUSINESS SOFTWARE — 8032/8096

WordPro 4+ or 5+	$ 225.00
Calc Result	$ 199.95
SuperBase (8096 only)	$ 225.00
Complete Accounting System From Software Design (G/L, A/R, A/P, P/R, I/M) .....each	$ 375.00

TERMS

Orders under 50.00 add 10.00 Handling fee
MasterCard, VISA, Money Order, Bank Check
COD (add 5.00)
Add 3% For Credit Cards

All Products In Stock Shipped Within 24 Hours

F.O.B. Dallas, Texas
All Products Shipped With Manufacturers
90 Day Warranty

PRICES ARE SUBJECT TO CHANGE WITHOUT NOTICE.

AUTHORIZED WHOLESALE DISTRIBUTOR FOR ALL COMMODORE BUSINESS MACHINE PRODUCTS.

BECOME A COMMODORE DEALER. AND SEE WHY IT'S THE BEST DEAL IN NEW COMPUTER PRODUCTS.

FOR PRODUCT CATALOG & PRICE LIST WRITE OR CALL MICRO-SYS DISTRIBUTORS.

Circle 212 on Reader Service card.

ORDERS ONLY CALL
1-800-527-1738

INQUIRIES & INFORMATION PLEASE CALL
1-214-231-2645

Micro-Sys
DISTRIBUTORS

641 Presidential Drive • Richardson, Texas 75081 • 9:30 a.m.-6:30 p.m. (Mon.-Fri.) • 10:30 a.m.-2:30 p.m. (Sat.)

COMPUTER AND SOFTWARE SALE

COMMODORE 64
(with $12.95 Bonus Pack Purchase)

$139.00*

- 170K Disk Drive $195.00 *
- Tractor Friction Printer $169.00 *
- 13" Hi-Res Color Monitor $195.00 *

*less coupon discount

WE HAVE THE BEST SERVICE

WE HAVE THE LOWEST PRICES

SUPER AUTO DIAL MODEM 64
(Best communications package in USA)

$59.00

- Computer Learning Pad $39.95
- New Voice Synthesizer $59.00
- 12" Green or Amber Monitor $79.95
- 13" Daisy Wheel Printer $249.00

* COMMODORE 64 COMPUTER $139.00
You pay only $139.00 when you order the powerful 84K COMMODORE 64 COMPUTER! LESS the value of the SPECIAL SOFTWARE COUPON we pack with your computer that allows you to SAVE OVER $500 off software sale prices!! With only $100 of savings applied, your net computer cost is $39.00!!

* 170K DISK DRIVE $195.00
You pay only $195.00 when you order the 170K Disk Drive! LESS the value of the SPECIAL SOFTWARE COUPON we pack with your disk drive that allows you to SAVE OVER $500 off software sale prices!! With only $100 of savings applied, your net disk drive cost is $95.00.

* 80 COLUMN 80 CPS TRACTION/FRICTION PRINTER $169.00
You pay only $169.00 when you order the Comstar T/F deluxe line printer that prints 8½x11 full size, single sheet, roll or fan fold paper, labels, etc. Impact dot matrix, bidirectional. LESS the value of the SPECIAL SOFTWARE COUPON we pack with your printer that allows you to SAVE OVER $500 off software sale prices!! With only $100 of savings applied your net printer cost is only $69.00.

* 13" HI-RES COLOR MONITOR $195.00
You pay only $195.00 when you order this 13" COLOR MONITOR with sharper and clearer resolution than any other color monitors we have tested! LESS value of the SPECIAL DISCOUNT COUPON we pack with your monitor that allows you to save over $500 off software sale prices!! With only $100 of savings applied, your net color monitor cost is only $95.00. (16 Colors).

80 COLUMN BOARD $89.00
Now you program 80 COLUMNS on the screen at one time! Converts your Commodore 64 to 80 COLUMNS when you plug in the 80 COLUMN EXPANSION BOARD!! PLUS 4 slot expander! Can use with most existing software.

80 COLUMNS IN COLOR EXECUTIVE WORD PROCESSOR $39.00
This EXECUTIVE WORD PROCESSOR is the finest available for the COMMODORE 64 computer! The ULTIMATE FOR PROFESSIONAL Word Processing. DISPLAYS 40 or 80 COLUMNS IN COLOR or black and white! Simple to operate, powerful text editing with 250 WORD DICTIONARY, complete cursor and insert/delete key controls line and paragraph insertion, automatic deletion, centering, margin settings and output to all printers! Includes a powerful mail merge.
List $99.00 **SALE $39.00** Coupon $29.95

SPECIAL SOFTWARE COUPON

We pack a SPECIAL SOFTWARE DISCOUNT COUPON with every COMMODORE 64 COMPUTER DISK DRIVE-PRINTER-MONITOR we sell! This coupon allows you to SAVE OVER $500 OFF SALE PRICES!!

(Examples)
PROFESSIONAL SOFTWARE
COMMODORE 64

Name	List	Sale	Coupon
Executive Word Processor	$99.00	$39.00	$29.95
Executive Data Base	$69.00	$29.00	$19.95
20,000 Word Dictionary	$24.95	$14.95	$10.00
Electronic Spread Sheet	$59.95	$49.00	$39.00
Accounting Pack	$49.00	$39.00	$29.00
Practicalc	$59.95	$34.95	$29.95
Programmers Reference Guide	$20.95	$16.95	$12.50
Programmers Helper (Disk)	$59.95	$39.95	$29.95
80 Column Screen (Disk)	$59.95	$39.95	$29.95
Disk Filer (by Flip-N-File)	$39.95	$14.95	$12.95
Deluxe Tape Cassette	$89.00	$39.00	$29.95
Pro Joy Stick	$24.95	$15.95	$12.00
Light Pen	$39.95	$14.95	$ 9.95
Dust Cover	$ 8.95	$ 6.95	$ 4.60
Pogo Joe	$29.95	$19.95	$16.95
Pitstop II Epyx	$39.95	$24.95 *	$19.95
		* Plus One FREE	
Music Calc 1	$59.95	$39.95	$34.95
Filewriter	$59.95	$39.95	$34.95

(See over 100 coupon items in our catalog)
Write or call for
Sample SPECIAL SOFTWARE COUPON!

EXECUTIVE QUALITY
PROFESSIONAL BUSINESS SOFTWARE

The Cadillac of Business Programs
for Commodore 64 Computers

Item	List	* Sale	Coupon
Inventory Management	$99.00	$34.95	$29.95
Accounts Receivable	$99.00	$34.95	$29.95
Accounts Payable	$99.00	$34.95	$29.95
Payroll	$99.00	$34.95	$29.95
General Ledger	$99.00	$34.95	$29.95

* SUPER AUTO DIAL MODEM $59.00
Easy to use. Just plug into your Commodore 64 computer and you're ready to transmit and receive messages. Easier to use than dialing your telephone, just push one key on your computer! Includes exclusive easy to use program for up and down loading to printer and disk drives. List $129.00 **SALE $59.00**.

NEW COMPUTER LEARNING PAD $39.95
Makes other graphics tablets obsolete. This new TECH SKETCH LEARNING PAD allows you to draw on your T.V. or Monitor and then you can print whatever you draw on the screen on your printers. FANTASTIC!!! List $79.95 **SALE $39.95**.

NEW VOICE SYNTHESIZER $59.00
For Com-64 or VIC-20 computers. Just plug it in and you can program words and sentences, adjust volume and pitch, make talking adventure games, sound action games and customized talkies!! FOR ONLY $19.95 you can add TEXT TO SPEECH, just type a word and hear your computer talk — ADD SOUND TO "Zork", SCOTT ADAMS AND AARDVARK ADVENTURE GAMES!! (Disk or tape.)

12" GREEN OR AMBER MONITOR $79.95
Your choice of green or amber screen monitor, top quality, 80 columns x 24 lines, easy to read, anti-glare! PLUS $9.95 for connecting cable. Com-64 or VIC-20.

13" DAISY WHEEL PRINTER $249.00
"JUKI" Superb letter quality daisy wheel printer, 13" extra large carriage, up to 12 CPS bi-directional printing, drop in cassette ribbon, centronics parallel or RS232 serial port built in! (Specify)
List $399.00 **SALE $249.00**

COM-64 4 SLOT EXPANSION BOARD $29.95
Easy to use, switch selectable, reset button and LED indicator — saves your computer and cartridges.
List $79.00 **Sale $29.95**

FLOPPY DISK SALE 98¢
Lowest prices in the U.S.A.!! Single sided single density, with hub rings, quality guaranteed! (100 bulkpack 98¢ ea.) (Box of 10 $12.00)

PHONE ORDERS
8 a.m. - 8 p.m. Weekdays
9 a.m. - 12 noon Saturdays

• LOWEST PRICES • 15 DAY FREE TRIAL • 90 DAY FREE REPLACEMENT WARRANTY
• BEST SERVICE IN U.S.A. • ONE DAY EXPRESS MAIL • OVER 500 PROGRAMS • FREE CATALOGS

Add $10.00 for shipping, handling and insurance. Illinois residents please add 6% tax. Add $20.00 for CANADA, PUERTO RICO, HAWAII, ALASKA, APO-FPO orders. Canadian orders must be in U.S. dollars. WE DO NOT EXPORT TO OTHER COUNTRIES.

Enclose Cashiers Check, Money Order or Personal Check. Allow 14 days for delivery, 2 to 7 days for phone orders, 1 day express mail!

VISA — MASTER CARD — C.O.D.

PROTECTO

We Love Our Customers

Box 550, Barrington, Illinois 60010

312/382-5244 to order

Circle 15 on Reader Service card.

Circle 15 on Reader Service card.

NEW 128K —MEGA BYTE DUAL DISK DRIVE—80 COLUMN

COMPUTER SYSTEM SALE!

HOME • BUSINESS • WORD PROCESSING



LOOK AT ALL YOU GET FOR ONLY **$795.**

	LIST PRICE
① B128 COMMODORE 128K 80 COLUMN COMPUTER	$ 995.00
② 4023 - 100 CPS - 80 COLUMN BIDIRECTIONAL PRINTER	499.00
③ 8050 DUAL DISK DRIVE (over 1 million bytes)	1795.00
④ 12" HI RESOLUTION 80 COLUMN MONITOR	249.00
• BOX OF 10 LORAN LIFETIME GUARANTEED DISKS	49.95
• 1100 SHEETS FANFOLD PAPER	19.95
• ALL CABLES NEEDED FOR INTERFACING	102.05
TOTAL LIST PRICE	**$3717.95**

$795 SALE PRICE

PLUS YOU CAN ORDER THESE BUSINESS PROGRAMS AT SALE PRICES

Programmers Reference Guide
List $29.95
Sale $24.95

	LIST	SALE	*SYSTEM PRICE**
Professional 80 Column Word Processor	$149.95	**$99.00**	***$49.00***
Professional Data Base	$149.95	**$99.00**	***$49.00***
Accounts Receivable	$149.95	**$99.00**	
Accounts Payable	$149.95	**$99.00**	
Payroll	$149.95	**$99.00**	
Inventory	$149.95	**$99.00**	
General Ledger	$149.95	**$99.00**	
Financial Spread Sheet	$149.95	**$99.00**	
Order Entry	$149.95	**$99.00**	

* When Bought with B128 Computer System.

☆ **PRINTER REPLACEMENT OPTIONS**
(replace the 4023 with the following printers at these sale prices. Interface Included)

	LIST	SALE
☆ Olympia Executive Letter Quality Printer	$699.00	**$369.00**
☆ Comstar Hi-Speed 160 CPS 15½" Business Printer	$779.00	**$459.00**
Telecommunications Deluxe Modem Package	$199.00	**$139.00**
IEEE to Centronics Parallel Printer Interface	$179.00	**$139.00**

15 DAY FREE TRIAL. We give you 15 days to try out this SUPER SYSTEM PACKAGE!! If it doesn't meet your expectations, just send it back to us prepaid and we will refund your purchase price!!
90 DAY IMMEDIATE REPLACEMENT WARRANTY. If any of the SUPER SYSTEM PACKAGE equipment or programs fail due to faulty workmanship or material we will replace it IMMEDIATELY with no service charge!!

Add $50.00 for shipping and handling!!
WE DO NOT SHIP THIS SYSTEM TO FOREIGN COUNTRIES, CANADA, PUERTO RICA, ALASKA, OR HAWAII.
Enclose Cashiers Check, Money Order or Personal Check. Allow 14 days for delivery. 2 to 7 days for phone orders. 1 day express mail! We accept Visa and MasterCard. We ship C.O.D. to continental U.S. addresses only.

PROTECTO
ENTERPRIZES (WE LOVE OUR CUSTOMERS)
BOX 550, BARRINGTON, ILLINOIS 60010
Phone 312/382-5244 to order

DAISY WHEEL PRINTER SALE!

JUKI®

(Japanese Highest Quality Award Winner)

DELUXE LETTER QUALITY "DAISY WHEEL PRINTERS"



Letter Quality Printer

JUKI®
DELUXE COMPUTER PRINTER

List Price $399 **SALE $249**

- Superb "Daisy Wheel" Computer Printer
- 100 Characters
- Bi-directional with special print enhancements-many type styl· $18.95
- Pitch 10, 12, 15 CPI
- Print Speed up to 12 CPS
- Print line width: 115, 138, 172 characters
- 12" Extra large carriage
- Drop in cassette ribbon (replacement $8.95)
- Centronics parallel RS 232 Serial interface built in (specify)

Letter Quality Printer/Typewriter

JUKI®
DELUXE "COMBINATION" PRINTER/TYPEWRITER

List Price $499 **SALE $299**

- Superb Computer Business Printer combined with the deluxe electronic typewriter!
- Two machines in one—just a flick of the switch!
- Superb letter quality correspondence—home, office, word processing!
- 12" Extra large carriage
- Drop in cassette ribbon—replacement $8.95
- Precision daisy wheel printing—many type styles! $18.95
- Pitch selector-10, 12, 15 CPS, Automatic relocate key!
- Automatic margin control and setting! Key in buffer!
- Centronics parallel or RS 232 Serial interface built-in (specify)

15 Day Free Trial - 90 Day Immediate Replacement Warranty

- COMMODORE 64 COMPUTER INTERFACE ONLY $49.00 - ATARI INTERFACE $79.00

ADD $10.00 for shipping and handling!!

Enclose Cashiers Check, Money Order or Personal Check. Allow 14 days for delivery, 2 to 7 days for phone orders, 1 day express mail! Canada orders must be in U.S. dollars. VISA — MASTER CARD ACCEPTED. We ship C.O.D.

PROTECTO

We Love Our Customers

Box 550, Barrington, Illinois 60010

312/382-5244 to order

Circle 15 on Reader Service card.

Circle 15 on Reader Service card.

FANTASTIC COMPUTER PRINTER SALE!!!



COM-STAR T/F

Tractor
Friction
Printer

only $ 169**

- Lowest Priced, Best Quality, Tractor-Friction Printers in the U.S.A.
- Fast 80-120-160 Characters Per Second • 40, 46, 66, 80, 96, 132 Characters Per Line Spacing
- Word Processing • Print Labels, Letters, Graphs and Tables • List Your Programs
- Print Out Data from Modem Services • "The Most Important Accessory for Your Computer"

** DELUXE COMSTAR T/F 80 CPS Printer $169.00

This COMSTAR T/F (Tractor Friction) PRINTER is exceptionally versatile. It prints 8½" x 11" standard size single sheet stationary or continuous feed computer paper. Bi-directional, impact dot matrix, 80 CPS, 224 characters. (Centronics Parallel Interface).

Premium Quality 120-140 CPS 10X COM-STAR PLUS+ Printer $199

The COM-STAR PLUS+ gives you all the features of the COMSTAR T/F PRINTER plus a 10" carriage, 120-140 CPS, 9 x 9 dot matrix with double strike capability for 18 x 18 dot matrix (near letter quality), high resolution bit image (120 x 144 dot matrix), underlining, back spacing, true lower decenders with super & subscripts, prints standard, italic, block graphics & special characters. It gives you print quality and features found on printers costing twice as much!! (Centronics Parallel Interface) (Better than Epson FX80). RATED "BEST BUY" BY CONSUMERS DIGEST BUYERS GUIDE, JANUARY 1985! List $499.00. **Sale $199.00.**

Premium Quality 120-140 CPS 15½X COM-STAR PLUS+ Business Printer $319.00

Has all the features of the 10" COM-STAR PLUS+ PRINTER plus 15½" carriage and more powerful electronics components to handle large ledger business forms! (Better than Epson FX 100). List $599. **Sale $319.00.**

Superior Quality 15½" COM-STAR PLUS+ H.S. High Speed 160-180 CPS Business Printer $449.00

15½" Carriage and more powerful electronic components to handle larger ledger business forms! (Serial Centronics Parallel Interface). List $799. **Sale $449.**

12" DAISY WHEEL PRINTER $249.00

"JUKI" Superb letter quality daisy wheel printer, 12" extra large carriage, up to 12CPS bi-directional printing, drop-in cassette ribbon, (90 day warranty) centronics parallel or RS232 serial port built in! (Specify). List $399.00. **Sale $249.00.**

Superior Quality 10" COM-STAR+ H.S. HIGH SPEED 160-180 CPS Business Printer $349.00

This **Super High Speed Com-Star+ Business Printer** has all the features of the 10" COM-STAR+ PRINTER with HIGH SPEED BUSINESS PRINTING 160-180 CPS, 100% duty cycle, 8K Buffer, diverse character fonts, special symbols and true decenders, vertical and horizontal tabs. **A RED HOT BUSINESS PRINTER** at an unbelievable low price (Serial or Centronics Parallel Interface). List $699.00.
Sale $349.00.

Printer/Typewriter Combination $299.00

"JUKI" Superb letter quality, daisy wheel printer/typewriter combination. Two machines in one — just a flick of the switch. 12" extra large carriage, typewriter keyboard, automatic margin control and relocate key drop in cassette ribbon! (90 day warranty) centronics parallel or RS232 serial port built in (Specify). List $499.00. **Sale $299.00.**

• 15 Day Free Trial - 1 Year Immediate Replacement Warranty

PARALLEL INTERFACES

For VIC-20 and COM-64 — $49.00. Commodore B-128 — $139.00. Apple — $79.00. Atari — $79.00.

Add $14.50 for shipping, handling and insurance. Illinois residents please add 6% tax. Add $29.00 for CANADA, PUERTO RICO, HAWAII, ALASKA, APO-FPO orders. Canadian orders must be in U.S. dollars. WE DO NOT EXPORT TO OTHER COUNTRIES.

Enclose Cashiers Check, Money Order or Personal Check. Allow 14 days for delivery, 2 to 7 days for phone orders, 1 day express mail!

VISA—MASTER CARD—We Ship C.O.D. to U.S. Addresses Only

PROTECTO ENTERPRIZES (WE LOVE OUR CUSTOMERS)
BOX 550, BARRINGTON, ILLINOIS 60010
Phone 312/382-5244 to order

COM-STAR PLUS+ Print Example:

ABCDEFGHIJKLMNOPQRSTUVWXYZ
ABCDEFGHIJKLMNOPQRSTUVWXYZ 1234567890

COLOR MONITOR SALE!!!

(Lowest price in USA)

- Built in speaker and audio
- Front Panel Controls
- For Video Recorders
- For Small Business/ Computers
- Apple-Commodore Atari-Franklin-etc.

13" Color Computer Monitor

16 COLORS

- Beautiful Color Contrast
- High Resolution
- Separated Video
- Sharp Clear Text
- Anti Glare Screen
- 40 Columns x 24 lines
- Supports 80 Columns
- List $399

SALE **$195**

15 Day Free Trial - 90 Day Immediate Replacement Warranty

12" XTRON SUPER HI-RESOLUTION "SWIVEL BASE" MONITOR

List $249 **SALE $119** *

80 Columns x 24 lines, Super Hi-Resolution 1000 lines
Green or Amber super-clear Easy to Read text with special anti-glare screen!

12" ZENITH HI-RESOLUTION GREEN OR AMBER TEXT DISPLAY MONITOR

List $199 **SALE $99** *

80 Columns x 24 lines, Hi-Resolution-crisp clear easy to read text with anti-glare screen! A MUST for word processing.

12" MONITOR GREEN OR AMBER TEXT

80 Columns x 24 lines, easy to read up front controls

List $159 **SALE $79.95** *

***Plus $9.95 connecting cable!**

• LOWEST PRICES • 15 DAY FREE TRIAL • 90 DAY FREE REPLACEMENT WARRANTY
• BEST SERVICE IN U.S.A. • ONE DAY EXPRESS MAIL • OVER 500 PROGRAMS • FREE CATALOGS

Add $10.00 for shipping, handling and insurance. Illinois residents please add 6% tax. Add $20.00 for CANADA, PUERTO RICO, HAWAII orders. WE DO NOT EXPORT TO OTHER COUNTRIES.

Enclose Cashiers Check, Money Order or Personal Check. Allow 14 days for delivery, 2 to 7 days for phone orders, 1 day express mail! Canada orders must be in U.S. dollars. Visa - MasterCard - C.O.D.

PROTECTO ENTERPRIZES (WE LOVE OUR CUSTOMERS)
BOX 550, BARRINGTON, ILLINOIS 60010
Phone 312/382-5244 to order

Circle 15 on Reader Service card.

Circle 15 on Reader Service card.

Sale

Commodore 64 MODEM



Sale

$59
List $129.95

Telecommunications

$59
List $129.95

FOR CHILDREN·ADULTS·BUSINESS

Complete Auto Dial Telecommunications Package

"The only telecommunications package you will ever need."

(Exclusive Easy To Use Features)

NEW

Total Telecommunications

NEW

• 300 Baud Modem • Auto Dial • Auto Answer • Upload & Download

• Membership in 52 Database Services (UPI News, etc.)

Reach Out and Access Someone

- Educational courses
- Financial Information
- Banking at Home
- Popular Games
- News Updates and Information
- Electronic Shopping
- Research and Reference Materials

The Total Telecommonications Package offers you all this plus ...

- Auto Log-on
- Dialing from Keyboard
- On-line Clock
- Capture and Display High Resolution Characters
- Download Text, Program or Data Files
- Stores on Disk Downloaded Files
- Reads Files from Disk and Uploads Text or Program Files
- Select Any Protocol (access almost any computer or modem)
- Plus Much, Much More

List $129.95

Special Low-Low Price $59.00

We are so sure this is the only telecommunications package you will need we will give you 15 days Free Trial.

Add $3.00 for shipping, handling and insurance. Illinois residents please add 6% tax. Add $6.00 for CANADA, PUERTO RICO, HAWAII, ALASKA, APO-FPO orders. Canadian orders must be in U.S. dollars. WE DO NOT EXPORT TO OTHER COUNTRIES.

Enclose Cashiers Check, Money Order or Personal Check. Allow 14 days for delivery. 2 to 7 days for phone orders. 1 day express mail!

VISA — MASTER CARD — C.O.D.

No C.O.D. to Canada, APO-FPO

PROTECTO

We Love Our Customers

Box 550, Barrington, Illinois 60010

312/382-5244 to order

COMMODORE-64

VOICE SYNTHESIZER

NEW NEW

MAKE YOUR COMPUTER TALK

VOTRAX BASED HARDWARE

SALE ONLY $59.00

You can program any words or sentences • Adjust volume and pitch • Receive Modem messages • Make adventure games that talk • Real sound action games • Make customized talkies • (Demo disk or tape included)

You can add TEXT TO SPEECH SOFTWARE that allows you to simply type what you want to hear!! Also allows you to add sound and voice to SCOTT ADAMS and "ZORK" ADVENTURE GAMES. List $29.95. SALE $19.95. (Disk or Tape).

• LOWEST PRICES • 15 DAY FREE TRIAL • 90 DAY FREE REPLACEMENT WARRANTY
• BEST SERVICE IN U.S.A. • ONE DAY EXPRESS MAIL • OVER 500 PROGRAMS • FREE CATALOGS

COMMODORE 64

80 COLUMN BOARD

SALE

FOR ONLY $89.00

(Word Processor Disk Program included FREE!!)

Now you can program 80 columns on the screen at one time! Converts your Commodore 64 to 80 columns when you plug in the PROTECTO 80 Expansion Board. List $199.00. **Sale $89.00.**

Includes 4 Slot Expander and can be used with most existing software!!!

Add $3.00 for shipping, handling and insurance. Illinois residents please add 6% tax. Add $6.00 for CANADA, PUERTO RICO, HAWAII, ALASKA, APO-FPO orders. Canadian orders must be in U.S. dollars. WE DO NOT EXPORT TO OTHER COUNTRIES.

Enclose Cashiers Check, Money Order or Personal Check. Allow 14 days for delivery. 2 to 7 days for phone orders. 1 day express mail!

VISA — MASTER CARD — C.O.D.

No C.O.D. to Canada, APO-FPO.

PROTECTO

We Love Our Customers

Box 550, Barrington, Illinois 60010

312/382-5244 to order

Circle 15 on Reader Service card.

Circle 15 on Reader Service card.

FUJI SALE $1.49 ea.

Premium Quality Floppy Disks

Box of 10 *with hub rings, sleeves and labels*

Famous Brand FUJI Floppy Disks for those who care about keeping their data.

List $39.95

Single Sided — Double Density
for Commodore 64, Atari, Apple

Sale $14.90

*** $12.95** ☆ ☆ ***Flip-N-File*** ☆ ☆ *** $12.95**

Data-Case

Floppy Disk Filer



Everyone Needs a Floppy Disk Secretary

Facts:

- Dust and Dirt particles can hurt your disks
- Most disks go bad due to mishandling in storage
- Proper filing of your disk collection will reduce unnecessary handling of your disks

The Floppy Disk Filer is an inexpensive hard plastic Fliptop case that will allow for easy filing, and protect your disks from dust, smoke, and dirt. Plus, the Floppy Disk Filer will keep all your disks out of unwanted hands and in one place where you can easily find them. **(Holds Over 50 Disks)**

List $24.95 **Introductory Sale Price $14.95** **** Coupon $12.95***

Add $3.00 for shipping, handling and insurance. Illinois residents please add 6% tax. Add $6.00 for CANADA, PUERTO RICO, HAWAII ALASKA, APO-FPO orders. Canadian orders must be in U.S. dollars. WE DO NOT EXPORT TO OTHER COUNTRIES.

Enclose Cashiers Check, Money Order or Personal Check. Allow 14 days for delivery. 2 to 7 days for phone orders. 1 day express mail!

VISA — MASTER CARD — C.O.D.

No C.O.D. to Canada, APO-FPO

PROTECTO

We Love Our Customers

Box 550, Barrington, Illinois 60010

312/382-5244 to order

Commodore 64 **CARDCO** Commodore 64

Fulfill All Your Personal & Business Needs "NOW"

Write Now! — Word Processor

Easy To Use Cartridge Based Word Processor for the C-64, With Full 80 Column On-Screen View Mode

The WRITE NOW! word processor provides you with the easiest to use, fastest to learn format available for your Commodore 64 computer. It will give you all the fetures you would expect in a professional word processor and some features not found in any other Commodore 64 word processor.
(Cartridge) List $49.95. **Sale $34.95.** *Coupon $29.95.*

- Program is on cartridge and loads instantly so there is no waste of time loading from unreliable tapes or disks.
- Built in 80 column display allows you to see exactly what you will print including headers, footers, justification, page numbers and page breaks.
- Can send all special codes to any printer, even in the middle of a line without losing proper justification.
- Page numbering in standard numbers or upper or lower case Roman numerals.
- Full string search and search/replace functions.
- Direct unlimited use of previously stored text from tape or disk called from within text during the print out so it uses no memory space and allows creation of unlimited length documents.
- Full scrolling up and down through text.
- No complicated editing modes or commands.
- Multiple line headers and footers.
- Justification and text centering.
- Block copy and delete commands.
- Save text to tape or disk.
- Easy full screen editing.
- Works with any printer.
- Easy to understand instruction booklet.
- 4 help screens included.

Spell Now — Spell Checker

"Spell Now" is a disk based professional spelling checker that interfaces with the "Write Now" word processor for the C-64. Use "Spell Now" to check the spelling in your "Write Now" files. It includes all features of the most expensive spelling checkers on the market. (Disk) List $39.95. **Sale $19.95.**

- 34,000 word dictionary.
- 1,000 word mini-dictionary.
- Unlimited number of supplemental dictionaries (user-definable).
- You see status of spelling check.
- Menu-driven; user-friendly.
- Fully compatible with "Write Now".
- Allows for marking, immediate correction and viewing in context.
- CARDCO, INC.'s Lifetime Guarantee.

Mail Now — Mailing List Software

The "Mail Now" is a disk based full random access data base designed to be used with the "Write Now" word processor. "Mail Now" allows the user to merge an address file into the text of the word processor for form letters. (Disk) List $39.95. **Sale $19.95.**

- Machine language fast sort.
- User-friendly, totally menu-driven operation.
- 10 character comment line.
- User-defined, print format can print one, two or three labels across.
- 2 character category field.
- Supports 600 entries per disk.
- Quick (in memory) sorts by Zip, Category, Last name and State.
- Includes data back-up utility.
- CARDCO, INC.'s Lifetime Guarantee.

File Now — Database

"File Now" is the inexpensive data base you've been waiting for. "File Now" interfaces with the "Write Now" word processor for the C-64. Helps you with data base management of your "Write Now" files and keeps separate data bases for other important information. (Disk) List $39.95. **Sale $29.95.**

- Functions as a deck of 3 x 5 note cards.
- Fields are user-definable.
- Full edit features; add, edit, delete.
- Searching is bidirectional.
- Wild card searching and printing.
- Capacity up to 700 cards per file-disk.
- Fully compatible with "Write Now".
- CARDCO, INC.'s Lifetime Guarantee.

Graph Now / Paint Now — Graphic/Logo Generator

A full graphics package capable of generating line, bar graphs and graphic art designs such as logos and pictures to be used with "Write Now" for the C-64. Save your graph or logo in a "Write Now" compatible file and print it out along with your "Write Now" text file. (Disk) List $39.95. **Sale $19.95.**

- Allows plotting of x,y coordinates from software or keyboard.
- Compatible with "Write Now" files.
- Menu-driven; user-friendly.
- Draw lines, rectangles and circles.
- 3 fill shades; white, gray and black
- Character font editor
- Load or save graphics.
- Optional joystick control.
- CARDCO INC.'s Lifetime Guarantee.

Add $3.00 for shipping, handling and insurance. Illinois residents please add 6% tax. Add $6.00 for CANADA, PUERTO RICO, HAWAII, ALASKA, APO-FPO orders. Canadian orders must be in U.S. dollars. WE DO NOT EXPORT TO OTHER COUNTRIES.

Enclose Cashiers Check, Money Order or Personal Check. Allow 14 days for delivery, 2 to 7 days for phone orders, 1 day express mail!

VISA — MASTER CARD — C.O.D.

No C.O.D. to Canada, APO-FPO.

PROTECTO

We Love Our Customers

Box 550, Barrington, Illinois 60010

312/382-5244 to order

Circle 15 on Reader Service card.

Circle 15 on Reader Service card.

Commodore 64

The Most Practical Business Software

Commodore 64

Special Low Low Prices - While Supplies Last

• Word Processor • Spread Sheet • Data Base • Diagnostic

• Track Expenses, inventories, investments • Make Charts and Graphs • Project Profits

• Keep Mailing Lists • Change Records, numbers, methods of filing • Information Retrieval

• Test RAM Memory • RS-232 Port • Keyboard • Video • Audio • Joystick • Printer • Disk Drive • And More!





Practicalc 64: A consistent best seller, Practicalc 64 has become a reference standard among Commodore 64 spreadsheets. With features like alphabetic and numeric sorting and searching, variable comumn widths, graphing and over 30 math functions, this program is an exceptional value. Practicalc 64 also interacts with Practifile, forming the perfect small business bundle.
List $59.95. **Sale $24.95**. (Disk or Tape)

Practifile: Flexibility and large capacity make Practifile the ideal data-base manager for the Commodore 64. (3800 records per file, sorts 5 fields at once.) Files written with the program are compatible with Practicalc 64 and popular word processing programs such as EasyScript, Word Pro, PageMate and PaperClip. Finally, a full-featured data-base at an affordable price!
List $59.95. **Sale $24.95**. (Disk.)

64 Doctor: A special diagnostic program for the Commodore 64, 64 Doctor takes the guesswork out of isolating troublesome hardware problems. The program tests each piece of hardware to pinpoint defects and help prevent costly and time-consuming service calls. An essential program for all Commodore 64 users!
List $34.95. **Sale $19.95**. (Disk.)

PractiCalc II *Better than Lotus 1-2-3* *Coupon $44.95*

PractiCalc II, a fast, versatile spreadsheet with database and word processing features, does away with erasers, broken pencils and a wastebasket filled with scrap paper. PractiCalc II, with its functions and features, has the ability to complete simple and complex tasks. PractiCalc II is flexible enough to be used for checkbooks, alphabetized lists, home budgets and business financial statements. PractiCalc II is the tool of the eighties. List $69.95. **Sale $49.95.** Coupon $44.95. (Disk)

With PractiCalc II you can:

- Use 250 rows by 100 columns
- Use 36 math functions from simple addition to square roots and trig functions.
- Sort alphabetically and numerically.
- Use upper and lower case letters.
- "Hide" columns of numbers for special reports without losing data.
- Create fixed titles of several rows and/or columns.
- Replicate any data in any area.
- Adjust individual column widths.
- Use graphic display option.
- Set global and individual cell formatting.
- Use IF ... THEN statements.
- Edit labels and formulas.
- Format disks from within the program.
- View disk catalog from within the program.
- Write expanded labels up to 88 characters long.
- Insert, delete and move information with ease.
- Start using PractiCalc II within ten minutes of opening the package.
- Consolidate separate spreadsheets for totalling.
- Search for known and variable entries.

Add $3.00 for shipping, handling and insurance. Illinois residents please add 6% tax. Add $6.00 for CANADA, PUERTO RICO, HAWAII, ALASKA, APO-FPO orders. Canadian orders must be in U.S. dollars. WE DO NOT EXPORT TO OTHER COUNTRIES.

Enclose Cashiers Check, Money Order or Personal Check. Allow 14 days for delivery, 2 to 7 days for phone orders, 1 day express mail!

VISA — MASTER CARD — C.O.D.

No C.O.D. to Canada, APO-FPO.

PROTECTO

We Love Our Customers

Box 550, Barrington, Illinois 60010

312/382-5244 to order

Commodore 64

Computer Learning Pad

- **Makes graphic tablets Obsolete**
- **Includes Special Printer Feature**

Hi-Resolution!

Sale! $37.95

Now you get this **Fantastic Tech Sketch Computer Light Pen Program** with a **Professional Light Pen Free!** ($39.95 value) plus the **Micro Illustrated Graphics Pen Program** that allows you to draw on your T.V. or monitor screen (better than Gibsons $99 light pen). Whatever you can draw on the screen you can print on your printer (A Tech Sketch Exclusive.) (Disk) List $59.95 **Sale $37.95.**

Also available is **Lite Sprite**, a light pen driven sprite builder (List $39.95 **Sale $29.95**).

MUSIC PORT

The ultimate music synthesizer and multi-track recording system for the Commodore 64. A **Full-sized REAL Keyboard** and all software including printing to the printer and preprogrammed songs are included. (Disk) List $149.95 **Sale $99.00.**



Fully Responsive "MUSICIANS" Keyboard

Sale! $99.00

No Extra Software Required



Add $3.00 for shipping, handling and insurance. Illinois residents please add 6% tax. Add $6.00 for CANADA, PUERTO RICO, HAWAII, ALASKA, APO-FPO orders. Canadian orders must be in U.S. dollars. WE DO NOT EXPORT TO OTHER COUNTRIES.

Enclose Cashiers Check, Money Order or Personal Check. Allow 14 days for delivery, 2 to 7 days for phone orders, 1 day express mail!

VISA — MASTER CARD — C.O.D.

No C.O.D. to Canada, APO-FPO.

PROTECTO

We Love Our Customers

Box 550, Barrington, Illinois 60010

312/382-5244 to order

Circle 15 on Reader Service card.

Circle 15 on Reader Service card.

American Educational Computer

NEW NEW

• Learn at home • Easy To Use • Colorful Graphics • Motivating and Fun • Teacher Designed

All programs were written by teachers and have been classroom validated. These programs teach in a standard classroom format with rewards as the user gets through the various lessons.

(Disk)

US Geography Facts — Has 35 pre-programmed lessons plus an authoring system that lets you create your own lessons. Excellent for teaching and reinforcing factual knowledge of the U.S. After completing two lessons the user earns the right to play a unique and challenging maze game. Fantastic educational value.
List $29.95. **Sale $16.95.**

US Government Facts — 35 lessons plus authoring system included. This program was designed for the following: • Eighth grade American History • Ninth grade Civics • High School electives in government • College refresher courses in government and American History. Fantastic aid to learning about American government.
List $29.95. **Sale $16.95.**

(Disk)

Commodore 64

(Disk)

AEC Spelling — A series of seven educational software programs for grades 2 through 8. It teaches the spelling of 4,000 words most commonly used in writing (98% of most people's writing vocabulary). The word lists used are the result of over 25 years of research into the writing/spelling needs of children and adults. Each grade level consists of one two-sided disk with word lists on one side and study activities on the other. The activities are designed to develop mastery in spelling utilizing a Test/Teach/Test approach. A pre-test is used to find out which words a user cannot spell correctly. These are recorded on a "Words To Study" list. The activities for learning these words are provided. Finally, a post-test is taken by the learner to measure progress. The approach is simple and rewards are built in. List $99.95. **Special Sale — 7 programs $34.95**. *Individual programs $19.95. (Specify grades 2-8).*

(Disk)

Commodore 64

(Disk)

Reading Comprehension Skills — Reading Comprehension Skills, 1, 2, and 3 help the learner develop the ability to read with understanding. The learner does work with cause and effect, similarities and differences, predicting outcomes, finding main ideas, differentiating between fact and opinion, etc.

	List	Sale
Level 1 (grades 1-3)	$29.95	**$16.95**
Level 2 (grades 4-6)	$29.95	**$16.95**
Level 3 (grades 7-8)	$29.95	**$16.95**

Words In Reading (Vocabulary) — Learn About Words In Reading, 1 and 2 teaches the structure of words to ensure success in reading. Such topics as prefixes, suffixes, contractions, synonyms, etc., are among the structural skills included in the program to promote progress and good grades in reading.

	List	Sale
Level 1 (grades 1-3)	$29.95	**$16.95**
Level 2 (grades 2-4)	$29.95	**$16.95**



(Disk)

Add $3.00 for shipping, handling and insurance. Illinois residents please add 6% tax. Add $6.00 for CANADA, PUERTO RICO, HAWAII, ALASKA, APO-FPO orders. Canadian orders must be in U.S. dollars. WE DO NOT EXPORT TO OTHER COUNTRIES.
Enclose Cashiers Check, Money Order or Personal Check. Allow 14 days for delivery. 2 to 7 days for phone orders. 1 day express mail!
VISA — MASTER CARD — C.O.D.
No C.O.D. to Canada, APO-FPO

PROTECTO
We Love Our Customers
Box 550, Barrington, Illinois 60010
312/382-5244 to order

Com-64 TIMEWORKS® Com-64

Evelyn Wood Speed Reading



The EVELYN WOOD DYNAMIC READER provides you with the exercises and tools you need to help you increase your reading comprehension and speed. You can use your own personal computer and develop your skills at your own pace. You can learn the essential techniques of Dynamic Reading in your own home — at any time that is convenient for you. You can repeat exercises as often as you wish to assure that you maintain optimal reading efficiency.

SALE $44.95

Evelyn Wood *Dynamic Reader* List $69.95

An effective and enjoyable way to improve your reading comprehension, retention and speed.

(See Page 29, 30, 54)

Home Management Sale

Data Manager 1

A general information storage and retrieval system — with exclusive "X-SEARCH" Feature.

List $24.95. **Sale $16.95.**



The Electronic Checkbook

Check recording, sorting and balancing system.

List $24.95. **Sale $16.95.**

The Money Manager

Home and business budget and cash flow system.

List $24.95. **Sale $16.95.**

All three Programs for only $44.95

Cave of the Word Wizard

For Commodore 64 Computers

An Intriguing Way to Develop Spelling Skills Using Human Speech and Arcade Action.

This state-of-the-art educational program includes 500 spoken words in 10 spelling skill levels and makes full use of the sound capabilities of your computer. The Wizard will talk to you in clear human speech. No additional hardware is needed for your computer system. (Tape/Disk)

List $39.95. **Sale $22.95.**

Add $3.00 for shipping, handling and insurance. Illinois residents please add 6% tax. Add $6.00 for CANADA, PUERTO RICO, HAWAII, ALASKA, APO-FPO orders. Canadian orders must be in U.S. dollars. WE DO NOT EXPORT TO OTHER COUNTRIES.

Enclose Cashiers Check, Money Order or Personal Check. Allow 14 days for delivery, 2 to 7 days for phone orders, 1 day express mail!

VISA — MASTER CARD — C.O.D.

No C.O.D. to Canada, APO-FPO.

PROTECTO

We Love Our Customers

Box 550, Barrington, Illinois 60010

312/382-5244 to order

Circle 15 on Reader Service card.

Circle 15 on Reader Service card.

DesignWare™

Learning Comes Alive

Rated No. 1 in Computer Education

☆ ☆ ☆ **Real Learning** ☆ ☆ ☆

Grammar Examiner

Now you can learn proper grammar as well as spelling. You are required to edit paragraphs or answer grammar questions as you move up the ranks of newspaper reporter. Fantastic learning capabilities.
(Grades 5 and up.) (Disk.) List $44.95.
Sale $29.95.

Spellakazam

Race the magician to spell over 400 prepared words (or enter your own). If you succeed you release the animals, otherwise you seal their fate. (Ages 7 and up) (Disk.)
List $34.95.
Sale $19.95.

States & Traits

Learn about U.S. geography and the famous facts of each state. You must piece states in with only mountains and river. Traits include problems like bordering states and rivers, historical facts, current trivia and capitols.
(Ages 9 and up.) (Disk.) List $44.95.
Sale $27.95.

European Nations And Locations

Learn country names, capitals, bordering nations, geographic landmarks, major mountain ranges, rivers and lakes, historical and cultural facts, and where they belong on a map in achallenging and fun game for the whole family. Fantastic way to learn about the countries of Europe. (Disk) List $44.95 Sale **$29.95.**



Commodore 64



The Body Transparent

Teaches the names, locations, and functions of organs and bones in the human body, plus important facts about them. Includes both the male and female body, so you can learn the similarities and differences between them. Move bones and organs to the proper parts of the body and match correct parts to the facts and functions presented. Fantastic education of the Human Body.
(Disk) List $44.95 **Sale $29.95.**

Commodore 64



Add $3.00 for shipping, handling and insurance. Illinois residents please add 6% tax. Add $6.00 for CANADA, PUERTO RICO, HAWAII, ALASKA, APO-FPO orders. Canadian orders must be in U.S. dollars. WE DO NOT EXPORT TO OTHER COUNTRIES.

Enclose Cashiers Check, Money Order or Personal Check. Allow 14 days for delivery, 2 to 7 days for phone orders, 1 day express mail!

VISA — MASTER CARD — C.O.D.

No C.O.D. to Canada, APO-FPO.

PROTECTO

We Love Our Customers

Box 550, Barrington, Illinois 60010

312/382-5244 to order

Commodore 64

$29.95 KEYBOARD $29.95

- Play "no-fault" music instantly
- Never hit a sour note
- Play eight different instruments
- Play along with background rhythms
- Make your own music
- Develop musical competence and confidence
- Learn notes on a music keyboard
- Develop sense of rhythm
- Begin learning music theory





ColorTone Keyboard — Now you can play and learn just like on an organ. Just point to one of the colortone's preset songs, change the musical scale you are playing in or make your Commodore 64 sound like one of eight different instruments. As you play, you'll see the notes you're hearing displayed on a musical staff then record your musical creations to listen to them again and again. List $59.95. **Sale $29.95.**

Turn Your Commodore-64 Into A Sophisticated Musical Instrument

"The Program That Gives You A Reason To Buy A Commodore-64."
New York Times.

MusiCalc

MusiCalc 1 — Synthesizer & Sequencer

MusiCalc 2 — ScoreWriter

MusiCalc 3 — Keyboard Maker

Synthesizer & Sequencer

This 1st step turn your Commodore-64 into a sophisticated musical instrument — a three voice synthesizer and fully interactive step sequencer play along with pre-recorded songs or develop your own and record the music you create. (Disk)

List $59.00. **Sale $29.95.**

ScoreWriter

Combine with Musicalc 1 and a graphics printer (Super-10) to produce sheet music from your original composition. (Disk) List $39.95. **Sale $19.95.**

Keyboard Maker

Turns your Commodore-64 into a musical keyboard. Comes with over 30 pre-set keyboard scales from Classical to Rock. Requires Musicalc 1. (Disk) List $39.95. **Sale $19.95.**

With Musicalc **anyone** can • Make and record sophisticated music • Print out sheet music from your creations • Turn your computer into a keyboard • **No experience necessary!**

Add $3.00 for shipping, handling and insurance. Illinois residents please add 6% tax. Add $6.00 for CANADA, PUERTO RICO, HAWAII, ALASKA, APO-FPO orders. Canadian orders must be in U.S. dollars. WE DO NOT EXPORT TO OTHER COUNTRIES.

Enclose Cashiers Check, Money Order or Personal Check. Allow 14 days for delivery, 2 to 7 days for phone orders, 1 day express mail!

VISA — MASTER CARD — C.O.D.

No C.O.D. to Canada, APO-FPO.

PROTECTO

We Love Our Customers

Box 550, Barrington, Illinois 60010

312/382-5244 to order

Circle 15 on Reader Service card.

Circle 15 on Reader Service card.

IMAGIC

Eye Grabbing Living Graphics

The Time Machine

Based on H.G. Wells' science fiction classic, THE TIME MACHINE adds unique joystick action, high-resolution graphics and extensive animation to Wells' ageless prose. Travel through the treacherous time tunnel. Venture into the mysterious land of the future. Befriend the gentle Eloi and struggle to save them from evil Morlocks who lurk in the dangerous underworld. Regain your time machine at all costs — or your tale will end in tragedy! (Disk) List $39.95. **Sale $29.95.**



Injured Engine

Work with an accurate cutaway representation of a functioning automobile engine. Brilliant graphics detail various engine systems and parts. Learn the names of each part and how it relates to the other parts of the engine, then, use your knowledge to diagnose computer-generated engine problems. Inspect and test at will but remember everything costs! Work against the clock to tune and repair the motor to perfect running condition. (Disk) List $39.95. **Sale $27.95.**





Speak and Seek

It talks!! Speak and Seek teaches the alphabet to children, ages 2-5. It shows children how to print letters in capital and lower cases, pronounces the letter as it is drawn and asks them to find and press the letter on the keyboard. Incorrect answers prompt a variety of helping phrases, such as "Try a little to the right" or "Try higher," and other encouraging and amusing feedback. The make a creature appear that starts with the collect letter. (Disk) List $39.95. **Sale $27.95.**

Macbeth

Shakespeare's enthralling play of murder, greed and intrigue comes to life in this startlingly textured and vivid treatment. Armed with your wits, an impeccably detailed edition of the Scottish play and a learned mentor who questions and guides your insights and judgements, the play's the thing for you to solve! An engrossing and educational interactive adventure!. (Disk) List $39.95. **Sale $29.95.**

Commodore 64



Demon Attack

Winged warriors wreak havoc from above! Only your laser cannon stands between you and oblivion! Blast those bizarre demons. Your arsenal includes missiiles and sheer intestinal fortitude. Only the strong survive! (Disk) List $24.95. **Sale $16.95.**

Commodore 64

Nova Blast

Pilot your own Novon Skysweeper above the underwater city. You must defend four cities in your quadrant from alien assault. Use your radar to detect enemy activity. Race to protect these civilized outposts in a deadly game of skill and strrategy. (Disk) List $24.95. **Sale $16.95.**

Add $3.00 for shipping, handling and insurance. Illinois residents please add 6% tax. Add $6.00 for CANADA, PUERTO RICO, HAWAII, ALASKA, APO-FPO orders. Canadian orders must be in U.S. dollars. WE DO NOT EXPORT TO OTHER COUNTRIES.

Enclose Cashiers Check, Money Order or Personal Check. Allow 14 days for delivery, 2 to 7 days for phone orders, 1 day express mail!

VISA — MASTER CARD — C.O.D.

No C.O.D. to Canada, APO-FPO.

PROTECTO

We Love Our Customers

Box 550, Barrington, Illinois 60010

312/382-5244 to order

Circle 15 on Reader Service card.



COMMODORE 64

IF YOU'RE SMART, YOU'LL GET FILTHY RICH.

FANTASTIC ADVENTURE — STRATEGY BOARD GAME!

(So good we bought out the factory)

"ANOTHER PROTECTO EXCLUSIVE"

*SALE PRICE ONLY **$19.95**

*includes beautiful $8.95 leatherette dust cover for your COM-64 Computer

Factory List Price $49.95

THE BEST ADVENTURE — STRATEGY BOARD GAME IN THE U.S.A.!

Are you eager for new challenges...ready to pit your skill and luck against others in an attempt to corner the world oil market? If so, Oil Barons is your game.

Starting with 4 parcels of land and over $1 million, you search for that ever-elusive gusher. The computer does all the work, including banking and scorekeeping, freeing you to plan your strategy and make decisions that will ultimately determine your success.

Obstacles like government regulations, well fires, and hurricanes complicate matters, but the fun of increased land holdings, striking it rich, and even unloading worthless parcels on the uninitiated, more than make up for the setbacks.

FOR ALL AGES — Family, schools; businessmen, stockbrokers, oilmen etc. One to eight players, large 4 color game board, over 200 playing pieces, two sided disk and manual in a large colorful box! Keyboard controlled.

Disk Drive Cleaner $19.95

Everyone needs a disk drive doctor

(Coupon Price $16.95)

Facts

- 60% of all drive downtime is directly related to poorly maintained drives.
- Drives should be cleaned each week regardless of use.
- Drives are sensitive to smoke, dust and all micro particles.
- Systematic operator performed maintenance is the best way of ensuring error free use of your computer system.

The Cheetah disk drive cleaner can be used with single or double sided 5¼" disk drives. The Cheetah is an easy to use fast method of maintaining efficient floppy diskette drive operation.
The Cheetah cleaner comes with 2 disks and is packed in a protective plastic folder to prevent contamination. List $29.95. **Sale $19.95.** ***Coupon $16.95.**

Add $3.00 for shipping, handling and insurance. Illinois residents please add 6% tax. Add $6.00 for CANADA, PUERTO RICO, HAWAII, ALASKA, APO-FPO orders. Canadian orders must be in U.S. dollars. WE DO NOT EXPORT TO OTHER COUNTRIES.
Enclose Cashiers Check, Money Order or Personal Check. Allow 14 days for delivery, 2 to 7 days for phone orders, 1 day express mail!
VISA — MASTER CARD — C.O.D.
No C.O.D. to Canada, APO-FPO.

PROTECTO
We Love Our Customers
Box 550, Barrington, Illinois 60010
312/382-5244 to order

Circle 15 on Reader Service card.

Commodore 64 EPYX™ Commodore 64

The Best Arcade Games Around



World's Greatest Baseball — Finally a great sports game. Realistic right down to the playing field. Control all the actions even the outfielders. Play realistic baseball all year round. (Fantastic graphics, action, and sound!) (Disk) List $34.95. **Sale $22.95.**

Ballblazer — Unique split-screen, 3-D graphics give you and your opponent a first person view of the field of play. You race across the playfield in your Rotofoil trying to capture the ball and fire it through the goal before your opponent. The winner is the player with the most points at the end of the timed competition. Hold onto your joystick and keep that finger on the fire button, this is the type of two player head-to-head action you've been waiting for. Two Players. (Disk) List $29.95. **Sale $21.95.**

Fast Load Cartridge — Load, save and copy disks five times faster than normal. It plugs into the cartridge port of the Commodore 64 and goes to work automatically, loading disks with ease. And that's only the beginning. It can copy a single file, copy the whole disk, send disk commands, and even list directories without erasing programs stored in memory. (Cartridge) List $39.95. **Sale $24.95.**

Barbie — The biggest name in dolls. Browse through Barbie's closet full of beautiful clothing and dress her for the party. You can cut her hair or make it longer and color it or change the style. Buy new clothing at the boutique or any of the six other specialty shops, or even go to the dress shop and create Barbie's designer clothes with the help of the computer. The combinations are endless and so is the fun. One or two players. (Disk) List $39.95. **Sale $24.95.**

G.I. Joe — The best selling toy soldier is now available as an activity toy on the home computer. Select the battle situation then choose the equipment you think you will need to get the job done. Choose from a number of uniforms and weapons in your well stocked arsenal and get ready for the action. Play alone or with a friend, if you plan the right strategy you will complete the mission if not you will have to try again. One or two players. (Disk) List $39.95. **Sale $24.95.**

Hot Wheels — Now all the action and fun from playing with Hot Wheels cars is taken one step further on the home computer. Hot Wheels lets you choose your play activity from repairing cars to the destruction derby. You can actually play the activities along with a partner on the computer screen, even build and customize your own cars. A whole new way to play Hot Wheels. One or two players. (Disk) List $39.95. **Sale $24.95.**

Break Dance — Break Dance is an action game in which your dancer tries to break through a gang of break dancers descending on him. "A simon-like game" where your dancer has to keep the steps of the computer controlled dancer, and even a free dance segment where you develop your own dance routines and the computer plays them back for you to watch. Now anyone can break dance!! (Disk) List $39.95 **Sale $24.95.**

Rescue On Fractalus! — Your mission is to fly your Valkyrie Fighter through the Jaggi defenses and rescue the downed Ethercorps pilots. Sounds easy, but don't let it fool you. It's tough enough jut to navigate the mountains and canyons of Fractalus, but try doing it while destroying enemy gun emplacements or dodging suicide saucers. We supply the Long Range Scanner, Dirac Mirror Shield and Anti-Matter Bubble Torpedoes... YOU supply the skill and guts! One Player. (Disk) List $29.95. **Sale $21.95.**

Add $3.00 for shipping, handling and insurance. Illinois residents please add 6% tax. Add $6.00 for CANADA, PUERTO RICO, HAWAII, ALASKA, APO-FPO orders. Canadian orders must be in U.S. dollars. WE DO NOT EXPORT TO OTHER COUNTRIES.

Enclose Cashiers Check, Money Order or Personal Check. Allow 14 days for delivery, 2 to 7 days for phone orders, 1 day express mail!

VISA — MASTER CARD — C.O.D.

No C.O.D. to Canada, APO-FPO.

PROTECTO

We Love Our Customers

Box 550, Barrington, Illinois 60010

312/382-5244 to order

ReRUN

Programs on cassette or disk that give you more time to enjoy your Commodore computer.

AVAILABLE NOW... a second collection of RUN magazine's best programs of 1984. ReRUN Volume II!

Great programs for the Commodore 64 and VIC-20, taken from the July through December issues.

With ReRUN, you'll get every program running in less time than it takes to read this ad! No tedious typing!

The new Volume II features:

- Helpful utilities like Datafile
- Educational programs like Speller
- Exciting games like Mystery of Lane Manor

You'll save yourself days of typing, build yourself a great reference library, and best of all—you'll enjoy your computer more. ReRUN is available on disk or cassette.

ReRUN Volume II, like its predecessor, promises to be in big demand. Orders for Volume I surpassed our expectations, so we've gone back to press for more. It's now available in limited quantities.

To order, simply return the coupon, or call TOLL FREE 1-800-258-5473. In New Hampshire, dial 1-924-9471. Charge it on your Visa, Mastercard, or American Express.

Order both volumes of ReRUN today and save $5 off the total price!

Commodore 64, VIC-20 & Plus/4 are registered trademarks of Commodore Business Machines, Inc.

Send me _____ copies of **ReRUN** Volume II on disk at $21.47.
Send me _____ copies of **ReRUN** Volume II on cassette at $11.47.
Send me _____ copies of **ReRUN** Volume I on disk at $21.47.
Send me _____ copies of **ReRUN** Volume I on cassette at $11.47.

YES! Enter my order for Volumes I & II and take $5 off my total order!

Volume I & II _____ DISKS Volume I & II _____ CASSETTES _____ TOTAL

Please specify disk or cassette.

CHECK/MO ☐ MC ☐ AE ☐ VISA ☐

NOTE: Prices include postage and handling. Foreign air mail, please add 45¢. US funds on US banks ONLY. Please allow 3-4 weeks for delivery.

Card# _____ Exp. Date _____
Signature _____
Name _____
Address _____
City _____ State _____ Zip _____

ReRUN • 80 Pine Street • Peterborough, NH 03458 4-85

Circle 73 on Reader Service card.

50% OFF **EDU-TAX** 50% OFF

EDU-TAX is a tax analysis program specifically designed for the average family.

Don't be caught suprised at tax time. Know exactly what your taxes will be all year long. EDU-TAX is a menu driven program with extensive on screen explanations. EDU-TAX includes these schedules and forms:

Form 1040
Schedule A — Itemized Deductions
Schedule B — Interest/Dividends
Schedule C — Business Income
Schedule D — Capital Gains/Losses
Schedule E — Supplemental Income
Schedule G — Income Averaging
Schedule W— Marital Deductions
Form 2106 — Unreimbursed Employee Expense
Form 2119 — Sales of Residence
Form 4684 — Casualties and Theft Losses

EDU-TAX is currently 50% off the suggested retail price of $50.00. EDU-TAX is now only **$25.00** plus $2.00 for shipping and handling. Direct only.

MasterCard VISA

EDU-TAX
P.O. Box 16785
San Antonio, TX 78216

CHECK OR MONEY ORDER

Texas Residents add 5%.
Commodore 64-Disk — Atari 48K-Disk

100,000 CHOOSE COMAL 50,000 USERS‡

(1) DISK BASED COMAL Version 0.14

- COMAL STARTER KIT—Commodore 64™ System Disk, Tutorial Disk (interactive book), Auto Run Demo Disk, Reference Card and COMAL FROM A TO Z book.
  $29.95 plus $2 handling

(2) PROFESSIONAL COMAL Version 2.0

- Full 64K Commodore 64 Cartridge
  Twice as Powerful, Twice as Fast
  $99.95 plus $2 handling (no manual or disks)
- Deluxe Cartridge Package includes:
  COMAL HANDBOOK 2nd Edition, Graphics and Sound Book, 2 Demo Disks and the cartridge (sells for over $200 in Europe). This is what everyone is talking about.
  $128.90 plus $3 handling (USA & Canada only)

CAPTAIN COMAL™ Recommends:

The COMAL STARTER KIT is ideal for a home programmer. It has sprite and graphics control (LOGO compatible). A real bargain—$29.95 for 3 full disks and a user manual.

Serious programmers want the Deluxe Cartridge Package. For $128.90 they get the best language on any 8 bit computer (the support materials are essential due to the immense power of Professional COMAL).

ORDER NOW:

Call TOLL-FREE: 1-800-356-5324 ext 1307 VISA or MasterCard ORDERS ONLY. Questions and information must call our Info Line: 608-222-4432. All orders prepaid only—no C.O.D. Send check or money order in US Dollars to:

COMAL USERS GROUP, U.S.A., LIMITED
5501 Groveland Ter., Madison, WI 53716

TRADEMARKS: Commodore 64 of Commodore Electronics Ltd; Captain COMAL of COMAL Users Group, U.S.A., Ltd
‡ estimated

Circle 150 on Reader Service card.

GOOD NEWS FOR COMMODORE OWNERS!

a system to help insure your financial survival in the '80s.

A LIFEWARE™ PRODUCT



LIFEPLAN™ is a financial planning tool designed for people without computer experience or accounting degrees. Middle-income families or singles will improve their financial outlook with help from LIFEPLAN™.

☐ First, LIFEPLAN™ shows you what your complete financial picture is today. Then, it works with you to produce positive results:

$ reduce or eliminate debt
$ establish or increase savings
$ manage expenses
$ plan for the future

☐ Over time, LIFEPLAN™ evaluates your progress and helps you stick to your financial plan.

☐ LIFEPLAN™ is easy to use. We took 4 years to research and test the system, *and. . .* **it works**. We are so confident that LIFEPLAN™ will help you that we offer a 100% money-back guarantee.

☐ ***100% MONEY-BACK GUARANTEE:***

You may return the undamaged product for any reason, within 30 days, for a full refund including shipping, less rebate.

Note: One disk drive required for program use.

☐ Order your copy today. You have nothing to lose. If you send for LIFEPLAN™ now, you'll receive a

☐ **Rebate Certificate** with your program, good for a $20 check.

Name _____

Street _____

City, State, Zip _____

64-A

☐ Check or money order enclosed for $99.95 + 1.50/shipping. (WA residents add 7.9% sales tax.)

Account Number ☐ MasterCard ☐ Visa

☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐

Expires: ____/____ Signature: _____

☐ Mail to: LIFEWARE, 2318 Second Ave. #64B, Seattle, WA 98121. VISA/MC orders may call (206) 322-5454 to order direct. Please allow 2-6 weeks for shipping.

LET IT SCROLL

By BRUCE JAEGER

Make your own marquee with this easy-to-use subroutine that lets you scroll those important (or just plain fun) messages across your screen.

Did you ever find yourself with a whole screen filled with graphics but still needing more room on the screen for more information? One way out is to clear the screen, print the information and then redraw the graphics. Not too efficient!

An easier and neater way is to use this brief Moving Marquee subroutine, which will scroll your information across the bottom of the screen (just like the electronic signs you often see on banks). Just set ME$ equal to your message and enter GOSUB 50000.

There are a couple of options you can use. Setting variable RE equal to 1 will make the message repeat until a key is pressed. (Set RE equal to 0 to cancel this option.)

By changing the number of CRSR DNs in line 50060, you can have the message scroll on a different line. You can change the speed of the message's scrolling by changing the variable DELAY in line 50080. A higher number will slow down the message; set it to zero, and watch the message scream by! R

Address all author correspondence to Bruce Jaeger, 1253 Ashland Ave., St. Paul, MN 55104.

Listing 1. *Moving Marquee program for the VIC-20.*

```
1 REM ********************************
2 REM **{27 SPACEs}**
3 REM **{6 SPACEs}MOVING MARQUEE{7 SPACEs}*
  *
4 REM **{27 SPACEs}**
5 REM **{7 SPACEs}BRUCE JAEGER{8 SPACEs}**
6 REM **{7 SPACEs}ST. PAUL, MN{8 SPACEs}**
7 REM **{27 SPACEs}**
8 REM ********************************
9 REM
1Ø REM
1ØØ REM DEMO PROGRAM, MARQUEE
11Ø REM
12Ø REM
13Ø ME$="THIS IS A TEST MESSAGE.{2 SPACEs}I
    T CAN BE "
131 ME$=ME$+"ANY LENGTH, UP TO ABOUT 21Ø CH
    ARACTERS. "
132 ME$=ME$+"JUST DON'T USE 'CONTROL' CHARA
    CTERS LIKE "
133 ME$=ME$+"'REVERSE' OR COLOR CHANGES."
14Ø REM ***************************
15Ø RE=Ø: REM DON'T REPEAT MESSAGE
16Ø GOSUB5ØØØØ
17Ø REM ***************************
18Ø RE=1: REM REPEAT MESSAGE UNTIL KEY PRES
    SED
19Ø ME$="THIS MESSAGE WILL REPEAT UNTIL A K
    EY IS PRESSED."
2ØØ GOSUB5ØØØØ
21Ø REM ***************************
22Ø END
23Ø REM
```

→

RUN It Right

VIC-20
Commodore 64

Listing 1 continued.

```
24Ø REM
25Ø REM
26Ø REM
5ØØØØ REM *** MARQUEE SUBROUTINE, VIC ***
5ØØ1Ø REM
5ØØ2Ø REM{5 SPACEs}PRINTS MESSAGE ME$
5ØØ3Ø REM
5ØØ4Ø SP$="{2Ø SPACEs}":REM 2Ø SPACES
5ØØ5Ø ME$=SP$+ME$+" ":X9=1
5ØØ6Ø CP$="{HOME}{22 CRSR DNs}{CRSR RT}"
5ØØ7Ø REM CP$ = "HOME, 22 CURSOR DOWNS, 1 C
     URSOR RIGHT"
5ØØ8Ø DELAY = 5Ø
5ØØ9Ø FOR XX = 1 TO DELAY : NEXT
5Ø1ØØ PRINT CP$;MID$(ME$,X9,2Ø);CHR$(19)
5Ø11Ø X9=X9+1:IFX9>LEN(ME$)THENX9=1
5Ø12Ø IF X9=1 AND RE=Ø THEN 5Ø15Ø
5Ø13Ø IF PEEK(2Ø3)=64 THEN 5ØØ9Ø
5Ø14Ø PRINTCP$;LEFT$(SP$+SP$,2Ø);CHR$(19)
5Ø15Ø RETURN
```

Listing 2. *Changes in Moving Marquee program for the C-64.*

```
5ØØØØ REM *** MARQUEE SUBROUTINE, 64 ***
5ØØ1Ø REM
5ØØ2Ø REM{5 SPACEs}PRINTS MESSAGE ME$
5ØØ3Ø REM
5ØØ4Ø SP$="{2Ø SPACEs}":REM 2Ø SPACES
5ØØ5Ø ME$=SP$+SP$+ME$+" ":X9=1
5ØØ6Ø CP$="{HOME}{24 CRSR DNs}{CRSR RT}"
5ØØ7Ø REM CP$ = "HOME, 24 CURSOR DOWNS, 1 C
     URSOR RIGHT"
5ØØ8Ø DELAY = 5Ø
5ØØ9Ø FOR XX = 1 TO DELAY : NEXT
5Ø1ØØ PRINT CP$;MID$(ME$,X9,38);CHR$(19)
5Ø11Ø X9=X9+1:IFX9>LEN(ME$)THENX9=1
5Ø12Ø IF X9=1 AND RE=Ø THEN 5Ø15Ø
5Ø13Ø IF PEEK(2Ø3)=64 THEN 5ØØ9Ø
5Ø14Ø PRINTCP$;LEFT$(SP$+SP$,38);CHR$(19)
5Ø15Ø RETURN
```

Programming Briefs

Handy Reference Listing

By MARY D. BRIGITO

New Disk (format)	OPEN15,8,15,"NO:name,ID# CLOSE15
Save and Replace	SAVE"@0:name",8
Verify	VERIFY"name",8 or "*"
Load	LOAD"name",8
List Directory	LOAD"$",8 then LIST
Initialize	OPEN15,8,15 PRINT#15,"I" CLOSE15
Scratch	OPEN15,8,15,"s0:name" CLOSE15
Validate	OPEN15,8,15 PRINT#15,"V" CLOSE15
RENAME	OPEN15,8,15 PRINT#15,"R0:newname = 0: oldfile" CLOSE15

Table. *Basic disk commands.*

Circle 32 on Reader Service card.

This Passover, start a new holiday tradition with Davka, the world's leading developer of fine Jewish software. You can study the timeless traditions and customs of Passover with **How to Conduct a Seder,** an entertaining instructional program with colorful animation, all the popular Seder melodies, and concise text. Whether you're a Seder veteran of Passovers past, or attending your very first Seder, you'll find HOW TO CONDUCT A SEDER helpful and informative.
ONLY *$29.95*

Davka CORPORATION

WHY IS THIS SOFTWARE DIFFERENT FROM ALL OTHER SOFTWARE ?
Because it's "Kosher for Passover"

And if selecting unusual and welcome Seder gifts for your family or hosts is your goal, look to Davka for these other programs guaranteed to provide hours of creative fun long after the Seder has ended.

Crumb Chaser—Chase the crumbs and sweep them up in a frantic attempt to rid your house of pre-Passover leaven. If you know your Passover facts, you can get more playing time. Joystick required.
Ages 7 and up *$24.95*

Israel Geography—You'll become an Israeli Sherlock Holmes as you attempt to pinpoint key locations in the Holy Land.
Ages 10 and up *$24.95*

All About Passover—A comprehensive guide to Passover traditions, customs, and observances, complete with colorful animation and helpful text.
Ages 10 and up *$29.95*

Samson and Delilah—Arcade fans will take delight in Samson's action-packed struggle to reach the Philistine temple.
Ages 7 and up *$24.95*

Jewish I.Q. Baseball—For all-around family fun there's Davka's popular Jewish Knowledge game, with outstanding sound and animation.
For all ages *$24.95*

Search for Your Israeli Cousin—Just the game for lovers of mystery and sleuthing. It's a trek through modern Israel to find a mysterious long-lost relative.
Ages 10 and up *$24.95*

for speedy delivery before Passover CALL TOLL-FREE 800-621-8227

MasterCard VISA

AND HERE'S AN OFFER YOU WON'T WANT TO *PASS OVER!*
Buy two or more programs—**save 25%!**
Buy any six programs **for $99—save over $50!**

for the Commodore 64 with disk drive

Name
Street Address
City, State, Zip
Phone # ( )
Enclose check or complete below.
Please charge my:
☐ American Express ☐ Visa
☐ MasterCharge
Card # Exp. Date
Signature

DAVKA CORPORATION
845 N. Michigan Ave., Suite 843
Chicago, Ill. 60611 (312) 944-4070

QTY.	PROGRAM NAME	LIST PRICE	DISC. PRICE	AMT.
	HOW TO CONDUCT A SEDER	$29.95	$22.50	
	SAMSON AND DELILAH	24.95	18.75	
	ISRAEL GEOGRAPHY	24.95	18.75	
	JEWISH I.Q. BASEBALL	24.95	18.75	
	ALL ABOUT PASSOVER	29.95	22.50	
	SEARCH	24.95	18.75	
	CRUMB CHASER	24.95	18.75	
	PASSOVER BONUS PACK (any six programs)	150.00	99.00	
	SHIPPING & HANDLING CHARGES			2.00
	TOTAL CHARGES			

Commodore 64 is a registered trademark of Commodore Electronics Ltd.

The Number Puzzle

By ZOLTAN SZEPESI

This puzzle might appear simple, but it offers you a real challenge.

The Fifteen Puzzle evoked as much excitement during the last quarter of the nineteenth century as the Rubik's Cube (or Magic Cube) does now.

The Fifteen Puzzle and the Rubik's Cube are very similar in principle. The Fifteen Puzzle consists of 15 scrambled numbers on a 4 × 4 square (one position is empty), and you must put the numbers into numerical order. Both games are extremely addictive; however, it is much easier to solve the Fifteen Puzzle than the Rubik's Cube.

The Fifteen Puzzle was invented in 1878 by an Englishman named Sam Lloyd. The idea of the game is very simple. The numbers from 1 to 15 are randomly placed in 16 squares, with one square empty. The object of the game is to arrange the numbers in numerical order, as in Figure 1. A number that is adjacent to the empty square can be moved into that square, thus leaving its own place empty for another number to move in.

There are almost 21 trillion, or precisely $16! = 16 \times 15 \times 14 \times 13 \times 12 \times 11 \times 10 \times 9 \times 8 \times 7 \times 6 \times 5 \times 4 \times 3 \times 2 \times 1$ possible starting positions for the Fifteen Puzzle. Mathematicians showed that half of these positions cannot be solved. According to D.D. Spencer's *Game Playing with Computers*, mathematicians derived a simple rule for checking whether or not a given setup can be solved.

From the first to the fifteenth po-

Statements	Steps
30–40	The computer sets the border and screen color and prints the title.
50–80	You are asked if you want to read the instructions, which are in statements 1300–1580.
100–210	The computer draws the 4 × 4 square.
230–270	This subroutine creates the random order of numbers 1 to 16 (notice the way it doesn't allow the same number to appear more than once in the series).
510–580	Subroutine to check if solution is possible. If not, it goes back and creates another set of random numbers.
600–680	If solution is possible, the program goes to subroutine 600, which displays the numbers on the game board. Play starts. Timer is set to 0. You press the number you want to move.
400–430	Subroutine 400 tells the board location of this number.
700–830	Subroutine 700 checks whether or not it was a legal move. If it was not, the computer informs you of this and asks you to choose another number. If the move was legal, the program goes to the next step, to subroutine 900.
900–930	Subroutine 900 checks to see if the game is completed, i.e., if the numbers are in proper order. If they are not, you are asked to move another number.
940	If the game is completed, your last move is shown on the board, the time is read, and
1110–1260	the computer plays the first five measures of Beethoven's Fifth Symphony (in three voices).
950–990	You are congratulated and told how many moves and how much time it took you to finish the game.
1000–1030	You are asked if you want to play again.

Table 1. *Fifteen Puzzle program line descriptions.*

RUN It Right

C-64

A Real Music Keyboard for Just $99.00!

(Price Includes a Complete Music Software Package Featuring Color Graphics, Record and Playback!)

Tap the full power of your Commodore 64's* music capability with the new *affordable* MusicMate keyboard from Sequential.

The MusicMate is a fully functional, quality music keyboard with full-sized keys. Unlike other keyboards, the MusicMate doesn't tie up your expansion slot! Just plug your MusicMate into your Commodore's joystick port! And it's fully polyphonic so you can play 3 notes at a time! Best of all, the MusicMate is available at a very affordable price!

SOFTWARE INCLUDED!

The MusicMate comes with the Model 970 music program on diskette. You can select between eight different instrument sounds and record and playback up to 10 continuous minutes of your music.

Add our other exciting MusicWare packages and extend the MusicMate's capabilities! They're just $39.95 each:

SONG BUILDER (Model 971)

Build your own songs by overdubbing 3 layers of notes (each with its own instrument sound!) Or record 2 parts of your song and play the third part live. Song Builder also lets you change the key and speed of your music, and save your songs on diskette.

SONG EDITOR (Model 972)

See the songs you write with SONG BUILDER displayed on a traditional Grand Staff on your monitor. Conveniently edit your songs one note at a time.

SONG PRINTER (Model 973)

Print your songs in standard music notation (must be used with our SONG EDITOR or SONG BUILDER program).

SOUND MAKER (Model 974)

View a graphic display that looks like the front panel of a professional synthesizer to program the shape, volume and tone of your own personal sounds. Store them on diskette in groups of 20.

OUR GUARANTEE!

Playing music on a typewriter keyboard or a plastic overlay of miniature-sized keys limits your music. We know. We're the largest American manufacturer of professional synthesizers. Our Prophet keyboards are used by your favorite artists on stage and in the studio. We've put our experience in making quality musical instruments into every MusicMate keyboard to help you express the music in yourself and your family. If you're not completely satisfied just return your MusicMate within 10 days of receipt to Sequential for a full refund.

SEQUENTIAL

For a complete catalog send $2.00 to: Sequential, 3051 North First Street, San Jose, CA 95134.

Commodore 64 is a registered trademark of Commodore, Inc.
**1985, Sequential*

Yes, I want to play my own songs on the MusicMate!

Name (Please Print) _____

Street _____

City/State _____ Zip _____

Check or ☐ Money Order ☐ Visa ☐ MasterCard ☐ American Express Please do not send cash.

Card # ☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐

Valid from: _____ to: _____

Signature _____

Quantity	Item		Price
_____	MUSICMATE(S)	@ $99.00	_____
_____	SONG BUILDER	@ $39.95	_____
_____	SONG EDITOR	@ $39.95	_____
_____	SONG PRINTER	@ $39.95	_____
_____	SOUND MAKER	@ $39.95	_____
	Shipping and Handling		$4.00
	State Sales Tax*		_____
	TOTAL PRICE		_____

*Ca. residents, please add 6% sales tax.

Satisfaction guaranteed or your money back! This offer applies in the U.S. and Canada only.

Mail order form to: Sequential, Dept. RN, 3051 North First Street, San Jose, CA 95134
Please allow 2 – 4 weeks for delivery.

SYMBOL MASTER™

MULTI-PASS SYMBOLIC DISASSEMBLER FOR THE COMMODORE 64*

disassembles any 6502/6510 machine code program into beautiful source

- Learn to program like the experts!
- Adapt existing programs to your needs!
- Automatic LABEL generation.
- Outputs source code files to disk fully compatible with your MAE,* PAL,* CBM* or Develop-64* assembler, ready for re-assembly and editing!
- Outputs formatted listing to screen and printer.
- Automatically uses NAMES of Kernal jump table routines and all operating system variables.
- Generates list of equates for external addresses.
- Generates complete cross-referenced symbol table.
- Recognizes instructions hidden under BIT instructions.
- 100% machine code for speed.

(Symbol Master™ is not copy protected.)

ORDER NOW! Available on disk only. Introductory price $49.95 postpaid USA.

*MAE is a trademark of Eastern House.
PAL is a trademark of Pro-Line.
Commodore 64 is a trademark and CBM is a registered trademark of Commodore.
Develop-64 is a trademark of French Silk.

UNLEASH THE POWER OF YOUR COMMODORE 64 WITH THE ULTIMATE INTERFACE

- Control & monitor your home—appliances, lights & security system
- Intelligently control almost any device
- Connect to Analog-to-Digital Converters
- Control Robots
- Perform automated testing
- Acquire data for laboratory & other instrumentation applications
- Many other uses.

Don't make the mistake of buying a limited capability interface. Investigate our universally applicable Dual 6522 Versatile Interface Adapter (VIA) Board, which plugs into the expansion connector and provides:

Four 8-bit fully bidirectional I/O ports & eight handshake lines • Four 16-bit timer/counters • Full IRQ interrupt capability • Four convenient 16-pin DIP socket interface connections • Expandability up to four boards & sixteen ports.

ORDER NOW! Price $169, postpaid USA. Extensive documentation included. Each additional board $149.

COMMODORE 64™ SOURCE CODE!

"What's Really Inside the Commodore 64"

• Most complete available reconstructed assembly language source code for the C-64's Basic and Kernal ROMs, all 16K. • You will fully understand calls to undocumented ROM routines, and be able to effectively use them in your own programs. • Uses LABELS. Not a mere one-line disassembly. All branch targets and subroutine entry points are shown. • TABLES are fully sorted out and derived. • Completely commented, no gaps whatsoever. You will see and understand the purpose of every routine and every line of code! • Complete listing of equates to external label references. • Invaluable fully cross-referenced symbol table.

Order C-64 Source. $29.95 postpaid USA.

All orders shipped from stock within 24 hours via UPS. VISA/MasterCard welcomed.

SCHNEDLER SYSTEMS

1501 N. Ivanhoe, Dept. R4, Arlington, VA 22205
Information/Telephone Orders (703) 237-4796

Variables	Description
A$,B$,C$,D$	Building lines of the game board.
X	Position on the game board.
A(X)	Number at position X.
N,N$	Number in subroutine 600 for displaying game board.
M	Number of moves.
F	Flag in subroutine 500. F = 1, game solvable; F = 0, game not solvable.
F	Flag in subroutine 700. F = 0, legal move and its value is the change in position; F = 1, not legal move.
SU	Sum in subroutine 500.
S	Start of sound chip.
H1,H2,H3 and L1,L2,L3	High- and low-frequency codes in subroutine 1100.

Table 2. *Variables used in Fifteen Puzzle program.*

1	2	3	4
5	6	7	8
9	10	11	12
13	14	15	

Figure 1. *Gameboard of Fifteen Puzzle.*

sition, count how many numbers are of lower value than the number in the starting position (count the empty space as 16), then add them together. Also, add 1 to the sum if the empty square is in one of the following positions: 2, 4, 5, 7, 10, 12, 13, 15. If the sum is even, then the puzzle can be solved; if it is odd, then it cannot be solved.

The difficulty in solving the Fifteen Puzzle depends on the particular order of the numbers. With some practice, you will learn how to succeed faster and in fewer steps.

However, be careful. This game is addictive. Once you start, it's difficult to stop.

When my wife and I began playing this game, our average number of moves for our first 13 games was 145, with a minimum of 75 and a maximum of 208. Our solving time ranged from 5½ to 19 minutes, with an average of 10. Our scores have improved with practice. R

Address all author correspondence to Zoltan Szepesi, 2611 Saybrook Drive, Pittsburgh, PA 15235.

Listing 1. *Fifteen Puzzle program.*

```
1 REM FIFTEEN PUZZLE V 4.4 FOR C-64,WRITTEN
  FOR TRS-8Ø BY W.L.COLSHER
1Ø REM KB/MICROCOMP.,V.5,P.114,FEB.1981.MOD
  IFIED AND CONVERTED FOR C-64 BY
2Ø REM Z.SZEPESI 2611 SAYBROOK DRIVE,PITTSB
  URGH,PA 15235
3Ø POKE53281,13:POKE5328Ø,2:PRINT"{SHFT CLR
  }{CTRL 1}{2 CRSR DNs}{12 SPACEs}FIFTEEN
  PUZZLE."
4Ø PRINT"{12 SPACEs}{15 COMD Us}"
5Ø PRINT"{2 CRSR DNs}{2 SPACEs}**DO YOU NEE
  D INSTRUCTIONS?"
6Ø PRINT"{CRSR DN}{4 SPACEs}PRESS 'Y', OR A
  NY OTHER KEY FOR NO."
7Ø GETA$:IFA$=""THEN7Ø
8Ø IFA$="Y"THENGOSUB131Ø
9Ø REM ***INITIALISATION*****************
  *****
```

Listing 1 continued.

```
100 DIM A(20):M=0:S=54272:PRINT"{SHFT CLR}"
110 A$=" {SHFT U}{4 SHFT Cs}{COMD R}{4 SHFT
     Cs}{COMD R}{4 SHFT Cs}{COMD R}{4 SHFT
    Cs}{SHFT I}":REM SH=SHIFT;CM=COMMODORE
    KEY IN FOLLOWING
120 REM SPACE;SH U;4 SH C;CM R;4 SH C;CM R;
    4 SH C;CM R;4 SH C;SH I
130 B$=" {COMD Q}{4 SHFT *s}{SHFT +}{4 SHFT
     *s}{SHFT +}{4 SHFT *s}{SHFT +}{4 SHFT
    *s}{COMD W}"
140 REM SPACE;CM Q;4 SH C;SH +;4 SH C;SH +;
    4 SH C;SH +;4 SH C;CM W
150 C$=" {SHFT B} {3 SHFT SPACEs}{SHFT -}{4
     SHFT SPACEs}{SHFT -}{4 SHFT SPACEs}{SH
    FT -}{4 SHFT SPACEs}{SHFT B}"
160 REM SPACE;SH B;4 SPACE;SH B;4 SPACE;SH
    B;4 SPACE;SH B;4 SPACE;SH B
170 D$=" {SHFT J}{4 SHFT Cs}{COMD E}{4 SHFT
     Cs}{COMD E}{4 SHFT Cs}{COMD E}{4 SHFT
    Cs}{SHFT K}"
180 REM SPACE;SH J;4 SH C;CM E;4 SH C;CM E;
    4 SH C;CM E;4 SH C;SH K
190 PRINTA$:FORI=1TO3
200 PRINTC$:PRINTC$:PRINTB$:NEXTI
210 PRINTC$:PRINTC$:PRINTD$:IFQ=1THEN RETUR
    N
220 PRINT"{2 CRSR DNs}{2 SPACEs}{CTRL 9}**W
    AIT PLEASE"
230 FORX=1TO16:A(X)=0:NEXT:REM **CREATING A
     SET OF RANDOM NUMBERS**
240 FORI=1TO16
250 X=INT(16*RND(RND(0)))+1:IFA(X)THEN250
260 A(X)=I:NEXT
270 GOSUB510:TI$="000000":IFF=0THEN230
280 PRINT:GOSUB610:PRINT:PRINT"{16 SPACEs}"
    :REM 17 SPACES
290 PRINT"{CRSR UP}{2 SPACEs}*YOUR MOVE";:X
    $="":X1$="":REM **PLAY STARTS*****
300 GETX$:IFX$=""THEN300
310 IFX$="{LEFT ARROW}"THENX=1:GOTO350
320 IFX$<>"1"GOTO340
330 GETX1$:IFX1$=""GOTO330
340 X$=X$+X1$:X=VAL(X$)
350 PRINTX:GOSUB410:GOSUB710:IFF THEN370
360 PRINT"{CRSR DN}{2 SPACEs}*ILLEGAL MOVE,
    RE-ENTER":GOTO280
370 A(X+F)=A(X):A(X)=16:GOTO910
380 M=M+1:GOTO280
400 REM ***CONVERT NUMBER TO LOCATION IN AR
    RAY***
410 FORI=1TO16:IFA(I)=XTHEN430
420 NEXT
430 X=I:RETURN
500 REM ***VERIFY IF SOLUTION IS POSSIBLE**
    ******
510 F=0:SU=0:FORI=1TO15:FORJ=I+1TO16
520 IFA(I)>A(J)THENSU=SU+1
530 NEXTJ:NEXTI:RESTORE
540 FORI=1TO8:READX:IFA(X)=16THENSU=SU+1
550 NEXTI
560 A=INT(SU/2):IFA*2=SUTHENF=1
570 RETURN
580 DATA2,4,5,7,10,12,13,15
600 REM ***DISPLAY GAME BOARD**********
    ******
610 PRINT"{HOME}":PRINT:FORI=1TO4:PRINT
620 PRINTSPC(1):FORJ=1TO4:N=A((I-1)*4+J):PR
    INTSPC(1);:N$=STR$(N)
630 IFN<10THENPRINT" ";
640 IFN=16THEN N$="{3 SPACEs}"
650 PRINTN$;SPC(1);
660 NEXTJ:PRINT:PRINT
670 NEXTI
680 PRINT:RETURN
```


Circle 29 on Reader Service card.

HOW TO AVOID BECOMING A DINOSAUR.



If dinosaurs had kept up with their rapidly changing world, you might have a pet bronto today. (It's probably just as well they didn't, since they wouldn't fit into a small imported car anyway.)

The point is, if you don't want to get left behind today, you need a computer with the latest software and accessories. No question about it.

The only question is, "where do I buy it?"

Ah! We thought you'd never ask. Computer Warehouse, of course. Nice guys, great prices. Give us a call today. We'll get your shipment out bronto—er, *pronto*.

MONITORS

Commodore 1702	$209.95
Gorilla (green)	$ 79.00
Gorilla (amber)	$ 89.00

PRINTERS

Commodore 1526/802	$209.00
Commodore 803	$169.00
Panasonic 1090	$239.00
Gemini 10X	$249.00
Gemini 15X	$349.00
Power Type (Daisy Wheel)	$369.00
Radix 10	$499.00
ELITE 5 CD (Daisy Wheel) Direct connect for Commodore	$299.00
AXIOM AT 550	$259.00
Star SG10	$269.00
Star SD10	$399.00
Star SR10	$499.00
Okidata 82, 83, 84, 92, 93	CALL
Okimate 10 Color Printer	$199.00
Panasonic 1091	$299.00

DISK DRIVES

Commodore 1541	$199.00
Rana 1000	$199.00
Indus GT	$299.00
MSD Single Drive	$299.00
MSD Dual Drive	$499.00

ACCESSORIES

We carry a full line of covers, ribbons, storage cases, surge suppressors and cables.

MODEMS

Westridge Automodem	$69.95
MPP 1064	$79.95
Total Telecommunication	$69.95
Modem 300 by Commodore	$89.95

PRINTER INTERFACES

Cardco B	$39.95
Cardco G+	$69.95
TYMAC Connection	$79.95
TURBO GT	$69.95
AXIOM Interface	$79.95

SOFTWARE

Flight Simulator II	$36.95
Super Base 64	$59.95
Paper Clip (w/spell)	$79.95
Multiplan by Microsoft	$59.95
Word Pro 3 Plus	$39.95
Koala Touch Tablet	$69.95
Tax Advantage	$69.95
Write Now (Cardco)	$39.95
Mastertronic Disk Game (C64)	$ 7.99

DISKETTES*

Computer Warehouse ss/dd	$14.95
Elephant ss/sd	$13.95
Elephant ss/dd	$16.95
Maxell MD 1	$18.95
Maxell MD2D	$24.95
SKC ss/sd	$13.95
SKC ss/dd	$16.95

*Prices per box of 10

We carry a full line of Commodore Hardware and Software.

COMPUTER WAREHOUSE

(in FL) 305-274-3680 ; 1-800-372-0214

7222 S.W. 117th Avenue, Miami, FL 33183

Add 3% for shipping and handling charges. Ad prices reflect 3% cash discount. Credit card orders should add 3%. Prices subject to change without notice.

Listing 1 continued.

```
7ØØ REM ***CHECK FOR LEGAL MOVE*********
    ******
71Ø F=Ø:IFX>16THEN RETURN
72Ø IF(X=4ORX=8ORX=12)ANDA(X+1)=16THENRETUR
    N
73Ø IF(X=5ORX=9ORX=13)ANDA(X-1)=16THENRETUR
    N
74Ø IFX+1>16THEN76Ø
75Ø IFA(X+1)=16THENF=1
76Ø IFX-1<=ØTHEN78Ø
77Ø IFA(X-1)=16THENF=-1
78Ø IFX+4>16THEN8ØØ
79Ø IFA(X+4)=16THENF=4
8ØØ IFX-4<ØTHEN82Ø
81Ø IFA(X-4)=16THENF=-4
82Ø IFF THENPRINT"{CRSR DN}{26 SPACEs}":REM
     26 SPACES
83Ø RETURN
9ØØ REM ***CHECK FOR A WIN***************
    ******
91Ø FORI=1TO16
92Ø IFA(I)<>ITHEN38Ø
93Ø NEXT
94Ø GOSUB61Ø:T$=TI$
95Ø GOSUB111Ø:PRINT"{SHFT CLR}{CRSR DN}{2 S
    PACEs}*CONGRATULATIONS!!!"
96Ø PRINT"{CRSR DN}{3 SPACEs}YOU DID IT IN
    ONLY"M"MOVES!!"
97Ø PRINT"{2 CRSR DNs}{2 SPACEs}*AND YOU NE
    EDED "VAL(MID$(T$,1,2))"HOUR,";
98Ø PRINT VAL(MID$(T$,3,2))"MINUTES"
99Ø PRINT"{CRSR DN}{3 SPACEs}AND"VAL(MID$(T
    $,5,2))"SECONDS."
1ØØØ PRINT"{2 CRSR DNs}{2 SPACEs}**PRESS 'Y
     ' TO PLAY AGAIN OR{14 SPACEs}{CRSR DN}
     ANY OTHER KEY TO END.
1Ø1Ø GETA$:IFA$=""THEN1Ø1Ø
1Ø2Ø IFA$="Y"THENCLR:GOTO1ØØ
1Ø3Ø END
11ØØ REM ***SOUND SUBROUTINES************
    *******
111Ø FORL=STOS+24:POKEL,Ø:NEXT:POKES+24,15
112Ø POKES+5,Ø:POKES+12,Ø:POKES+19,Ø:POKES+
    6,24Ø:POKES+13,24Ø:POKES+2Ø,24Ø
113Ø RESTORE
114Ø FORI=1TO8:READZ:NEXT
115Ø READH1,H2,H3:IFH1=-1THENFORL=STOS+24:P
    OKEL,Ø:NEXT:RETURN
116Ø READL1,L2,L3,D:POKES+1,H1:POKES+8,H2:P
    OKES+15,H3
117Ø POKES,L1:POKES+7,L2:POKES+14,L3:POKES+
    4,17:POKES+11,17:POKES+18,17
118Ø FORT=1TOD:NEXT:POKES+4,16:POKES+11,16:
    POKES+18,16:FORT=1TO5Ø:NEXT:GOTO115Ø
119Ø DATA25,12,6,3Ø,143,71,1ØØ
12ØØ DATA25,12,6,3Ø,143,71,1ØØ
121Ø DATA25,12,6,3Ø,143,71,1ØØ
122Ø DATA19,9,4,239,247,251,4ØØ,Ø,Ø,Ø,Ø,Ø,Ø,Ø
    ,1ØØ
123Ø DATA22,11,5,96,48,152,1ØØ
124Ø DATA22,11,5,96,48,152,1ØØ
125Ø DATA22,11,5,96,48,152,1ØØ
126Ø DATA18,9,4,2Ø9,1Ø4,18Ø,8ØØ,-1,1,1
13ØØ REM ***INSTRUCTIONS*****************
    *******
131Ø PRINT"{SHFT CLR}{CRSR DN}{5 SPACEs}FIF
    TEEN PUZZLE"
132Ø PRINT"{5 SPACEs}{14 COMD Ys}"
133Ø PRINT" *THE OBJECT OF THE FIFTEEN PUZZ
    LE IS"
134Ø PRINT" TO MOVE THE NUMBERS AROUND, SO
    THAT"
135Ø PRINT" THEY ARE IN ORDER FROM 1 TO 15.
    "
136Ø PRINT" A MOVE IS MADE BY TYPING IN THE
     NUMBER"
137Ø PRINT" YOU WISH TO MOVE. HOWEVER, IF Y
    OU"
138Ø PRINT" WANT TO MOVE THE NUMBER '1', PR
    ESS"
139Ø PRINT" INSTEAD THE LEFT ARROW ('{LEFT
    ARROW}')."
14ØØ PRINT" *THE NUMBER TO BE MOVED MUST BE
    "
141Ø PRINT" ADJACENT TO THE EMPTY SQUARE."
142Ø PRINT" THE TYPED NUMBER THEN MOVES INT
    O THE"
143Ø PRINT" EMPTY SQUARE."
144Ø PRINT"{CRSR DN} *DO NOT PRESS RETURN A
    FTER TYPING THE"
145Ø PRINT" NUMBER."
146Ø PRINT"{CRSR DN} *YOU WIN, WHEN THE BOA
    RD LOOKS LIKE THE"
147Ø PRINT"{CRSR UP}{2 SPACEs}FIGURE WHICH
    FOLLOWS:"
148Ø PRINT"{CRSR DN} **PRESS ANY KEY TO CON
    TINUE"
149Ø GETA$:IFA$=""THEN149Ø
15ØØ Q=1:GOSUB1ØØ
151Ø FORI=1TO16:A(I)=I:NEXTI
152Ø GOSUB61Ø
153Ø PRINT"{CRSR DN} **PRESS ANY KEY TO STA
    RT"
154Ø GETA$:IFA$=""THEN154Ø
155Ø Q=Ø:CLR:GOTO1ØØ
156Ø PRINT"{CRSR DN} **PRESS ANZ KEY TO CON
    TINUE"
157Ø GETA$:IFA$=""THEN157Ø
158Ø PRINT"{SHFT CLR}":RETURN
```


Circle 192 on Reader Service card.

May

COMING ATTRACTIONS

- **Home Applications**—There's no place like home for the C-64, and this is nowhere more evident than in the upcoming May issue, which features articles that will help you integrate your computer into the home with time-saving, useful applications. For example:
  Home Inventory—Keep an up-to-date list of all your valuables and home furnishings. Hopefully, you'll never need to use this program, but, for your own protection, you'll have a detailed inventory of your belongings.
  Shopper's Companion—Good news for the harried shopper! Now you can become more efficient and organized. Simply use this program to generate a printed shopping list at home. No more return trips to the supermarket to pick up items you may have forgotten.
  Energy Watchdog—This "Kilowatt Kontroller" program stores readings from your electric meter, calculates usage and computes your daily electricity cost.
- **On-Line with Telecommunications**—Home telecommunications promises to be a major application for computerists in 1985. Next month, *RUN* begins a series on telecommunications that will focus on the services available for on-line users. First to take the spotlight will be the popular CompuServe.
- **In Therapy**—Now there's C-64 software that claims to help you lose weight, quit drinking or smoking and even improve your sex life! *RUN*'s resident psychiatrist takes an analytical look at these commercially available self-help programs. Do they really work?
- **Guide to Troubleshooting**—Have you ever decided against typing in a program listing for fear of making errors? Well, fear no more. This article provides you with hints on how to prevent errors and helps you understand and deal with those errors that do occur.
- **Plus/4's High-Resolution Graphics**—With the Plus/4 you needn't fuss with Peek and Poke commands to achieve those high-resolution graphics displays. Instead, you can use simple one-word commands such as DRAW, CIRCLE and BOX.
- **VIC Patrol**—Don't think that the VIC-20 has outlived its usefulness. There are plenty of applications for the VIC-20 that will save you money and make your life easier and safer. For example, you can control lights, alarms, robots, sprinkler systems, thermostats, appliances—anything that can be turned on and off with a switch—with your VIC-20.
- **Snakes**—In this strategic game for the C-64, you must maneuver your snake to gain the territorial advantage on the screen and thus defeat your opponents.

A First Lesson in Programming for Kids

By AMY and JAMES BLODGETT

The Basic Print and Goto statements can make a child's introduction to programming both easy and enjoyable.

Kids like to program. They like to be able to make the computer do things, and a few simple Basic language statements will help them get started.

The most useful is the Print statement, which is both easy and interesting. It lets kids make the computer draw pictures. For example:

```
100 PRINT "  XXX  "
110 PRINT "XO  OX"
120 PRINT "X  L  X"
130 PRINT "X  -  X"
140 PRINT "  XXX  "
150 PRINT "  !    !  "
160 PRINT "/        \"
```

Another Basic command kids sometimes enjoy is the GOTO statement. They find they can use it to make their pictures print repeatedly:

```
100 PRINT "  XXX  "
110 PRINT "XO  OX"
120 PRINT "X  L  X"
130 PRINT "X  -  X"
140 PRINT "  XXX  "
150 PRINT "  !    !  "
160 PRINT "/        \"
170 GOTO 100
```

By learning these two statements, kids can write their own programs and take the first steps toward learning programming. R

Address all author correspondence to Amy and James Blodgett, 11 Fullerton St., Albany, NY 12209.

A Review of

Simons' Basic

By ROBERT W. BAKER

Noted Commodore author Bob Baker takes a hard look at Simons' Basic, which adds over 100 commands to your C-64 system.

Simons' Basic for the Commodore 64 originated in England over a year ago. It was written by a sixteen-year-old student named David Simons.

The cartridge adds 114 commands to the normal Basic that's built into the C-64. Available memory is reduced to only 30K, and the standard screen colors are changed to black characters on a gray screen with a dark-blue border.

The Basic extensions provide many powerful and useful commands, which were, unfortunately, implemented very poorly for a commercial package. There is very little command parameter checking, and many things have been overlooked or ignored.

Reviews appearing in England back in 1983 pointed out some of the deficiencies, but nothing was done to correct these items prior to bringing the package into the United States.

One review of Simons' Basic commented that the package presents "plenty of quantity but little quality," and I couldn't agree more.

The commands are generally easy to use. On the other hand, be careful in using Simons' Basic during initial program development—small, hard-to-find mistakes can cause unpredictable results. Also, keep in mind that any program written using these commands will not run without the Simons' Basic cartridge installed.

Criticisms

Simons' Basic is very sloppy in changing Basic program text into tokens. Its keywords in Data statements are changed into tokens and will normally read as garbage.

Any keywords that appear in hex numbers are also tokenized. For example, attempting to enter PRINT $CDEF will result in an error message, since DEF is tokenized and hence is no longer a valid hex character.

When entering program lines, you cannot abbreviate Simons' keywords. Since some commands are quite long, the process of entering lines can become a little tedious.

Another drawback of Simons' Basic is its spacing—spaces between keywords and their parameters are sometimes required and sometimes not allowed. The manual further confuses the issue by insisting that all commands (except Find) must be separated by a space.

Many command parameters are not checked to see if they are within range, and many strange effects can thus occur. Some commands allow values up to 255, while others allow up to 65535 before displaying an Illegal Quantity error. Plotting commands are the biggest offenders and can cause bizarre results when parameters exceed the normal screen boundaries.

You are also unable to flip back and forth from text to graphics character sets using the CBM and shift keys or the CHR$(8) and CHR$(9) commands, because that function of those keys and commands is disabled by Simons' Basic.

Further, the restore key usually sets everything back to normal, but, in Simons' Basic, flashing borders and characters remain. Some options in Simons' Basic are selected by numeric values instead of words, like ON or OFF. The Trace option, for example, is enabled by TRACE 10 and disabled by TRACE 0.

The accompanying manual is approximately 150 pages long and is broken into 13 sections. It provides a brief introduction, plus detailed information on the various commands and features. The material is generally well presented with helpful examples. However, several errors are scattered throughout the book. At least one of the examples will not work as presented.

By the way, I found two reserved variables, defined by Simons' Basic, that are not mentioned in the manual. The word GRAPHICS is defined as the base address of the VIC video chip, 53248, and can be referenced just like any other variable within your program. Likewise, the word SOUND is defined as the base address of the SID sound chip, 54272.

Simons' Basic Commands

Note: Some of the commands and their definitions are followed by qualifying explanations, denoted by bullets (●).

AUTO Provides automatic line numbering and allows an increment of up to 255.

BCKGNDS Allows displaying messages with three different character background colors.

● With the BCKGNDS command, only the characters shown on the top of each key can be used (graphics characters cannot be used). You'll have to actually issue a BCKGNDS command in order to see the correct text within the program listing. Otherwise, graphics characters will appear instead. Printed listings present a problem, since they'll no longer match displayed listings.

BLOCK Allows you to plot a rectangle and fill it with a specified color.

CGOTO Allows an expression in place of the normal GOTO target line number.

CHAR/TEXT Allow individual characters or entire lines of text to be superimposed on a graphics screen.

● The CTRL-A and CTRL-B characters used to select upper- or lowercase letters in the TEXT command are not really needed (the default is uppercase). Cursor controls and other special control codes (like colors) cannot be used within the character string for the TEXT command. The reverse on and off can be used, but only the text will be reversed on the screen (spaces are not reversed).

All high-resolution plotting uses X,Y coordinates, starting at 0,0 in the top left corner of the screen and ending at 319,199 in the bottom right. In Multicolor mode, the bottom right corner becomes 159,199, due to the double-width plotting of each point. There is very little checking for valid coordinates by each plotting command; only values greater than 65535 or 255 cause errors. There are no error messages if you're only slightly out of bounds, and results are unpredictable.

CMOB Used to set up colors for a multicolor MOB.
MOB SET Used to initialize a MOB.
MMOB Used to display MOBs.
MOB OFF Used to clear MOBs.
RLOCMOB Moves a specific MOB across the screen at a specified rate, but only one MOB can be moved at a time.

● A speed of 0 is valid for both the MMOB and RLOCMOB commands and produces the fastest motion.

COLD Resets the C-64 under software control, but will not reset attached peripherals.

COLOUR/HIRES/MULTI Allow selecting colors, plotting types and initializing the high resolution or multicolor graphics modes.

LOW COL/HI COL Allow you to change plotting colors.

NRM Allows you to return to a low-resolution screen from a graphics screen.

● The difference in coordinates between normal High-resolution and Multicolor Graphics modes makes it difficult to set up a screen in High-resolution and then see what it would look like in Multicolor mode. The difference in plot type codes for both graphics modes makes switching from one mode to the other even more complex. Incidentally, none of the graphics commands are compatible with the VIC's Super Expander, making the transfer of programs difficult.

COPY/HRDCPY Allow you to print a copy of a graphics or low-resolution screen on a serial printer.

SCRSV Saves low-resolution screen data in a datafile on cassette or disk.

SCRLD This same low-resolution screen data can be restored to the screen using this command.

● Be careful when loading a screen from disk—strange things happen if the file is not found. Also, don't try to load a screen from tape on an Executive-64, since Simons' Basic uses tape routines in ROM that do not exist in the SX-64.

CSET Allows selecting either of the C-64 character sets or recalling and displaying the last graphics screen.

DEFINE/@ Used to define specific characters in the same manner as defining MOBs.

DELAY Controls the scrolling rate.

DESIGN Used to specify the location in memory where the data for each movable object block (sprite, or MOB) is to be stored.

● The sample sprite program on page 8-4 of the manual will not work properly as written. When the program runs, the sprite data will overwrite and destroy the Basic program so it cannot be run again. If you change the following lines in the example, the sprite data will be stored in an unused area of high RAM without harming the program:

```
85 MEM
90 DESIGN 0,$F000
320 DESIGN 1,$F000+64
700 MOB SET 0,192,0,1,0
710 MOB SET 1,193,2,0,1
```

To use the DESIGN command and sprites as designed, you'll have to move the start of Basic program space higher in memory. Otherwise, you'll have to use the MEM command and then put sprite data in the high area of RAM, starting at location 61440 ($F000), as hinted in the manual.

A BAD CHAR FOR A MOB error will occur if the DESIGN command is not immediately followed by exactly 21 @... format lines, each with exactly 12 or 24 valid color codes. If more than 21 format lines exist, a Syntax error will occur. If there are too many color codes in a format line, no error will be reported.

DETECT/CHECK Used to initialize and control MOB-collision detection.

● The CHECK command must have two parameters or you'll get a

Just don't try to redefine these variables within your program.

Besides the mistakes in the documentation and the operation of the program, there are basic flaws in the overall design of the package.

The inconsistencies, plus poor attention to detail and lack of error checking, seem to indicate the package was written in a piecemeal fashion without any clear concept of the end result. In preparing such a utility package, it is vital to spend a great deal of time planning the final product.

Simons' Basic, however, does have many useful features. Its graphics and sound commands will save a lot of Peeking and Poking, while the structured programming commands may help newcomers getting started with programming. R

Address all author correspondence to Robert W. Baker, 15 Windsor Drive, Atco, NJ 08004.

Syntax error. The single zero parameter for CHECK, shown in the manual, is not allowed.

DIR Allows displaying the disk directory with selectable character matching and without loading into memory.

DISK Allows you to send command strings over the disk-command channel.

- There is no provision for reading the error status returned by the disk following any disk command.

DISABLE/RESUME Allow disabling and reinstating the previous ON KEY command, which, once initiated, stays in effect throughout the program.

DISAPA/SECURE Program security aids that can be used to hide portions of a program when it's being listed.

- Despite the manual's claims, the DISAPA command works anywhere in a Basic program line. When secured, the remainder of the line disappears, leaving the colon prior to DISAPA.

Make sure DISAPA always appears within quotes in Data statements. It will still function by adding colons and securing the remainder of the line even if no colon is entered. The DISAPA command actually places five colons, not three, as the manual claims, before following code. If you look at the examples, they do show five colons being added.

DRAW Allows you to draw an arbitrary shape that you define as a string of command letters, much like turtle graphics.

- There is no check for valid command letters in the string used by the DRAW command. The first invalid character encountered terminates the command at that point.

DUMP Displays the current values of all non-array variables, but has a problem handling string variables.

- If you use a string variable in a Get command to read the keyboard or a disk file, you may get garbage listed for that variable in the dump.

FCHR/FILL Allow filling an area of the screen with a specified character.

FCOL Allows changing a character color in a specified screen area.

INV Used to invert a specified screen area.

- For the FCHR, FILL, FCOL and INV commands, be careful that the row plus depth does not exceed 25 and that the column plus width does not exceed 40. If the screen limits are exceeded, you'll get a BAD MODE error. You'll get the same error if either the width or depth, the third or fourth parameter, is 0.

FETCH Allows you to limit the number and type of characters that will be accepted as user input.

- When using FETCH, watch your screen handling, as this command does not position the cursor past the input line, like the INPUT command. Any following PRINT will overwrite the inputted data. Also, you cannot enter a null string when a FETCH has been executed; you must enter valid data.

When looking for numeric data, FETCH also allows the entry of characters such as commas, colons, semicolons, equals signs, plus signs, minus signs, greater-than and less-than signs, asterisks and at (@) signs. The cursor-right control is listed as accepting alphanumeric and shifted characters, but it only accepts normal and shifted letters A–Z.

FLASH/BFLASH/OFF Control flashing the entire screen or just the border.

- When flashing the border at fast speeds (under 7 or 8), you'll actually see a mixing of the colors, which can be used to create interesting effects. Since BFLASH and FLASH both affect the internal interrupt routines, the TI variable is slowed down significantly, and input and output characters may be lost by the system.

IF...THEN...ELSE/REPEAT...UNTIL/LOOP...EXIT IF...END LOOP Allow you to write structured code.

- The manual is a little fuzzy on these commands, but the IF...THEN...ELSE command can have null, true and/or false arguments.


CBUS™
For The Commodore 64*
CARTRIDGE BACKUP SYSTEM
CARTRIDGE BACK UP SYSTEM
CBUS I — $34.95
Lets you copy any cartridge to disk. Many cartridge images can be run from disk (software listings provided) with no changes. Some cartridge images may require modifications.
CBUS I DELUXE
Above with necessary programs on diskette
$49.95
CBUS II — $84.95
Will run ANY cartridge image without modification. CBUS II is a true cartridge emulator and will run cartridges with even the heaviest of copy-protection.
CBUS II DELUXE
Above with necessary programs on diskette $99.95
CBUS COMBO
CBUS I & II
With programs on diskette $119.95
ORDERS ONLY
1-800-CBUSC64
TECH INFO.
(215) 622-5495
PLEASE ADD $3.00 FOR SHIPPING
PA. RESIDENTS ADD 6% SALES TAX
VISA, MC, P.O., CHECKS OR CASH
Circle 219 on Reader Service card.
R. J. BRACHMAN ASSOCIATES, INC.
P. O. BOX 1077 • HAVERTOWN, PA. 19083

The REPEAT...UNTIL command must have colons after the repeat and before the UNTIL, but can contain multiple conditions separated by colons. The correct format for a LOOP statement includes colons after LOOP, before and after EXIT IF and before the END LOOP.

Note, there must be a space in the EXIT IF and END LOOP keywords, and loops may span over multiple program lines. The RCOMP statement will always take the true (IF) path if a prior IF...THEN was not executed.

INKEY Provides a quick and easy test for a function-key input.

- When using the INKEY, the value returned may not always be between 1 and 8. Much higher numbers will be returned when you hold the control key (166–173), shift-control (205–212) or the Commodore key, shifted or unshifted (9–16), while pressing a function key.

INSERT Allows one character string to be inserted within another at a specific point.

INST Does the same thing as INSERT, except the substring will overwrite the original string contents.

DUP Allows creating a repetitive string.

PLACE Provides an easy way to find a given substring within a string and to return its position.

- INSERT does not work in Direct mode with immediate values for both strings. INST does not work in Direct mode when the substring equals the string. PLACE doesn't work in Direct mode if the substring is an immediate string.

Also, despite what the manual claims, PLACE cannot be used to compare numeric variables, but only strings. The DUP command accepts a rep count value up to 65535, but produces incorrect results if the created string exceeds 255 characters in length. For instance, DUP("A",259) creates a string of three A's; DUP("ABC",100) produces a string of 44 Cs.

KEY Assigns a character string to a function key, allowing one-keystroke access to often-used commands.

DISPLAY Lets you review the current assignments for each function key.

- Clearing a key definition by assigning a null string doesn't work; it assigns to the key a garbage string with unpredictable contents. To clear a key definition, use a space.

LIN Returns the current line number of the cursor. The manual does not describe this command.

LINE/REC/CIRCLE/ARC/ANGL Draw full two-dimensional figures of the corresponding shape.

- The CIRCLE command actually draws an ellipse with selectable X and Y radii. Equal values for the X and Y radii do not yield a perfect circle, due to the rectangular shape of the screen and the differences in the X and Y sizes of each dot. You'll have to adjust the values yourself to compensate for the screen.

LOCAL Defines variables to operate locally.

GLOBAL Restores a variable's global values.

- Variable arrays are not handled correctly. If any array element is listed in a LOCAL command, the entire array is cleared and set as local. When the corresponding GLOBAL command is executed, it doesn't restore the original values to the array. Also, the DUMP command may display multiple values for variables after using a LOCAL command. In this case, the first value listed should be the current value.

MEM Before you create user-defined characters, use this command to copy the standard character set from ROM to RAM.

- Once the MEM command is issued, sprite data can only be stored starting at location 61440 ($F000). The only problem with the MEM command is that screen memory moves to location 52224 ($CC00), and some commands that write directly into screen RAM (like TRACE) continue to write into the original screen area. By the way, the last line in the example on page 8-13 should be line 100, not 30 as shown.

MERGE Appends a program on disk to the end of any program currently in memory.

Circle 144 on Reader Service card.

UNIPRINT
UNIVERSAL PRINTER INTERFACE

THE QUALITY INTERFACE FOR THE QUALITY PRINTER

• **NO DIP SWITCHES** OR CHIP CHANGES NECESSARY. THE NEW COMMODORE PRINTER INTERFACE THAT YOU JUST PLUG IN AND IT'S READY TO USE.
• INTERFACES THE COMMODORE 64 AND VIC 20* WITH A PARALLEL PRINTER—**EPSON AND COMPATIBLES**, CANON, STAR GEMINI, BMC, PANASONIC, SMITH CORONA, RITEMAN, ETC. **OKIDATA—DAISY WHEELS** JUKI, STAR MICRONICS (POWERTYPE), QUME, DIABLO, BROTHER, SILVEREED, ETC.
• ACCESSES YOUR PRINTER'S SPECIAL FEATURES • SUPPORTS DOT-ADDRESSABLE GRAPHICS
• COMPATIBLE WITH YOUR FAVORITE SOFTWARE PROGRAMS—PAPERCLIP, EASY SCRIPT, BANK STREET, DOODLE, CHARTPAK 64, MUSICALC, MIRAGE DATA-BASE, PRACTICALC, VIP TERMINAL, ZORK 1,2,3, AND MANY MORE
• CONVERTS COMMODORE ASCII TO STANDARD ASCII CODE • EMULATES THE VIC-1525 PRINTER
• TRANSPARENT MODE • COMPLETE LANGUAGE TRANSLATION

SEND COUPON OR CALL
(201) 941-1800

MANUFACTURED IN THE U.S.A. BY
GIGA INTERNATIONAL CORPORATION
605 BROAD AVENUE
RIDGEFIELD, NEW JERSEY 07657

*COMMODORE 64 & VIC 20 ARE REGISTERED TRADEMARKS OF COMMODORE BUSINESS MACHINES, INC

LIST PRICE $69.95

YES! PLEASE SEND MORE INFORMATION ON YOUR EXCITING NEW INTERFACE
NAME
ADDRESS
CITY STATE ZIP

• Note that the MERGE command *appends* a program; it is not a true merge, since line numbers are ignored. The program from disk immediately follows the program in memory (lines are not interspersed as expected).

MOD Returns the remainder when one integer is divided by another.
DIV Returns the integer portion of the same operation.
EXOR Performs a logical exclusive OR between two numbers.
FRAC Extracts the fractional part of a floating-point number.

• The numeric functions (MOD, DIV and EXOR) only work with values in the range of 0 to 65535, where normal Basic integers range from −32768 to 32767 (negative numbers are invalid).

Non-decimal numbers can be used in all expressions by preceding binary numbers with a percent sign and hexadecimal numbers with a dollar sign. There's a slight problem with hex numbers, though, since certain combinations of hex digits can include Basic keywords that are still tokenized by Basic. Also, there is no provision of converting numbers to binary or hexadecimal.

All binary numbers must be eight digits long, and all hex numbers must be four digits, but the manual fails to tell you this. If a number contains an incorrect number of digits, you'll get an Invalid Character error, even though the number contains valid binary or hex digits. If the number of digits is a multiple of 8 (binary) or 4 (hex), only the first set is used, and the extras are ignored without an error message.

MOVE Used to duplicate a section of the screen in a new location.

OLD Allows reversing the effects of a NEW command and regaining access to the program still in memory.

ON ERROR With reserved variables ERRN and ERRLN, provides a mechanism to trap selected errors and pass control to a specified line in the program. The value of ERRN indicates the type of error that occurred, while ERRLN indicates what line in the program caused the problem.

OUT/NO ERROR Used to disable the last error condition or restore normal error processing.

• If you have trouble listing a program and keep getting repeated error messages, use the NO ERROR command and try listing the program again. Remember that ON ERROR and NO ERROR both must have the separating space.

ON KEY Provides a filter that only accepts specified input characters and ignores all others. On receipt of a valid character, program control is passed to a specified line in the program.

• Character codes must be used with caution in ON KEY commands, since numbers above 127 are treated as negative in ST. A comparison like A = ST will not give expected results for shifted keys.

OPTION Highlights any Simons' Basic commands within a listing, making them easier for you to find.

FIND Helps you search for other character strings or codes in a program.

• The FIND command only lists the line numbers of where a particular item is found. Also, when you're searching for specific character strings within quotes, the entire string must be an exact match. FIND will not find sections of strings within quotes, like "CD" within "ABCDEFG."

PAGE Divides a listing into screen pages of a specified length.

• The paging function displays one more line than requested and does not always work as described.

PAINT Lets you fill in any enclosed area with color.

• The PAINT command can be very slow when filling large areas. Also, when painting an area with a different color than that used to draw the object, some sides will be replaced with the new color while others will stay unchanged. If the X and Y coordinates used in the PAINT command fall directly on the border of an object, the object will not be filled in. Invalid plot types in a PAINT command are not detected and can cause rather strange results.

PAUSE Provides timed delays in program execution that can be aborted by pressing the return key.

PENX/PENY Used to determine the location of a light pen on the screen.

PLOT Handles individual point plotting.

POS Returns the horizontal cursor position.

POT/JOY Used for interfacing paddles and joysticks.

• In the POT command, the parameter that indicates which paddle to read can be a variable. Unfortunately, the JOY command only supports joystick #2, so you'll still have to resort to PEEKs to read the other joystick.

PRINT AT Allows printing strings at specific positions on the screen.
CENTRE Centers a character string on a screen line.

• Using row or column numbers that exceed screen limits in a PRINT AT command will produce unpredictable results. Placing embedded cursor controls in a character string to be centered on the screen will defeat the function of the CENTRE command.

PROC/END PROC Used to create named procedures. Once defined, you can call them as subroutines with the EXEC command or branch to them by using the CALL command.

• The only thing missing in the commands used to create named procedures is the ability to pass parameters to the procedure. As implemented, procedures are nothing more than labeled line numbers, and EXEC acts like GOSUB, CALL like GOTO and END PROC like RETURN.

RCOMP...ELSE Repeats the last IF...THEN condition test without having to repeat the same code again.

• The RCOMP...ELSE command simply uses the result of the previous condition test, so, if conditions are changed, they must be retested.

RENUMBER Renumbers all program lines and allows an increment of up to 65535.

• RENUMBER does not change the line numbers following GOTOs, GOSUBs and so on, so its usefulness is questionable. (Also, both AUTO and RENUMBER can generate illegal line numbers above 63999, causing all kinds of problems.)

RESET Allows moving the data pointers so that subsequent READ commands start reading data at a specified line number.

ROT Allows you to display the selected shape scaled up and/or rotated through multiples of 45 degrees.

SCROLLING Allows easy control of scrolling within a given area of the screen.

• When using the SCROLLING command, you can scroll the data in one of four directions and control whether or not the data continues when it reaches the end of the screen. The maximum height and width of the scroll area is incorrect in the manual; it's really the entire screen of 25 lines down by 40 characters across. It appears the manual was never updated from the original VIC-20 version.

TEST Allows a check to see if something has been drawn at a specific location.

TRACE/RETRACE For tracing program execution as an aid to debugging.

• As program lines are executed, the line numbers are displayed in a window in the upper right corner of the screen. TRACE uses white characters on a gray background and can be very difficult to read. Also, it doesn't show the line currently being executed, but, rather, displays it only *after* the next line is started.

USE Formats the screen.

• A "print using" function combines the USE command and the normal PRINT statement to format numbers stored as strings. It will only accept one field or variable per command, but multiple commands can be used to format an entire line. The usual zero-filling, left and right justification and other features normally found in a print-using function, do not exist.

The USE command does not work in Direct mode and cannot be used to format printed output. It only works for the screen.

VOL/WAVE/ENVELOPE/MUSIC/PLAY These commands make sound effects extremely easy to program without the usual barrage of Pokes.

• Be careful of the binary number in the WAVE command. Bits that must be 0 and invalid combinations of bits are not flagged as errors.

Circle 62 on Reader Service card.

Commodore Accessories Super Sale

by CPX

BEST SERVICE • HIGHEST QUALITY • LOWEST PRICES

COLOR MONITOR

- 14" screen
- Resolution meets or exceeds Commodore 1701/1702
- 15% larger screen than the Commodore or CA monitors.
- Complete with Cable and instructions

Our best buy. This is the monitor that Commodore should have made. We bought the same design that is used in monitors costing hundreds more. Meets or exceeds Commodore specifications. Great for use with your VCR too.

Catalog #1210 **$189.95**

AMBER MONITOR

- Highest performance available
- 12" screen
- Up to 132 columns x 25 lines
- Front panel controls
- Amber screen
- Rugged metal case
- Complete with cable and instructions

This is the monitor for professional work. If you plan to use an 80 column board (see below) or if you use your 64 a lot **save your eyes** and use the best. We bought the same design used by Sanyo that sells for up to $199.95.

Catalog #1220 **$99.95**



DATA 20 XL 80 (80 column board)

- 80 column x 25 line display
- Clear, sharp display
- Includes:
  Wordmanager Wordprocessor
  Planmanager Spreadsheet
  Com-manager Communications
  Disk copy utility
- Auto boot and auto start
- Speeds up the system up to 15% **including the disk drive**
- 1 year manufacturer's warranty

Every Apple or IBM has an 80 column screen, so can your 64. This amazing cartridge is the best new product we've seen in years. Simply plug it in, and watch the XL 80 load and run its easy to use programs **automatically**. The included programs are fast, powerful, and very easy thanks to the 80 column screen. A **must for wordprocessing**. Use with any monochrome monitor (see above).

Catalog #1230 **$99.95**

DATA 20 PARALLEL INTERFACE

- 100% compatable with all Commodore Computers Plus 4, 16, 64, VIC 20, SX 100 (portable), and 128
- No power taps to tape, user, joystick ports, or **any** outside source
- No setup required
- No software drivers required
- Great graphics with Printshop, Flexidraw, etc...
- As easy to use as a cable.
- 1 year manufacturers warranty

You wanted graphics, no hassle, and low price. DATA 20 gave it to you. This new interface (never sold before) uses a custom chip that is so low power, it gets all the power it needs from the signals going to the Printer! Works with **any printer or software** or your money back.

Catalog #1240 **$49.95**

DISKETTES

- High Quality
- Single sided, double density
- 10 per box
- Includes rugged plastic disk filer, a $12.95 value-**FREE**
- Includes labels, sleeves, and write protect tabs

No one sells diskettes like we do. A super value with our exclusive **free** disk filer. No more scrounging through stacks of loose disks. Our filer also doubles as a easel-type stand for easy reference. Protect your valuable data but **at the best price! No limit.**

Catalog #1250 **$14.99**

Need more than 10? Buy in quantity and save. Box of 100 includes labels, sleeves, and write protect tabs. Filer not included.

Catalog #1260 **$129.95**

CALL CPX TO ORDER **(714) 581-4570** **24 HOUR ORDER LINE**

VISA MasterCard AMERICAN EXPRESS COD

90 DAY WARRANTY

15 DAY FREE TRIAL • SATISFACTION OR YOUR MONEY BACK!
NO CHARGE UNTIL WE SHIP YOUR ORDER

Prices do not include shipping or applicable taxes or duties.
Sorry no personal checks accepted.

computer peripheral exchange

P.O. Box 2576, Laguna Hills, California 92654

Add a little punch to your programs with this short subroutine that lets you box in your screen messages and menus with ease.

Making Boxes

By RICHARD LOVETT

Some of the more attractive computer programs dress up their screen menus or other important text by printing boxes around them. However, determining which graphics characters to use, how to space and print them and how to put a box where you want it can take lots of trial and error. And with each new box, much of the guessing starts all over again.

Here's a little subroutine to help



PHIL GERACI

RUN It Right

VIC-20 or C-64

you get boxed in quickly. Simply include it in your programs, define a few variables and then enter GOSUB 10000. With one or more passes of this subroutine, you can easily make as many boxes as you want, of any shape and size. The same subroutine works on both the VIC and the 64.

The variables that need to be defined before each call of the subroutine are: WID, the width of the box in spaces; DEP, the depth of the box in lines; DOWN, the number of lines from the top of the screen for the box to begin; and LEF, the number of spaces from the left screen margin for the side of the box to begin.

Here's the subroutine:

```
10000 REM ** BOX MAKER SUBROUTINE
10010 POKE211,LEF:POKE214,DOWN:
  PRINT"{CRSR UP}"
10020 FOR I=1 TO WID:PRINT
  "{COMD P}";:NEXT:PRINT
10030 FORI=1 TO DEP:PRINTTAB(LEF);
  "{COMD H}";TAB(LEF+WID-1)
  "{COMD N}":PRINT"{CRSR UP}":NEXT
10040 POKE211,LEF:POKE214,
  DOWN+DEP+1:PRINT"{CRSR UP}";
10050 FORI=1TOWID:PRINT"{COMD Y}";:
  NEXT:RETURN
```

Of course, there are limits to the parameters you can set. WID must be at least 2, and it can't exceed 21 on the VIC-20 or 39 on the Commodore 64 without producing a jumble. DEP can't exceed 21 on the VIC or 23 on the Commodore 64 without the same result. DOWN must be at least 1, and both DOWN and LEF must stay within reasonable bounds or you will push the box off the screen.

To see how the subroutine works, type it in and run it along with the demonstration program (see Listing 1 for the VIC-20 version, Listing 2 for the C-64 version).

When you use the subroutine in your own programs, you should first print the text or graphics to be boxed, then create the box. If you draw the box first, the cursor is likely to erase part of it when putting the text or graphics inside.

The subroutine has lots of possibilities. By changing the variables each time you use GOSUB 10000, you can print boxes within boxes, or put boxes at several points on the screen simultaneously. If you'd like, each box can be a different color.

With a little experimenting, you will soon be a professional boxer, and your screen messages and menus will take on an added authenticity. R

Address all author correspondence to Richard Lovett, 6649 Oak St., Kansas City, MO 64113.

Listing 1. *VIC-20 demonstration program. Run with subroutine.*

```
5 REM VIC VERSION
1Ø PRINT"{SHFT CLR}{8 CRSR DNs}"
2Ø PRINTTAB(3)"TA-DAH!{2 SPACEs}HERE'S
3Ø PRINTTAB(4)"OUR TEXT WITH
4Ø PRINTTAB(3)"A BOX AROUND IT.
5Ø WID=18:DEP=7:DOWN=7:LEF=INT((22-WID)/2)
7Ø GOSUB1ØØØØ:PRINT:PRINT:PRINTTAB(4)"PRESS
   ANY KEY"
8Ø GETJ$:IFJ$=""THEN8Ø
9Ø PRINT"{SHFT CLR}{CRSR DN}DRAW A BOX TO Y
  OUR OWN SPECIFICATIONS
1ØØ INPUT"BOX WIDTH (2-21)";WID
11Ø INPUT"BOX DEPTH (1-21)";DEP
12Ø PRINT"DISTANCE DOWN":PRINT"FROM TOP";:I
   NPUT DOWN
13Ø IFDEP+DOWN>22THENPRINT"YOU CAN'T DO THA
   T":GOTO11Ø
14Ø PRINT"CENTER THE BOX":PRINT"LEFT/RIGHT"
   ;:INPUTAN$
15Ø IFLEFT$(AN$,1)="Y"THENLEF=INT((22-WID)/
   2):GOTO18Ø
16Ø INPUT"DISTANCE FROM LEFT";LEF
17Ø IFLEF+WID>21THENPRINT"YOU CAN'T DO THAT
   ":GOTO16Ø
18Ø PRINT"{SHFT CLR}":GOSUB1ØØØØ:FORI=1TO5Ø
   ØØ:NEXT:INPUT"{SHFT CLR}{CRSR DN}ANOTHE
   R BOX (Y/N)";AN$
19Ø IFAN$="Y"THEN1ØØ
2ØØ END
1ØØØØ REM *** BOX MAKER SUBROUTINE ***
1ØØ1Ø POKE211,LEF:POKE214,DOWN:PRINT"{CRSR
     UP}";
1ØØ2Ø FORI=1TOWID:PRINT"{COMD P}";:NEXT:PRI
     NT
1ØØ3Ø FORI=1TODEP:PRINTTAB(LEF);"{COMD H}";
     TAB(LEF+WID-1)"{COMD N}":PRINT"{CRSR
     UP}":NEXT
1ØØ4Ø POKE211,LEF:POKE214,DOWN+DEP+1:PRINT"
     {CRSR UP}";
1ØØ5Ø FORI=1TOWID:PRINT"{COMD Y}";:NEXT:RET
     URN
```

Listing 2. *C-64 demonstration program. Run with subroutine.*

```
5 REM C-64 VERSION
1Ø PRINT"{SHFT CLR}{8 CRSR DNs}"
2Ø PRINTTAB(12)"TA-DAH!{2 SPACEs}HERE'S
3Ø PRINTTAB(13)"OUR TEXT WITH
4Ø PRINTTAB(12)"A BOX AROUND IT.
5Ø WID=21:DEP=7:DOWN=7:LEF=INT((4Ø-WID)/2)
7Ø GOSUB1ØØØØ:PRINT:PRINT:PRINTTAB(8)"PRESS
   ANY KEY TO GO ON
8Ø GETJ$:IFJ$=""THEN8Ø
9Ø PRINT"{SHFT CLR}{CRSR DN}DRAW A BOX TO Y
  OUR OWN SPECIFICATIONS
1ØØ INPUT"WIDTH OF BOX (2-39)";WID
11Ø INPUT"DEPTH OF BOX (1-23)";DEP
12Ø INPUT"DISTANCE DOWN FROM TOP";DOWN
13Ø IFDEP+DOWN>24THENPRINT"YOU CAN'T DO THA
   T":GOTO11Ø
14Ø INPUT"CENTER THE BOX LEFT/RIGHT";AN$
15Ø IFLEFT$(AN$,1)="Y"THENLEF=INT((4Ø-WID)/
   2):GOTO18Ø
16Ø INPUT"DISTANCE FROM LEFT";LEF
17Ø IFLEF+WID>39THENPRINT"YOU CAN'T DO THAT
   ":GOTO16Ø
18Ø PRINT"{SHFT CLR}":GOSUB1ØØØØ:FORI=1TO5Ø
   ØØ:NEXT:INPUT"{SHFT CLR}{CRSR DN}ANOTHE
   R BOX (Y/N)";AN$
19Ø IFAN$="Y"THEN1ØØ
2ØØ END
1ØØØØ REM *** BOX MAKER SUBROUTINE ***
1ØØ1Ø POKE211,LEF:POKE214,DOWN:PRINT"{CRSR
     UP}";
1ØØ2Ø FORI=1TOWID:PRINT"{COMD P}";:NEXT:PRI
     NT
1ØØ3Ø FORI=1TODEP:PRINTTAB(LEF);"{COMD H}";
     TAB(LEF+WID-1)"{COMD N}":PRINT"{CRSR
     UP}":NEXT
1ØØ4Ø POKE211,LEF:POKE214,DOWN+DEP+1:PRINT"
     {CRSR UP}";
1ØØ5Ø FORI=1TOWID:PRINT"{COMD Y}";:NEXT:RET
     URN
```

Sound Sampler

This program gives you 17 amusing, captivating or out-of-this-world sounds that you can add to your own programs.

By BRUCE BARTLETT

Sound Effects Sampler is a menu-driven program that demonstrates the amazing sound capabilities of the Commodore 64. The menu provides a list of sound effects with a letter beside each one. To hear the desired sound effect, press the appropriate key.

The letter of your choice lights up to indicate which effect is playing; otherwise the letter is light blue.

You can add these sound effects to your own programs by typing in the appropriate subroutines and initializing statements. There are 17 subroutines with titles at lines 100, 200, 300 and so on. Lines 10 and 20 should also be included; they clear the sound chip and define the sound parameters.

How It Works

In the sound subroutines, up to three kinds of For...Next loops are used. FOR F =...NEXT F increments or decrements frequency. That is, it sweeps the pitch from low to high, or vice versa. FOR D =... NEXT D increments or decrements duration. It varies the duration, or length, of silences in between tones. FOR N =...NEXT N increments the number of repetitions, to repeat an effect several times.

For definitions of the program variables, see Table 1.

Here are the functions of the program lines:

Line 10 clears the sound chip.

Line 20 defines the sound parameters.

Lines 25–49 make up the screen display (the menu).

Line 50 restores a yellow letter to light blue after a sound effect has been played.

Line 55 resets the attack/decay and sustain/release to nominal values for most of the sound effects.

Line 60 gets keyboard input.

Line 70 converts the typed-in letter to a number for use with the On... Goto statement in line 80.

Line 72 colors the typed-in letter yellow, to indicate which sound effect is playing.

Lines 75–77 branch to the appropriate subroutine for sound effects 16 and 17 (letters P and Q).

Line 80 branches to the appropriate subroutine for sound effects 1 through 15 (letters A through O).

Lines 100–1790 make up the sound-effect subroutines.

Inside the Subroutines

I will now briefly describe what's happening in each sound subroutine. I won't mention the ADSR settings, since they are self-explanatory. In the last program line of each sound effect, the voice is turned off. If the Filter mode, or resonance, has been used, it is also turned off. Then the program goes back to line 50 to reset the selected letter to blue and get a new keystroke.

Echoing UFO Takeoff enables ring modulation, sets the Voice-2 frequency for ring modulation and sweeps FU and FL up in frequency.

Pulsing UFO Takeoff alternates rapidly between a triangle waveform and a noise waveform as it sweeps upward in frequency.

Crystal Goblet enables the Voice-2 triangle wave, enables synchronization and sweeps up and down in frequency four times.

Alien Planet sets the Voice-2 frequencies, enables ring modulation and sweeps up and down in frequency four times.

S = 54272, the start of sound chip memory
FL = S = lower frequency
FU = S+1 = upper frequency
W = S+4 = waveform
AD = S+5 = attack/decay
SR = S+6 = sustain/release
SL = S+14 = Voice 2 lower frequency, used in Ring Modulation and Synchronization modes
SU = S+15 = Voice 2 upper frequency, used in Ring Modulation and Synchronization modes
S+21 = filter lower cutoff frequency
S+22 = filter upper cutoff frequency
S+23 = Filter and Resonance modes
V = S+24 = volume and bandpass
F = frequency (when used in a For...Next loop)
D = duration (when used in a For...Next loop)
N = number of repetitions (when used in a For...Next loop)
PU = pulse tone = memory location 54275
PL = pulse width = memory location 54274
POKEW,19 enables ring modulation
POKEW,21 enables synchronization

Table 1. *Definitions of the program variables, which refer to Voice 1, except as noted.*

RUN It Right

Commodore 64
Datassette

Circle 84 on Reader Service card.

The Handicapper

Use your **Commodore 64** to improve your performance at the track! These fine programs for **Thoroughbreds, Harness Horses** and **Greyhounds** combine the power of your computer with the savvy of a veteran handicapper. Spend a few minutes entering data, and The Handicapper will rank the horses or dogs in each race. All the information you need is readily available from the Thoroughbred Racing Form, harness or greyhound track program. We even provide a diagram that shows you where to find it!

Horse racing factors include speed, class, past performance, post position, stretch gain, beaten favorite, jockey or driver's record, weight (for thoroughbreds) and parked-out signs (for trotters). **Greyhound factors** include speed, past performance, class, favorite box, kennel record, breaking tendencies, beaten favorite.

Instructions and wagering guide included. **Thoroughbred, Harness or Greyhound Handicapper,** only $34.95 each on tape or disk. Any two, just $54.95. All three only $74.95.

Federal Hill Software
825 William Street
Baltimore, MD 21230
Toll Free (Orders Only) 800-245-6228
For Information Call 301-547-1447

Circle 202 on Reader Service card.

Program Your Own EPROMS

▶ VIC 20
▶ C 64 **$99.50**



PLUGS INTO USER PORT.
NOTHING ELSE NEEDED.
EASY TO USE. VERSATILE.

- Read or Program. One byte or 32K bytes!

OR Use like a disk drive. LOAD, SAVE, GET, INPUT, PRINT, CMD, OPEN, CLOSE—**EPROM FILES!**

Our software lets you use familiar BASIC commands to create, modify, scratch files on readily available EPROM chips. Adds a new dimension to your computing capability. Works with most ML Monitors too.

- Make Auto-Start Cartridges of your programs.
- The *promenade*™ C1 gives you 4 programming voltages, 2 EPROM supply voltages, 3 intelligent programming algorithms, 15 bit chip addressing, 3 LED's and NO switches. Your computer controls everything from software!
- Textool socket. Anti-static aluminum housing.
- EPROMS, cartridge PC boards, etc. at extra charge.
- Some EPROM types you can use with the *promenade*™

2758	2532	462732P	27128	5133	X2816A*
2516	2732	2564	27256	5143	52813*
2716	27C32	2764	68764	2815*	48016P*
27C16	2732A	27C64	68766	2816*	

▶ *Commodore Business Machines — *Denotes electrically eraseabl types

promenade™

Call Toll Free: 800-421-7731
In California: 800-421-7748

JASON-RANHEIM
580 Parrott St., San Jose, CA 95112

Circle 225 on Reader Service card.

LEROY'S CHEATSHEET®

KEYBOARD OVERLAYS



FOR COMMODORE 64

(VIC-20 also available)

LEROY'S CHEATSHEETS® are plastic laminated keyboard overlays designed for use with popular software and hardware for Commodore's VIC-20 & C-64 computers.

These cut-it-out yourself overlays are designed to fit over the keyboard surrounding the keys with commands and controls grouped together for easy references.

LEROY'S CHEATSHEETS™

make life easier for you

WORD PROCESSORS
- ☐ Easy Script
- ☐ HES Writer
- ☐ Paper Clip
- ☐ Quick Brown Fox
- ☐ Script 64
- ☐ Speedscript (GAZETTE)
- ☐ Wordpro 3/PLUS
- ☐ Omniwriter

SPREADSHEETS
- ☐ Calc Result (advanced)
- ☐ Calc Result (easy)
- ☐ Easy Calc
- ☐ Multiplan
- ☐ PractiCalc 64 (or PLUS)

DATA BASES
- ☐ The Consultant (Delphi's Oracle)
- ☐ The Manager (CBM)
- ☐ SuperBase 64

PRINTERS
- ☐ Printer (CBM) 1525, MPS 801, MPS 803
- ☐ Printer (CBM) 1526, MPS 802
- ☐ Printer (Epson) RX-80
- ☐ Printer (Gemini) 10X
- ☐ Printer Okidata 92 & 93

RUN 4

MISCELLANEOUS
- ☐ Blanks (3 each - NOT Laminated)
- ☐ For The Beginner (using the 64)
- ☐ Sprites Only
- ☐ Flight Simulator II
- ☐ Doodle
- ☐ 1541 Disk

LANGUAGES & UTILITIES
- ☐ COMAL
- ☐ SIMON'S BASIC
- ☐ Basic
- ☐ Hesmon 64
- ☐ LOGO (sheet 1)
- ☐ LOGO (sheet 2)
- ☐ Pilot (CBM)

TERMINALS
- ☐ Vidtex
- ☐ The Smart 64 Terminal
- ☐ VIP Terminal
- ☐ Term 64

Qty.___ X $3.95 $ _____
Shipping & handling $ 1.00
6% sales tax (PA residents only) $ _____
TOTAL U.S. FUNDS $ _____

Dealer inquiries welcome

Name _____
Address _____
City _____ State _____ Zip _____
(1) Products of Commodore Business Machines.

CHEATSHEET PRODUCTS™
P.O. Box 111368 Pittsburgh PA. 15238
(412) 781-1551

. . . OR SEE YOUR LOCAL DEALER !

Computer Computing enables synchronization, sets the Voice-2 frequencies and plays 50 random-frequency tones.

Chipmunk Fight enables ring modulation and plays 150 random-frequency tone bursts of Voice 1 and Voice 2.

Beating Rising Buzzer sets the Voice-2 upper frequency, sets the Voice-1 frequencies, enables ring modulation and sweeps the Voice-2 lower frequency slowly upward.

Seasick enables ring modulation and sweeps the Voice-2 lower frequency up and down four times.

Rubber Band sets the Voice-1 lower and upper frequencies, sets the Voice-2 upper frequency, enables synchronization and sweeps the Voice-2 lower frequency upward in frequency.

Chime sets the Voice-2 frequencies, sets the Voice-1 upper frequency and turns on a ring-modulated tone with ADSR set to sound like a chime.

Spinning Falling Wheel enables the bandpass filter, sets resonance to maximum, turns on the sawtooth waveform and sweeps Voice 1 and the filter-cutoff upper frequency *down* in frequency at an accelerating rate (by increasing the step size). Whew!

Bwee turns on the triangle waveform and sweeps a gentle tone upward between two random frequencies, 30 times.

Cosmic Rays turns on the sawtooth waveform and sweeps Voice 1 down in frequency between two random frequencies, 15 times.

Pulse Sweep sets the Voice-1 frequency, turns on the pulse waveform, sets the pulse width and tone and sweeps the pulse width from long to short to long, three times.

Ow sets Voice 1 to a random frequency, sets resonance to maximum, enables the bandpass filter and sweeps down the bandpass-filter upper frequency. All this is repeated ten times.

Warbling turns on the triangle waveform, sweeps upward rapidly in frequency 30 times, then sweeps upward less rapidly, 20 times.

Deedle Deedle turns on the sawtooth waveform and alternates between two frequencies; first slowly (duration D is long), then rapidly (D is short), then slowly (D is long).

If you'd rather not type in the program, I'll be glad to send you a copy if you send me $3, a self-addressed stamped envelope and a blank cassette with "Sound Effects Sampler" printed on the label. R

Address all author correspondence to Bruce Bartlett, 26921 Dumbarton Court, Elkhart, IN 46514.

Listing 1. *Sound Effects Sampler program.*

```
5 PRINT"{SHFT CLR}"
10 S=54272:FORL=0TO24:POKES+L,:NEXT
20 V=S+24:W=S+4:FU=S+1:FL=S:AD=S+5:SR=S+6:S
   L=S+14:SU=S+15:POKEV,15:POKEAD,15
25 PRINT"{CRSR DN}{5 SPACEs}{CTRL 8}*** {CT
   RL 9}SOUND EFFECTS SAMPLER{CTRL 0} ***"
30 PRINT"{CRSR DN}{11 SPACEs}{CTRL 6}BY BRU
   CE BARTLETT{COMD 7}"
31 PRINT"{CRSR DN}{CTRL 9}A{CTRL 0} ECHOING
    UFO TAKEOFF"
32 PRINT"{CTRL 9}B{CTRL 0} PULSING UFO TAKE
   OFF"
33 PRINT"{CTRL 9}C{CTRL 0} CRYSTAL GOBLET"
34 PRINT"{CTRL 9}D{CTRL 0} ALIEN PLANET"
35 PRINT"{CTRL 9}E{CTRL 0} COMPUTER COMPUTI
   NG"
36 PRINT"{CTRL 9}F{CTRL 0} CHIPMUNK FIGHT"
37 PRINT"{CTRL 9}G{CTRL 0} BEATING RISING B
   UZZER"
38 PRINT"{CTRL 9}H{CTRL 0} SEASICK"
39 PRINT"{CTRL 9}I{CTRL 0} RUBBER BAND"
40 PRINT"{CTRL 9}J{CTRL 0} CHIME"
41 PRINT"{CTRL 9}K{CTRL 0} SPINNING FALLING
    WHEEL"
42 PRINT"{CTRL 9}L{CTRL 0} BWEE"
43 PRINT"{CTRL 9}M{CTRL 0} COSMIC RAYS"
44 PRINT"{CTRL 9}N{CTRL 0} PULSE SWEEP"
45 PRINT"{CTRL 9}O{CTRL 0} OW"
46 PRINT"{CTRL 9}P{CTRL 0} WARBLING"
47 PRINT"{CTRL 9}Q{CTRL 0} DEEDLE DEEDLE"
49 PRINT"{CRSR DN}{CTRL 4}{5 SPACEs}TYPE TH
   E LETTER OF YOUR CHOICE{COMD 7}"
```

PEOPLE SAY THE NICEST THINGS ABOUT WORDPRO 64TM

"Well thought out and easy to use" — W.H., Halifax N.S.
"By far the best..." — R.H., Oneonta N.Y.
"A remarkable product - the most powerful word processing program I have ever seen." — J.H., Nantucket Mass.
"I will not hesitate to give unqualified endorsement." — B.W., Gig Harbour Wa.

Toll Free Order Line
1-800-387-3208
PRO·LINE SOFTWARE
755 The Queensway East, Unit 8, Mississauga, Ontario, Canada L4Y 4C5 . Phone 416-273-6350

Listing 1 continued.

```
5Ø IFA>ØANDA<18THENPRINT"{HOME}":FORN=1TOA+
   3:PRINT:NEXT:PRINT"{CTRL 9}{COMD 7}"CHR$
   (A+64)"{CTRL Ø}"
55 POKEAD,15:POKESR,Ø
6Ø GETA$:IFA$=""THEN5Ø
7Ø A=ASC(A$)-64:IFA<1ORA>17THEN5Ø
72 PRINT"{HOME}":FORN=1TOA+3:PRINT:NEXT:PRI
   NT"{CTRL 9}{CTRL 8}"CHR$(A+64)"{CTRL Ø}"
75 IFA=16THEN16ØØ
77 IFA=17THEN17ØØ
8Ø ONAGOTO1ØØ,2ØØ,3ØØ,4ØØ,5ØØ,6ØØ,7ØØ,8ØØ,9
   ØØ,1ØØØ,11ØØ,12ØØ,13ØØ,14ØØ,15ØØ
1ØØ REM ***ECHOING UFO TAKEOFF***
11Ø POKESR,8
12Ø POKEW,21
13Ø POKESL,67:POKESU,12
14Ø FORF=ØTO255:POKEFU,F:POKEFL,F:NEXT
15Ø POKEW,2Ø:FORT=1TO1ØØ:NEXTT
16Ø GOTO5Ø
2ØØ REM ***PULSING UFO TAKEOFF***
21Ø FORF=ØTO155:POKEW,17:POKEFU,F:FORT=1TO6
   :NEXTT
22Ø POKEW,129:FORT=1TO5Ø:NEXTT
23Ø NEXTF
24Ø POKEW,128
25Ø GOTO5Ø
3ØØ REM CRYSTAL GOBLET
31Ø POKES+18,17:POKEW,19
32Ø POKESU,64
33Ø FORN=1TO4
34Ø FORF=1TO255:POKEFU,F:NEXTF
35Ø FORF=255TO1STEP-1:POKEFU,F:NEXTF
36Ø NEXTN
37Ø POKEW,18:GOTO5Ø
4ØØ REM ***ALIEN PLANET***
41Ø POKESL,67:POKESU,12
42Ø POKEW,21
43Ø FORN=1TO4
44Ø FORF=ØTO255:POKEFU,F:NEXTF
45Ø FORF=255TOØSTEP-1:POKEFU,F:NEXTF
46Ø NEXTN
47Ø POKEW,2Ø:GOTO5Ø
5ØØ REM ***COMPUTER COMPUTING***
51Ø POKESL,24Ø:POKESU,12
52Ø POKEW,19
53Ø FORN=1TO5Ø:F=INT(RND(1)*255)+1:POKEFU,F
54Ø FORT=1TO6Ø:NEXT
55Ø NEXTN
56Ø POKEW,18:GOTO5Ø
6ØØ REM ***CHIPMUNK FIGHT***
61Ø POKEW,21
62Ø FORN=1TO15Ø:F=INT(RND(1)*255)+1
63Ø POKEFU,F:POKESU,F
64Ø FORT=1TO12:NEXTT
65Ø NEXTN
66Ø POKEW,2Ø:GOTO5Ø
7ØØ REM ***BEATING RISING BUZZER***
71Ø POKEAD,9:POKESU,3
72Ø POKESR,64+12
73Ø POKEFU,4:POKEFL,1Ø
74Ø POKEW,21
75Ø FORF=ØTO255STEP.3:POKESL,F:NEXT
76Ø POKEW,2Ø:FORT=1TO1ØØØ:NEXT:GOTO5Ø
8ØØ REM ***SEASICK***
81Ø POKEAD,63:POKEFU,4:POKEFL,1Ø:POKESU,1Ø
82Ø POKEW,21
83Ø FORN=1TO4
84Ø FORF=ØTO255:POKESL,F:NEXTF
85Ø FORF=255TOØSTEP-1:POKESL,F:NEXTF
86Ø NEXTN
87Ø POKEW,2Ø:GOTO5Ø
9ØØ REM ***RUBBER BAND***
91Ø POKEAD,1Ø:POKESR,64+9
92Ø POKEFU,67:POKEFL,12:POKESU,5
93Ø POKEW,19
94Ø FORF=ØTO255STEP1.3:POKESL,F:NEXT
95Ø POKEW,18:FORT=1TO5ØØ:NEXT:GOTO5Ø
1ØØØ REM ***CHIME***
1Ø1Ø POKEAD,1Ø:POKESR,64+11
1Ø2Ø POKESU,1Ø:POKESL,1Ø
1Ø3Ø POKEFU,4:POKEW,21:FORT=1TO5Ø:NEXT
1Ø4Ø POKEW,2Ø:FORT=1TO18ØØ:NEXT
1Ø5Ø GOTO5Ø
11ØØ REM ***SPINNING FALLING WHEEL***
111Ø POKEV,15+32:POKES+23,239
112Ø POKEW,33
113Ø FORSP=1ØTO255
114Ø FORF=255TOØSTEP-SP:POKEFU,F:POKES+22,F
   :NEXT
115Ø NEXTSP
116Ø POKEW,32:POKES+23,Ø:GOTO5Ø
12ØØ REM ***BWEE***
121Ø POKEAD,119
122Ø FORN=1TO3Ø
123Ø POKEW,17
124Ø FORF=INT(RND(.)*5Ø)+5ØTOINT(RND(.)*15Ø
   )+5ØSTEP2:POKEFU,F:NEXT:POKEW,16
125Ø NEXTN
126Ø GOTO5Ø
13ØØ REM ***COSMIC RAYS***
131Ø POKEAD,119
132Ø FORN=1TO15
133Ø POKEW,33
134Ø FORF=INT(RND(.)*15Ø)+5ØTOINT(RND(.)*5Ø
   )STEP-1
135Ø POKEFU,F:NEXTF
136Ø POKEW,32
137Ø NEXTN
138Ø GOTO5Ø
14ØØ REM ***PULSE SWEEP***
141Ø POKEFU,2:POKEFL,12:POKEW,65:PL=54274:P
   U=54275
142Ø FORN=1TO3
143Ø FORL=ØTO255STEP2:POKEPL,L:POKEPU,Ø:NEX
   T
144Ø FORL=255TOØSTEP-2:POKEPL,L:POKEPU,Ø:NE
   XT
145Ø NEXTN
146Ø POKEW,64:GOTO5Ø
15ØØ REM ***OW***
151Ø POKEAD,47:POKES+23,239:POKEV,15+32
152Ø FORN=1TO1Ø
153Ø POKEFU,INT(RND(.)*5)+2
154Ø POKEW,33
155Ø FORSW=1ØØTOØSTEP-3
156Ø POKES+22,SW:NEXTSW
157Ø POKEW,32:FORT=1TO1ØØ:NEXT
158Ø NEXTN
159Ø POKES+23,Ø:POKEV,15:GOTO5Ø
16ØØ REM ***WARBLING***
161Ø POKEW,17:FORN=1TO3Ø
162Ø FORF=5ØTO2ØØSTEP2Ø:POKEFU,F:NEXTF
163Ø NEXTN
164Ø FORN=1TO2Ø
165Ø FORF=5ØTO2ØØSTEP1Ø:POKEFU,F:NEXTF
166Ø NEXTN
167Ø POKEW,16:GOTO5Ø
17ØØ REM ***DEEDLE DEEDLE***
171Ø POKEW,33:FORD=1ØØTOØSTEP-5
172Ø POKEFU,64:FORT=1TOD:NEXT
173Ø POKEFU,54:FORT=1TOD:NEXT
174Ø NEXTD
175Ø FORD=ØTO1ØØSTEP5
176Ø POKEFU,64:FORT=1TOD:NEXT
177Ø POKEFU,54:FORT=1TOD:NEXT
178Ø NEXTD
179Ø POKEW,32:GOTO5Ø
```

From p. 10.

The ideal dummy line would be easy to type in, easy to replicate with various line numbers and would be self-documenting when executed. After years of looking, I finally found it:

```
1200 STOP:RETURN
```

When executed, this line will cause a Break In XXX message, where XXX is whatever line number you've given it. When you then enter CONT, the program will return from the subroutine. Of course, if you've used a Goto rather than a Gosub command, you don't need the Return command in your dummy line.

Louis F. Sander
Pittsburgh, PA

$1CD Calculated Goto command—On the C-64, you can use this one-liner to jump to any calculated line number within your program. Simply set the variable GL to the desired line number, then enter GOTO 1000.

```
1000 POKE 785,188 : POKE 786,168 : POKE GL,PEEK(GL) :
     GL = USR(0)
```

It may not look like it, but believe me, it works! [Yes, it does! Ed.]

Randy Thompson
Eugene, OR

$1CE Shifted REMs—If you put a shifted letter inside a REM statement, the computer will interpret it as a Basic keyword when it is listed. (The same is true of the graphics characters created by the Commodore key.)

A shifted L in any REM statement will cause a Syntax error if the computer tries to list it. REM followed by an alternating series of shifted V's and unshifted spaces will commemorate nylon stockings, the Olympics and an equally famous fountain of knowledge. Replacing the shifted V's with shifted S's will show what you do with the latter.

When shifted or Commodore key characters follow a quotation mark, they list as themselves rather than as Basic keywords. So, if you *must* use shifted characters in your REM statements, precede them by a quotation mark.

Ellen Pekar
Florence, MA

$1CF Word trick contest—Last month, we announced a contest based on the principle described above. This month's grand prize entry is:

```
10 LIST
20 REM  Q: HOW FAR IS IT FROM THE TOP
21 REM     OF THE EMPIRE STATE
22 REM     BUILDING TO THE BOTTOM?
```

Circle 137 on Reader Service card.

Dreams CAN come true!

Back in June of 1983, Kelvin Lacy had a dream. He dreamed of creating one integrated program that would include a spreadsheet, business graphics *and* a database. A program with the power of Lotus 1-2-3. On the Commodore 64. People laughed! He had just finished OmniWriter, to be marketed by HESWARE. Ignoring the skeptical, he started on VIZASTAR.

Now, after 15 months, his dream has come true. VIZASTAR has a full-featured spreadsheet, as good as Multiplan. But much faster—faster than many spreadsheets on the IBM PC! It is written 100% in 6502 machine language code and is ALWAYS in memory. It is menu-driven, using the latest techniques in user-friendliness. It is compatible with virtually all printers and word processors. Up to 9 windows can be open simultaneously, anywhere. Remarkably, 10K of memory is available for spreadsheet use.

The database is equally impressive. Create file layouts by simply painting a picture of the layout on up to 9 screens, showing where a field starts and ends; VIZASTAR does the rest.

Imagine the power of a spreadsheet integrated with a database. Now add graphics — bar, line, and multi-color pie and 3-D "skyscraper" graphs. You could access a customer's profile in the database, transfer the data to the worksheet, and let it calculate discounts, sales tax etc. and then transfer the updated data back to the database. Open up a window anywhere and display a graph of your data, instantly. This integration is the key to VIZASTAR's power—the **first and only** program of this kind on the C-64. All commands can be automated, so you can "program" your own applications and run them with one keystroke.

Trademarks: Lotus 1-2-3/Lotus Development. Commodore 64/Commodore Electronics Ltd. Multiplan/Microsoft.



Actual screen dump printed by VIZASTAR

VIZASTAR includes a cartridge, a 1541 diskette with a backup, reference and tutorial manuals. VIZASTAR is ONLY $119.97. We are so positive you will be delighted with VIZASTAR that we offer a **15day money-back** guarantee. Try it risk-free! Compare VIZASTAR with any other spreadsheet or database.

So order today. Call or send a check or Money Order. Calif. residents add 6.5% sales tax. MC/VISA accepted.
Add P&H: UPS—$3; COD, Canada—$6

SOLID STATE SOFTWARE

1125 E. Hillsdale Blvd., Suite 104
Foster City, CA 94404-1609
(415) 341-5606
Dealer Inquiries Welcome

```
30 REM " A: {2 SPACES}{SHIFT -}{E}{SPACE}{SHIFT
   LB.}{SHIFT 1}
40 REM  Q: WHAT TAKES TWO (10 BINARY)?
50 REM " A: {2 SPACES}{COMD @}{SPACE}{SHIFT *}{SHIFT K}
60 REM  Q: WHAT DID THE BROKEN GUITAR
61 REM       SAY TO ITS DISTRAUGHT OWNER?
70 REM " A: {2 SPACES}{COMD LB.}{SPACE}{COMD @}
   {SPACE}{COMD U}{T}
```

Type the answers very carefully, with no extra spaces, and save the program. Then delete the quotes and run it to see the answers.

Gary Forney
Oelwein, IA

$1D0 Last prize

—This is the absolute worst entry we received. It is printed here as a tribute to programming ingenuity, no matter how misdirected.

```
10 LIST
20 REM  Q: WHAT'S AN APPLECOSTA?
30 REM " A: {2 SPACES}{COMD V}
   {T}{SPACE}{A}{SPACE}{SHIFT R}{E}
```

Mike Leherr
Startzen University
Puget Sound, WV

$1D1 Automatic line numbering

—This Direct mode line puts ten line numbers on the screen. By moving your cursor to the proper position on the screen line, then typing a program line, you can use them as line numbers.

```
FOR A = 10 TO 100 STEP 10 : PRINT A : NEXT
```

The number values, of course, can be changed to anything you'd like. If you're typing in Data statements, change the line to read:

```
FOR A = 10 TO 100 STEP 10 : PRINT A;"DATA" : NEXT
```

You then only have to enter the data items themselves.

Lum Kin Leon
Kuala Lumpur, Malaysia

$1D2 Fade in, fade out

—Have you ever thought of having the title of your program fade in, then out, on a black screen? It's a nice effect, and it's actually quite simple. The C-64 has 16 colors, three of which are different shades of gray, with black and white at either end, and you can use them in your fading process. The following program summarizes it. Have fun!

```
10 POKE 53280,0 : POKE 53281,0
20 A$(1) = "{CTRL 2}" : A$(2) = "{COMD 8}" : A$(3) = "{COMD 5}" :
   A$(4) = "{COMD 4}" : A$(5) = "{CTRL 1}"
```


Circle 23 on Reader Service card.

COMMODORE
-USER WRITTEN SOFTWARE-
Supporting all COMMODORE computers
Written by users, for users
★ GAMES ★ UTILITIES ★ EDUCATIONAL ★

Our Latest Releases

C-64	Best Of Games	$10.00
C-64	Best Of Educational	$10.00
C-64	Best Of Utilities	$10.00
C-64	84 Contest C-64 #1	$10.00
C-64	84 Contest C-64 #2	$10.00
C-64	84 Contest C-64 #3	$10.00
Vic 20	Best Of Games	$10.00
Vic 20	Best Of Educational	$10.00
Vic 20	Best Of Utilities	$10.00
Vic 20	Contest Vic #1	$10.00

Specify Disk Or Tape

COMAL STARTER PAK
4 Disk Set - $35.00

Bulletin Board System For C-64 or VIC 20
On Best Of Utilities Collections-$10.00-Specify Disk Or Tape

COMMODORE 64™
64 collections # 1 thru 12
25 + programs per collection-Tape/Disk $10.00 each

VIC 20™
Vic 20 collections # 1 thru 12
50 + programs per collection-Tape/Disk $10.00 each

DINSET™: Reset Switch
Works on Vic 20 or Commodore 64 — $5.00

SERIAL CABLES
10 FT.—$10.00 15FT.—$15.00

LOC-LITE™ Operation Status Indicator
Assembled and Tested $20.00
Kit w/inst. $15.00 Board w/inst. $7.50

PDI Program Manual $10.00
Instructions and Help For VIC-20 and C-64 Collections

Shipping and Handling Charges
US/Canadian Orders Add $3.00
Foreign Orders Add $5.00
CHECK, MONEY ORDERS, VISA and MASTERCARD accepted. No COD's or P.O.'s
Write For A FREE Catalog
FREE CATALOG FREE CATALOG

'PUBLIC DOMAIN™', INC.
5025 S. Rangeline Rd., W. Milton, OH 45383
10:00 a.m. - 5:00 p.m. EST — Mon. thru Fri.
(513) 698-5638 or (513) 339-1725

VIC 20™, CBM™ and Commodore 64™ are Trademarks of Commodore Electronics Ltd.
PET® is a Registered Trademark of Commodore Business Machines, Inc.

BEST C64 EDUCATIONAL 1
BEST C64 EDUCATIONAL 2
84 CONTEST VIC 1
84 CONTEST C64 1
84 CONTEST C64 2
84 CONTEST C64 3
BEST C64 UTILITIES 1
BEST C64 UTILITIES 2
BEST VIC UTILITIES 1
BEST VIC UTILITIES 2
BEST VIC EDUCATIONAL 1
BEST VIC EDUCATIONAL 2
BEST VIC GAMES 1
BEST VIC GAMES 2
BEST VIC GAMES 3
BEST VIC GAMES 4
BEST VIC GAMES 5
BEST VIC GAMES 6
BEST VIC GAMES 7
BEST VIC GAMES 8
BEST VIC GAMES 9
BEST VIC GAMES 10
BEST VIC GAMES

```
30 INPUT "{SHIFT CLR} MESSAGE";ME$
40 PRINT "{SHIFT CLR}" : FOR J = 5 TO 1 STEP -1 : PRINT
   "{HOME}";A$(J);ME$ : FOR K = 1 TO 95 : NEXT : NEXT
50 FOR J = 1 TO 5 : PRINT "{HOME}";A$(J);ME$ : FOR K = 1 TO 95
   : NEXT : NEXT : PRINT A$(1)
```

Greg Burns
Address unknown

$1D3 Disk wedge tip—Wedge commands can be used from within Basic programs, as long as the proper syntax is used. The @, >, /, % or up-arrow symbol must be the first character in the statement, with no quotes around it. The rest of the command must be enclosed in quotes. The following routine, for example, will put a directory on the screen, read the error channel, print a message, then load a program.

```
200 @ "$"
210 @
220 PRINT "WIZARDRY, INDEED!"
230 / "THE LAND OF OZ"
```

With normal Program mode loads, you must be concerned about program length; with this one, you don't. The technique has worked with every wedge command we've tried it on.

Arnie Lee
Abacus Software

Circle 172 on Reader Service card.

FANTASTIC FILER
COPYRIGHT© 1984 BY DAVID M. SMITH
A SOPHISTICATED AND EASY TO USE FILE MANAGEMENT SYSTEM FOR THE COMMODORE 64 AND 1541 DISK DRIVE. PACKAGE INCLUDES:

1) Complete Menu Driven subsections.
2) Simple One Stroke Key Commands
3) Free form record layout design to place data anywhere on the screen.
4) Maximum of 50 fields per record.
5) Maximum of 256 characters/record.
6) Average of 1000 records per disk.
7) Fast 3 second search using index match or specific search criteria on all field combinations.
8) Full arithmetic calculations between fields
9) Built in multifunction columnar report and mailing label generator.
10) Ability to create sequential disk sub files for merging data with popular word processors.
11) Complete and thorough users manual.

SO MUCH SOFTWARE FOR ONLY $29.95

All in all Fantastic Filer is a Fantastic Data Base Program at an even more Fantastic price. Why pay more for others when Fantastic Filer will fill your data base needs?

Available from:
Micro-W. DISTRIBUTING, INC.
1342 B Route 23
Butler, N.J. 07405
Call: (201) 838-9027 To Order

$1D4 Shifted spaces in filenames—Things would be easier if all disk files had short names—like M1 instead of MONITOR.49152, for example. But how do you remember the meaning of M1? If you save or rename a file using a shifted space inside the name, you can use its left portion (before that shifted space) as a normal name, while the rest of it may be treated as a comment. If you save a program as

"M1{shift space}MONITOR.49152"

the directory will list it as

"M1"MONITOR.49152

From then on, you will be able to treat it as just "M1." If you forget, just list the directory and see the whole name. Incidentally, the DOS still considers the entire name, so these two files can coexist with no problems:

"M1"MONITOR.49152
"M1"MONITOR.51111

This is not any convenience, however, since any command aimed at "M1" will affect only the one that appears first in the directory.

Carlos A.G. de Figueiredo
Sao Paulo, Brazil

$1D5 Easy load filenames—If you load programs by typing on top of a directory listed to the screen, the easy part is typing the word LOAD on top of the number of blocks to the left of the filename. It's somewhat harder to move the cursor past the filename in order to type ,8,1 or ,8: (either the ,1 or the colon removes the need to erase the PRG).

It is generally known that messages may be embedded to the right of the filename, just past the second question mark, by renaming the file and using a shifted space to separate the filename from the message. If we could put a ,8,1 message in the filename like that, we'd make it a lot easier to load the program from its directory listing. Unfortunately, the drive will not accept a comma when it renames a file.

But there is a way to put a comma there. Instead of using a comma, use a Commodore-D, the little block character that the D key makes when pressed with the Commodore key. The disk drive will accept this character, and the new directory will print it out as a comma!

For example, to embed the phrase ,8,1 after the filename MERLIN, just type the following.

```
OPEN 15,8,15 , "R:MERLIN{shift space}{COMD D}8{COMD D}
1 = MERLIN" : CLOSE 15
```

To put a colon in the filename, use the shifted @.

Doug Ferguson
Elida, OH

$1D6 Disk de-banger—When using copy-protected programs, the copy-protection scheme can create a lot of disk-head bumping, as evidenced by the 1541's machine-gun sound effects. The banging tends to knock

drives out of alignment or to kill them before their time.

If you run the following program before loading any DOS-protected software, most of the banging will stop.

```
10 OPEN 15,8,15
20 PRINT#15,"M-W";CHR$(106)CHR$(0)CHR$(1)CHR$(133)
30 CLOSE 15
```

The de-banger will stay in effect until the drive is powered down.

Gilbert D. Helland
Scott AFB, IL

$1D7 Directory trouble—I forgot to enter NEW after loading a disk directory, and after spending an hour typing in a program, I found I was in trouble. When the program was listed, the directory lines were interspersed with the program lines. Since the directory line "numbers," really the numbers of sectors, etc., were not in numerical sequence, they wouldn't erase in the usual way.

I solved the problem by renumbering the few program lines that were mixed in with the directory numbers and erasing the original program lines. When I relisted the program, all the directory lines appeared at the beginning, where they could easily be deleted by typing their numbers.

Richard L. Mitchell
Lafayette, LA

$1D8 Loading machine language—The common way to load a machine language program from disk is:

```
LOAD "filename",8,1
```

It isn't widely known that *any* odd number can be used instead of the 1. I find it easier to use:

```
LOAD "filename",8,9
```

since the 9 is right next to the 8 on the keyboard.

Eric the Juggler
Squirrel Hill, PA

$1D9 Loading "*"—When you enter LOAD"*",8 with your Commodore disk drive, you don't always get the first program on the disk. Usually, in fact, you get the last program you've accessed. To fix this, just insert a colon in front of the asterisk:

```
LOAD":*",8
```

This gives you the first program every time.

Brian Kennedy
Colorado Springs, CO

$1DA Disk copying tip—When making a copy of disks, using the programs that require switching source and destination disks, it is a good idea to put a write-protect tab over the window of the source disk. It provides extra protection against accidental erasing of the source material.

Larry Thomas
Hooks, TX

WHATEVER HAPPENED TO FAY WRAY

In the software jungle,
no copy program for the Commodore 64™
works better or copies more at any price!
Copy Q is the fastest, most reliable, and easiest-to-use.
And **Copy Q** even comes with a backup!

The NEW **Copy Q** contains a TRUE INTELLIGENT NIBBLER which copies all the information on a disk and even the newest copy protection including half tracks, track 36+, varying data density, misordered and extra sectors, gap and sync tracks, and much more.

Copy Q is fully automatic. There are no parameters to set. You don't even need to swap disks when using two drives.

And **Copy Q** makes the FASTEST backups by using intelligent scanning, data compression, and super-fast data communication. Most disks are copied in just three minutes. And many disks that require extensive nibbling are copied in less than five minutes.

Copy Q contains other features found nowhere else: **Copy Q** revirgins disks rather than erasing them. **Copy Q** also contains a utility that automatically backs up any data disk and removes all data errors in just two minutes.

It's a software protection jungle and your data and program integrity are at stake. So don't monkey around with the others. You can climb straight to the top with the NEW **Copy Q** by Q-R & D.

Now only **$39.95**
Seven day money back guaranteed.

Copy Q and other fine Q-R & D products are available at more than 300 dealers nationally. For the name of the dealer nearest you call:

To Order Direct call: **612 831-1088**
612 922-0516

Q R&D

ONE WEST LAKE STREET, MINNEAPOLIS MN 55408 – 612 922-7628

Circle 188 on Reader Service card.

Graph Maker 64

This program allows you to create, save and print colorful vertical bar graphs on your C-64. It also includes two routines that let you load your graphs into other programs.

By DOUG SMOAK

Graph Maker draws vertical bar graphs on your screen, then allows you to add titles and text, and edit the screen. You can then save your graph to disk and print out a hard copy. Once saved, you can reload the screens to edit or print out again.

Also, I have included two routines you can add to your own programs to load previously prepared graphs for presentations.

Setting Up the Graph

After you type in Graph Maker (Listing 1), save it. When you run the program, you'll be prompted for bar parameters of the graph. You must first give the maximum vertical scale. This should be at least the size of the highest value to be graphed.

Occasionally, you might have one value that greatly exceeds the rest of the bars. To avoid a disproportionate graph, you should enter a value closer to the second highest bar. In this case, the largest bar will still appear, reaching to the top of the screen. You can then use the Text mode to enter that highest bar's actual value.

You will find that using whole numbers for the maximum graph value will yield a more attractive display. If your values are more than three digits, then only the left-most three digits will be displayed. This is



Screen shot of Graph Maker program.

necessary to maintain as much space for the bars as possible. If you have very high values, it is probably better to break them into percentages and then use 100 as your maximum value; or you can divide them by 100, 1000 and so on, and, in Text mode, add a note like "in hundreds." The best way to learn is just to experiment with the program for a while.

The second prompt will request the number of vertical bars you want on the screen. You may have from two to 36. I chose 36 as the maximum because it is more evenly divisible by the most likely charted items, such as 12 months (up to three years' worth). Here again, you'll receive the best results by experimenting to get a feel for how it works.

Next, you will be prompted to label each of the bars and told how many characters each title can possess. If you want only numbers beneath each bar, just hit the return key, and Graph Maker will automatically enter the number for that bar as its title.

After having set the maximum bar height, the number of bars and their labels, the final step will be to enter the values for each bar. You will be prompted for the value to be graphed, with the title after the number, such as:

```
BAR #1, JAN
```

These values must be entered carefully to avoid having to redo all of the input.

After all the data has been entered, the graphing begins, taking only a few seconds for even a 36-bar chart. Then, at the bottom of the screen, you will see a flashing prompt showing the options available: Text, Save, Abort, Load and Print.

If you hit A for Abort, the program will rerun from the beginning and wipe out what has been done up to that point.

The Program's Options

Text mode will give you a flashing cursor that you can move about the screen to add titles or notes or to edit bar titles. Just use the cursor controls

RUN It Right

Commodore 64
1541 disk drive

to move about and then type in your desired characters. If you want a reversed character, you must first type it in normally; then go back and press the return key over each character you want highlighted.

To change colors in Text mode, just do it as you normally would, by simultaneously pressing the CTRL and color keys or the Commodore and color keys. When you have finished with Text mode, you escape to Command mode by pushing the pound key (£). Then you will again get the flashing prompt.

If you hit S for Save, the flashing prompt will be replaced with a prompt for a filename. To abort this option, hit the return key without entering a name. After entering the filename, the drive should come on and *two* saves will be made. Why two?

The first file is the screen memory, saved right off the screen as a program file. The second (saved as filename.C) is the screen-color memory, saved right out of memory as a second program file. This means that for every graph, there are two files of four blocks each on the disk. The color file has the same name as the screen file, except ".C" is added to it.

When you hit L for Load, you will again be prompted for your filename. You enter only the filename for the screen file; the program itself will then look for the color file with the same name. You could use this option to make rough drafts, saving them and then later reloading to add text before resaving final versions. To abort the Load option, just hit the return key without entering a name.

Don't save graphs under the same name, or you'll get a disk error. In the case of any Load or Save errors, you will get a flashing message on the bottom line of the screen and an opportunity to redo the procedure.

If you choose P for a printout of the screen, you must have a printer/interface combination that will support the 64's keyboard graphics; otherwise the printout will not be usable. Note that the printout uses double-width characters to make a chart that is 80 columns wide. If you want smaller charts (40 columns), then change CHR$(14) in line 1470 (in the printout routine) to CHR$(15).

The two short loader programs will allow you to load your screens into your own programs. The first one is



Figure 1. *Sample of Graph Maker hardcopy.*

Listing 1. *Graph Maker program.*

```
1 REM ******************************
2 REM *{29 SPACEs}*
3 REM *{6 SPACEs}GRAPHMAKER 64 (C) 1984 *
4 REM *{9 SPACEs}DOUG SMOAK{1Ø SPACEs}*
5 REM *{9 SPACEs}3Ø3 HEYWARD ST.{5 SPACEs}*
6 REM *{9 SPACEs}COLUMBIA SC 292Ø1{3 SPACEs
  }*
7 REM *{9 SPACEs}(8Ø3)-765-1189{6 SPACEs}*
8 REM *{29 SPACEs}*
9 REM ******************************
1Ø BO=5328Ø:BG=BO+1:POKEBG,Ø:POKEBO,Ø:POKE5
  6296,Ø
2Ø OV$="{41 CRSR RTs}"
3Ø DN$="{HOME}{21 CRSR DNs}"
4Ø BL$=DN$+"{3 CRSR DNs}"+"{38 SPACEs}{HOME
  }"
5Ø CC=4:DIMFR$(7),T$(36),V(36),CL$(7),F$(2)
  ,S(2),E(2)
6Ø S(1)=1Ø24:E(1)=2Ø24:S(2)=55296:E(2)=5629
  7
7Ø CL$(Ø)="{COMD 5}":CL$(1)="{CTRL 8}":CL$(
  2)="{COMD 1}":CL$(3)="{CTRL 3}":CL$(4)="
  {CTRL 5}":CL$(5)="{CTRL 7}"
8Ø CL$(6)="{COMD 7}":CL$(7)="{COMD 8}"
9Ø PRINT"{SHFT CLR}{COMD 5}{14 SPACEs}GRAPH
  MAKER 64"
1ØØ PRINT"{2 CRSR DNs}{CRSR RT}C{LEFT ARROW
  }CREATE A GRAPH":PRINT"{CRSR DN}{CRSR R
  T}L{LEFT ARROW}LOAD A GRAPH"
11Ø GETG$:ON-(G$="")GOTO11Ø:IFG$<>"L"ANDG$<
  >"C"THEN11Ø
12Ø IFG$="L"THEN117Ø
13Ø INPUT"{SHFT CLR}{CRSR DN}{CRSR RT}MAXIM
  UM VERTICAL SCALE VALUE";MX:BI=MX/2Ø:LI
  =BI/7:IFMX=<ØTHEN13Ø
14Ø GOSUB28Ø:GOSUB57Ø
15Ø FORI=1TOVB
16Ø PRINT"{SHFT CLR}{CRSR DN}{CRSR RT}VALUE
   TO BE GRAPHED":PRINT"{CRSR DN}{CRSR RT
  }FOR BAR #"I"{CRSR LF}, "T$(I);
17Ø INPUTV(I):IFV(I)>MXTHENV(I)=MX
18Ø GOSUB39Ø
19Ø NEXT:PRINTGR$MX$
2ØØ :
21Ø REM ** LOOP FOR BARS **
22Ø :
23Ø FORC=1TOVB:V=V(C):V=V-3*(BI/7):GOSUB46Ø
  :NEXT
24Ø GOTO81Ø
25Ø :
26Ø REM ** SET UP PARAMETERS **
27Ø :
28Ø PRINT"{SHFT CLR}{CRSR DN}{CRSR RT}HOW M
  ANY VERTICAL BARS":PRINT"{CRSR DN}{CRSR
   RT}(2-36) ";:INPUTVB
29Ø IFVB>36ORVB<2THEN28Ø
3ØØ BW=INT(36/VB)
31Ø FORI=1TOVB
32Ø PRINT"{SHFT CLR}{CRSR DN}{CRSR RT}TITLE
   FOR BAR #"I:PRINT"{CRSR DN}{CRSR RT}UP
   TO"BW"CHARACTERS";
33Ø INPUTT$(I):IFT$(I)=""THENT$(I)=STR$(I)
34Ø IFLEN(T$(I))>BWAND(BW>2)THEN32Ø
35Ø NEXT:RETURN
36Ø :
37Ø REM ** CENTER ROUTINE **
38Ø :
39Ø IFBW<3THENT$(I)=RIGHT$(T$(I),1):RETURN
4ØØ IFLEN(T$(I))=BWTHENRETURN
41Ø MR=BW-LEN(T$(I)):MR=MR/2:IFMR<1THENRETU
  RN
```

→

A NEW YEAR, A NEW ReRUN

1985 March Quarterly

You live in a complicated world. The last thing you need is stress that comes from do-it-yourself programming.

This year, let the new **ReRUN** give you great ready-to-load Commodore-64, Plus/4*, and VIC-20 programs more often.

Beginning in March, the best and most recent programs listed in **RUN** can be yours every four months. That's right, **ReRUN**'s going quarterly! AND . . . Commodore-64 and VIC-20 programs will be offered on separate cassettes/disks! No more getting only half of what you're looking for.

Every quality cassette or disk will contain approximately 10 outstanding programs for home, business, or school. And just in time to help you face the IRS, the March **ReRUN** will be highlighted by "Tax Records 64" . . . it keeps track of all your deductions so that you do less groaning on April 15! (Runs on the C-64 and Plus/4.)

Also, in March, "Hi Res Painter" will let the artist in you create a masterpiece on your VIC screen. Plus, March **ReRUN** offers challenging, fun-filled games like "Quatro" and "Fly The Grand Canyon".

Your quarterly comes with a complete booklet of documentation and loading instructions. The hard work has already been done. All you do is load, run, and enjoy!

Order your March **ReRUN** on cassette for **just $11.47**,** or on disk for **just $21.47.** Simply return the coupon today, or call **TOLL FREE 1-800-258-5473.** In NH, dial 1-924-9471.

It can be just the beginning of more enjoyable, relaxing programming in 1985!


The Home User's
Jim Butterfield Previews Plus/4, C-16
The Home User's Guid
Program of the Month Computerized Calendar
Program of the Month— Print Your Screen

* Plus/4 programs are contained on the C-64 loader.
** Prices include postage and handling.

Commodore 64, VIC-20 & Plus/4 are registered trademarks of Commodore Business Machines, Inc.

I Want To Begin '85 With Great Programming!

Please send me the March issue of **ReRUN:**

( ) C-64 ( ) VIC-20
( ) Cassette ($11.47) ( ) Disk ($21.47)
( ) Check/MO ( ) AE ( ) VISA ( ) MC

Card # _____ Exp. Date _____

Signature _____

Name _____

Address _____

City _____ State _____ Zip _____

4-85

80 PINE STREET • PETERBOROUGH, NH 03458

the simplest, but I prefer to use the second.

The first one (Listing 2) uses the Basic Load command, but when a load is executed from a program, it is a load/run. After the loading procedure, a run is executed.

This means that your program has to set some kind of flag to check to see whether or not the Run command is the first one you typed in or the one from the Load routine. If it is from the Load routine, is it from the screen file or the color file? This gets complicated.

The second loader (Listing 3) uses the Kernal Load routine, doing all the necessary preparation for it in Basic. This routine does not execute a run, so no flags are necessary, and program flow is easier to keep up with.

The Pokes in both of them are to set the border and background colors to the value that was used when the graph was created. You may change this value in line 10 of the program. The Graph Maker program uses the second routine for Loading and Saving.

Line Explanations

Lines 10–120. Initialize some variables and prompt for the choice to create or load a graph.

Lines 130–200. Begin the defining of parameters for the graph.

Lines 210–250. Set up the loop to draw the bars after input is complete.

Lines 260–360. Subroutine called from line 140 to further define parameters and input the data.

Lines 370–430. Subroutine that centers the titles for each bar.

Lines 460–550. Do the actual drawing of the bars from previously defined strings and such.

Lines 560–780. Subroutine called from line 140 to set up the strings for this particular graph.

Lines 790–890. Loop that presents the flashing prompt and processes the choice of options.

Lines 900–1020. Assemble the filenames for the two files under which a particular screen will be saved.

Lines 1030–1080. Called by the Save and Load routines to prepare for calling the Kernal Save and Load routines.

Lines 1090–1140. Finish the preparation for Saving the two files.

Lines 1150–1220. Input the filename of a graph to be loaded and finish the setup to load both files.

Lines 1230–1430. Form the Text routine that allows you to add text to a screen that has been created.

Lines 1440–1570. Form the Printer Dump routine to allow a hardcopy to be made of a screen.

Lines 1580–1650. Read the disk error channel when an attempt to load or save has been made. If an error has occurred, the error will be flashed at the bottom of the screen along with a "press any key to continue" prompt.

Some Fine Distinctions

I think you will be happy with the high-quality graphs that this program generates. It has the ability to make very fine distinctions, since it can resolve about 160 gradations in the vertical direction, which is one pixel of the 64's screen. Also, the Text mode gives you the freedom to customize the final result to suit your needs and wishes.

While Graph Maker is an excellent program for business needs, you can also use it for comparative analysis of nonbusiness applications, such as utility bills, grades at school, commodities pricing and even ages of family members.

I have included REM statements to title each subroutine and give you a brief description of the program.

Finally, if you don't have the time or inclination to type in the program, I can supply all three programs on tape for $5, or on disk for $8, to cover costs; or, if you just want to ask a question, feel free to write me (include a self-addressed stamped envelope for a reply). R

Address all author correspondence to Doug Smoak, 303 Heyward St., Columbia, SC 29201.

Listing 1 continued.

```
42Ø MR$="":FORJ=1TOMR:C$="{CRSR RT}"+C$:NEX
    T:T$(I)=C$+T$(I):C$="":RETURN
43Ø :
44Ø REM ** CHART ROUTINE**
45Ø :
46Ø IFV<LIANDV(C)>ØTHENFR=1:GOTO48Ø
47Ø IFV>ØTHENBL=INT(V/BI):F=V-BL*BI:FR=INT(
    F/LI)
48Ø CC$=LEFT$(OV$,CC)
49Ø PRINTDN$"{COMD 5}{2 CRSR DNs}"CC$T$(C);
5ØØ PRINT"{HOME}"CL$(CAND7)
51Ø PRINTDN$CC$;:IFBL=ØTHEN53Ø
52Ø FORI=1TOBL:PRINTCL$;:NEXT
53Ø IFFR>ØTHENPRINTFR$(FR)
54Ø CC=CC+BW:BL=Ø:FR=Ø:RETURN
55Ø :
56Ø REM ** SET UP STRINGS **
57Ø :
58Ø MX$=STR$(MX):MX$=RIGHT$(MX$,LEN(MX$)-1)
59Ø MX$=LEFT$(MX$,3):J=3-LEN(MX$):IFJ=ØTHEN
    61Ø
6ØØ FORI=1TOJ:M$=" "+M$:NEXT:MX$=M$+MX$:M$=
    ""
61Ø HF=1ØØ*MX:HF=INT(HF/2):HF=HF/1ØØ:HF$=ST
    R$(HF)
62Ø HF$=RIGHT$(HF$,LEN(HF$)-1):HF$=LEFT$(HF
    $,3)
63Ø J=3-LEN(HF$):IFJ=ØTHEN65Ø
64Ø FORI=1TOJ:M$=M$+" ":NEXT:HF$=M$+HF$:M$=
    ""
65Ø IFVAL(HF$)>VAL(MX$)THENHF$=LEFT$(" "+HF
    $,3)
66Ø MX$="{HOME}{2 CRSR DNs}"+MX$+"{1Ø CRSR
    DNs}{3 CRSR LFs}"+HF$
67Ø GR$="{SHFT -}{CRSR DN}{CRSR LF}{COMD Q}
    {CRSR DN}{CRSR LF}":FORI=1TO4:C$=C$+GR$
    :NEXT:C$=C$
68Ø C$="{COMD 5}{SHFT CLR}{2 CRSR DNs}{3 CR
    SR RTs}{COMD Q}{CRSR DN}{CRSR LF}"+C$
69Ø FORI=1TO5:C$=C$+GR$:NEXT:GR$=C$+"{SHFT
    -}{CRSR LF}{CRSR DN}":C$=""
7ØØ GR$=GR$+"{CRSR LF}Ø{COMD Z}{36 SHFT *s}
    {HOME}"
71Ø FORI=1TOBW:C$=C$+" ":NEXT:CL$=C$:C$=""
72Ø FORI=1TOBW:C$=C$+"{CRSR LF}":NEXT:CL$="
    {CTRL 9}"+CL$+C$+"{CRSR UP}{CTRL Ø}":C$
    =""
73Ø FR$="{COMD @}{COMD P}{COMD O}{COMD I}{C
    OMD U}{COMD Y}{COMD T}":FORI=1TO7:FR$(I
    )=MID$(FR$,I,1)
74Ø IFI>4THENFR$(I)="{CTRL 9}"+FR$(I)+"{CTR
    L Ø}"
75Ø NEXT
76Ø FORI=1TO7:FORJ=1TOBW:F$=F$+FR$(I):NEXTJ
    :FR$(I)=F$:F$="":NEXTI
77Ø RETURN
78Ø :
79Ø REM** INPUT FOR S/L,TITLE ,ETC.**
8ØØ :
81Ø PRINTDN$"{COMD 5}{3 CRSR DNs}{2 CRSR RT
    s}<T>EXT <S>AVE <A>BORT <L>OAD <P>RINT{
```

→

Listing 1 continued.

```
    HOME}":FORT=1TO8ØØ:NEXT
82Ø GETG$:IFG$<>""THENPRINTBL$:GOTO84Ø
83Ø PRINTBL$:FORT=1TO125:NEXT:GOTO81Ø
84Ø IFG$="A"THENRUN
85Ø IFG$="L"THEN117Ø
86Ø IFG$="T"THEN125Ø
87Ø IFG$="P"THEN146Ø
88Ø IFG$<>"S"THEN81Ø
89Ø :
9ØØ REM ** GET SAVE FILENAME **
91Ø :
92Ø F$="":PRINTDN$"{3 CRSR DNs}FILENAME? {C
    OMD +}{CRSR LF}";
93Ø GETG$:ON-(G$="")GOTO93Ø
94Ø IFASC(G$)>31ANDASC(G$)<96THENF$=F$+G$
95Ø IFG$<>CHR$(13)THENPRINT" {CRSR LF}"G$"{
    COMD +}{CRSR LF}";:GOTO93Ø
96Ø PRINTBL$:IFF$=""THEN81Ø
97Ø IFLEN(F$)>14THEN92Ø
98Ø F$(1)=F$:F$(2)=F$+".C"
99Ø OP$="S":FORJ=1TO2:F$=F$(J)
1ØØØ S=S(J):E=E(J)
1Ø1Ø GOSUB1Ø5Ø:NEXT:GOSUB16ØØ:GOTO81Ø
1Ø2Ø :
1Ø3Ø REM ** SAVE AND LOAD**
1Ø4Ø :
1Ø5Ø FORI=1TOLEN(F$):POKE819+I,ASC(MID$(F$,
    I,1)):NEXT
1Ø6Ø POKE183,LEN(F$):POKE187,52:POKE188,3:P
    OKE186,8:POKE185,1
1Ø7Ø IFOP$="L"THEN121Ø
1Ø8Ø :
1Ø9Ø REM ** SAVE **
11ØØ :
111Ø SH=INT(S/256):SL=S-SH*256:EH=INT(E/256
    ):EL=E-EH*256
112Ø POKE251,SL:POKE252,SH:POKE78Ø,251:POKE
    781,EL:POKE782,EH
113Ø SYS65496:RETURN
114Ø :
115Ø REM ** LOAD **
116Ø :
117Ø INPUT"{SHFT CLR}{CRSR DN}{CRSR RT}EXAC
    T FILENAME";F$:IFF$=""ORLEN(F$)>14THEN
    117Ø
118Ø F$(1)=F$:F$(2)=F$+".C"
119Ø FORJ=1TO2:F$=F$(J):OP$="L":GOSUB1Ø5Ø
12ØØ NEXT:GOSUB16ØØ:GOTO81Ø
121Ø POKE78Ø,Ø:SYS65493:RETURN
122Ø :
123Ø REM ** CURSOR ROUTINE **
124Ø :
125Ø SC=1Ø24:CR=55296
126Ø IFIN<ØTHENIN=Ø
127Ø IFIN>959THENIN=959
128Ø OM=PEEK(SC+IN):OC=PEEK(CR+IN)
129Ø POKESC+IN,(PEEK(SC+IN)+128)AND255:POKE
    CR+IN,PEEK(646)
13ØØ GETG$:ON-(G$="")GOTO129Ø
131Ø IFG$="{LB.}"THENGOSUB141Ø:GOTO81Ø
132Ø IFG$="{SHFT INST}"ORG$="THENG$="{SHFT
    -}"
133Ø IFG$=CHR$(13)THENOM=(OM+128)AND255:GOS
    UB141Ø:IN=IN+1:GOTO126Ø
134Ø IFG$="{CRSR RT}"THENGOSUB141Ø:IN=(IN+1
    ):GOTO126Ø
135Ø IFG$="{CRSR LF}"THENGOSUB141Ø:IN=(IN-1
    ):GOTO126Ø
136Ø IFG$="{CRSR UP}"THENGOSUB141Ø:IN=(IN-4
    Ø):GOTO126Ø
137Ø IFG$="{CRSR DN}"THENGOSUB141Ø:IN=(IN+4
    Ø):GOTO126Ø
138Ø SP=IN:GOSUB142Ø:PRINTG$
139Ø IFASC(G$)>31ANDASC(G$)<128THENIN=IN+1
14ØØ GOTO126Ø
141Ø POKESC+IN,OM:POKECR+IN,OC:RETURN
142Ø Y=INT(SP/4Ø):X=SP-4Ø*Y:POKE781,Y:POKE7
    82,X:SYS6552Ø:RETURN
143Ø :
144Ø REM ** PRINTER DUMP **
145Ø :
146Ø R$=CHR$(145):V$=CHR$(146):OPEN4,4:CMD4
    :G=PEEK(648)*256
147Ø PRINTR$+CHR$(14);
148Ø FORP=GTOG+999
149Ø C=PEEK(P):C$=""
15ØØ IF(P-G)/4Ø=INT((P-G)/4Ø)THENPRINTCHR$(
    8)+CHR$(13)+CHR$(14);
151Ø IFC>128THENC=C-128:C$=CHR$(18)
152Ø IFC<32ORC>95THENC=C+64:GOTO154Ø
153Ø IFC>63ANDC<96THENC=C+128
154Ø C$=C$+CHR$(C):IFLEN(C$)>1THENC$=C$+V$+
    R$
155Ø PRINTC$;:NEXT:PRINT#4:CLOSE4
156Ø GOTO81Ø
157Ø :
158Ø REM ** READ DISK ERROR CH **
159Ø :
16ØØ OPEN15,8,15:INPUT#15,A,B$,C,D
161Ø CLOSE15
162Ø IFA=ØTHENRETURN
163Ø PRINTBL$DN$"{3 CRSR DNs}{2 CRSR RTs}"A
    "{CRSR LF} "B$" ERROR{HOME}":FORT=1TO8
    5Ø:NEXT
164Ø GETG$:IFG$<>""THENRETURN
165Ø PRINTDN$"{3 CRSR DNs}{2 CRSR RTs}PRESS
     ANY KEY TO CONTINUE{HOME}":FORT=1TO85
    Ø:NEXT:GOTO163Ø
```

Listing 2. *Graph Maker loader #1.*

```
5 REM LOADER #1 GRAPHMAKER-SMOAK
1Ø IF A=1THEN6Ø
2Ø IF A=2THEN4Ø
3Ø PRINT"{SHFT CLR}FIRST TIME THRU"
4Ø INPUT"{HOME}{CRSR DN}{CRSR RT}FILENAME";
   F$:F$(1)=F$:F$(2)=F$+".C"
5Ø A=1:LOADF$(2),8,1
6Ø POKE5328Ø,PEEK(56296)
7Ø POKE53281,PEEK(56296)
8Ø A=2:LOADF$(1),8,1
```

Listing 3. *Graph Maker loader #2.*

```
5ØØØØ REM ** LOAD SUBROUTINE{4 SPACEs}**
5ØØ1Ø :
5ØØ2Ø REM ** (C) 1984 BY D. SMOAK **
5ØØ3Ø :
5ØØ4Ø INPUT"{SHFT CLR}{CRSR DN}{CRSR RT}EXA
    CT FILENAME";F$:IFF$=""ORLEN(F$)>14TH
    EN5ØØ4Ø
5ØØ5Ø F$(2)=F$:F$(1)=F$+".C"
5ØØ6Ø FORJ=1TO2:F$=F$(J)
5ØØ7Ø IFJ=2THENCL=PEEK(56296):POKE5328Ø,CL:
    POKE53281,CL
5ØØ8Ø FORI=1TO LEN(F$):POKE819+I,ASC(MID$(F
    $,I,1)):NEXT
5ØØ9Ø POKE183,LEN(F$):POKE187,52:POKE188,3:
    POKE186,8:POKE185,1
5Ø1ØØ POKE78Ø,Ø:SYS65493:NEXTJ
5Ø11Ø REM** RETURN (IF CALLED BY GOSUB){2 S
    PACEs}**
```

Circle 124 on Reader Service card.

BEAT the SAT®

The most complete program of study your money can buy.Includes comprehensive reviews for the verbal and math modules, thousands of questions,practice SATs,and much more.Your insurance for good scores in the SAT.(Disk for the 64)

FOR ONLY $39.95

CPA - 64®

This up to date program is the creation of CPAs and Tax experts.The CPA-64 will take care of the endless list of ''what ifs'' and deductions.Handles all forms:1040;2441,Schedules A,B,C,D,E,G and W. (D)

FOR ONLY $24.95

Special offer..... BEAT the SAT and also CPA-64 plus a free SuperCloner backup®

ONLY $59.95

Check or M.O.
Free CODs and
Shipping & Handling
2 to 10 days delivery

Write to:
GOOD GUY's
St.12 N.O. 1378
PuertoNuevo PR 00920

Circle 176 on Reader Service card.

COOL STACK

DESIGNED FOR USE WITH COMMODORE 1541 DISK DRIVES

PATENT PENDING

COOL STACK is a device that allows you to stack your 1541's without fear of overheating. Our tests indicate that with ***COOL STACK,*** both top and bottom drives operate 30 to 38% cooler than a standard non-externally cooled drive. Highly efficient design effectively cools two drives using one fan. This system allows better utilization of the limited space available on most computer desks.

Top quality materials include: High volume (55 CFM) low rpm (1800), super quiet (18 DB) axial fan, and cabinet is made of solid oak.

COOL STACK is built to last and prices at only $59.00

Carbo Tech products are assembled in the USA

Visa, Mastercard, Check, or Money Order
Georgia residents add 3% sales tax
Shipping and handling within US add $5.00
Canadian orders in US dollars only
Shipping and handling to Canada $2.00 plus applicable freight charges.
Test data available on request

Clamp on Desk Lamp pictured above priced at only $35.00 includes shipping and handling in USA

Commodore 1541 is a trademark of Commodore Business Machines

Call or write today AC 404-979-6124

CARBO TECH INCORPORATED

P.O. BOX 652—SNELLVILLE, GEORGIA 30278—404-979-6124

Circle 193 on Reader Service card.

We'll Have the New Advanced Commodore Products 1st!!

NEW PRODUCTS! LOW PRICES!

Call for information on new products . . .
CATALOGS: Free on written request.

NEW from STAR MICRONICS:
Everything the Gemini 10X was and more!

SG10 PRINTER
2K Buffer
NLQ Mode
CALL!

PRINTERS

Powertype Daisywheel 18 CPS with Cardco B	$354	**Epson RX 80** with Tymac Connection	$299
Okidata 92 160 CPS with Tymac Connection	429	**DPS 1101** Daisywheel Direct Connect to C64	Call
Commodore MPS 802	Call	**Riteman C+** NEW	Call
Okidata 182 NEW	Call	**MW-350 Interface** NEW	Call

SPECIAL • **PRINT SHOP** ..... $32.00 • *SPECIAL*

DISK DRIVES

MSD Super Drive	Call	**Commodore 1541**	Call
Indus GT	Call	**Phonemark Datasette**	$29
Epyx Fast Load	$27		

COMPUSERVE STARTER KIT AND VIDTEX
Get both for only . . . **$39.95**

MODEMS

Westridge 6420	Call
Mighty Mo	Call
VIP Terminal	$35
Commodore 1660	59

MONITORS

Teknika MJ10	$239	**Zenith ZVM** Gr/Amb	$89/99
Commodore 1702	Call		

DATABASE MANGERS

The Consultant	$62	**PFS:File**	$59
Super Base 64	49	**PFS:Report**	49
The Manager	35		

WORD PROCESSORS

Paper Clip/& speller	$59/79	**Easy Script**	$35
Fleet System 2 NEW	Call	**Easy Spell**	17

SPREADSHEETS

Calc Result Easy/Adv	$25/49	**MuiltiPlan**	65

XIDEX SS/DD PRECISION DISKETTES
Lifetime Warranty **$13.00**
STORE THEM IN DATACASE 50 .. **$10.00**

ACCESSORIES

Com Cool Drive Fan	$49	**Power Pak**	$27
Com Cool Plus w/ surge	$69	**Surge Protector** 4-Plug	27

BLACK NAUGAHYDE COVERS

ORDER ANY 4 OR MORE COVERS AND HAVE THEM SHIPPED FREE!!!

C-64 or 1541 Drive	ea. $5	**1702 Monitor**	$10
MSD Drives 1/2	5/6	**1525/MPS 801**	7
Gemini 10X	9	**1526/MPS 802**	8

MOST ORDERS SHIPPED WITHIN 48 HOURS! Advertised prices are for bank check or money order. VISA/MC orders add 3.5%. NO C.O.D ORDERS. Personal or company checks delay orders 21 days. All sales are final – defective merchandise exchanged for same product only. Add 3% for shipping ($2.50 min.) Please call for shipping on monitors. Ohio residents add 5.5% sales tax. Prices & availability subject to change.

HOURS: MON-FRI 10 AM to 10 PM • SAT 10 AM to 5 PM • SUN Noon to 5 PM

800-638-2617

INFORMATION & IN OHIO 216/758-0009

BIG BYTES

1301 BOARDMAN-POLAND ROAD POLAND, OHIO 44514

A User's Castle

Blueprint for a Computer Sanctuary

By JIM STEPHENS

A room of one's own—quiet, spacious and light—is what every Commodore user really needs, and this article describes how to build one.

Now that you've finally acquired all your computer components and have decided that you're serious about programming, you need a suitable place to work. A well-designed computer area is as important as the keyboard console, yet it's a component rarely mentioned in the list of needed peripherals.

I designed and built my own computer room, but not without a great deal of trial and error (lots of error). I could have avoided these errors had I known then what I know now.

If I'd known that my little Commodore 64 keyboard and portable TV were only the small beginning of a long list of components that would eventually be necessary, I never would have tried to work on the dining room table.

I couldn't blame my wife for hating computers, especially since she had to fight for table space to serve dinner. I fought bravely, but finally surrendered and moved to the den. What she didn't know was that my new disk drive needed another outlet and my books needed more space. The den seemed like a great idea at the time, but was I ever wrong!



Figure 1. *Plan view of computer room design.*

My reference library grew amazingly fast, and with the addition of a printer, I needed still more space and another outlet.

When "hacking," a true programmer has a tendency to spread out. That is, things have a habit of migrating outward. Open magazines, note sheets and printouts seem to explode into every available space, including the floor.

A bigger desk and furniture rearranging were necessary, so I thought. I mean, you can't have your system just anywhere, right? However, more serious problems developed.

Shhh...Be Quiet

Our den has the family television, the kids, the dog, others' kids, the telephone and a noise level like downtown at rush hour. My constant screams of "pipe down, daddy's working" only seemed to add to the confusion. The kids couldn't laugh at the Saturday morning cartoons (at least not aloud) and the telephone had to be dragged into the next room for all use.

The noise level appeared to double when I tried to find out why a program wouldn't run. This is one phenomenon that I've never fully understood, but there's probably a scientific law—for every mistake in a program, there is an equal and proportional increase in bedlam.

I found that I was constantly waiting for a television commercial, so I could hit the print key. I'd then pray that the printer would finish the listing before

the TV program returned. I got rather good at terminating the listing before everyone started yelling. Eventually, something had to go, and, of course, I lost.

My Own Space

The basement was the last unused space in the house but I just *couldn't* put my beautiful system in that cold, dark, damp "dungeon." I once left an old pair of boots down there, only to find they'd turned green and withered away.

I agonized for days, until my brother, a master carpenter, suggested we build a custom environment for my unloved and unwanted "child." He saw right away from my existing work space that it would cost very little to finish out the area I would need. He noted that my scrap material alone would be enough to frame a small room. We listed each environmental item that's necessary for proper programming and found that there was a way to control these to any standard.

My greatest fear was mildew, which is caused by moisture, a lack of ventilation and a difference in temperature between the air and the surfaces. This could be easily handled by a small thermostatically controlled heater and a vent fan.

Lighting would be done with two small ceiling-hung fluorescent tubes, and the space could be framed and insulated well to maintain the heating (or cooling). This insulation would also act somewhat as a buffer against sound.

I would only need about sixty-four square feet of floor space, and by using a corner of the basement, we would only have to frame two walls.

A week and three mashed fingers later, my brother and I completed a small, well-designed computer room. The following description highlights some of the more important factors involved in designing a room—whether you build in an attic, an unused bedroom or a garage.

Design and Build Upward

Building materials cost a fortune. I could not work in a hardware store and sleep at night. Just one 2 × 4 eight-foot piece of wood costs more than most people make an hour. Therefore, we held the floor space to a minimum.

I learned there were places that sell "seconds." A second is a piece of wood that is not exactly straight, smooth or whatever. It costs about half as much as one that is. We used only seconds and saved a bundle.

Since floor space was minimal, we built upward. Figure 1 shows that most of the space is countertop ($^5/_8$-inch plywood. Shelving is used for storing all computer-related materials, and the countertop is reserved entirely for the hardware and writing surface. Even the disk drive is placed under the counter to conserve space. The printer is elevated so you may place its paper supply under it. Access holes were drilled into the counter to eliminate the tangle of wires that take up valuable space on the counter.

> I couldn't blame my wife for hating computers, since she had to fight for table space to serve dinner.

The space was divided into three areas: work, keyboard and printing. Since I do a lot of hardware interfacing work, a small area of the counter was reserved for tinkering. This area is higher, with an ample supply of shelving above and below.

Electrical power is supplied by three separate circuits; one line powers all the computer equipment; one is used entirely for the lights, general outlets and the ventilating fan; a separate circuit (210 volts, in my case) powers the heater. I hope someday to connect a small air conditioner to this circuit, too.

Make sure that the circuit you use for your computer's power supply is not one that already has large motor-type appliances, such as the refrigerator or washer, on it. The sudden drop in voltage that occurs when these motors start up causes terrible things to happen to your system. The motors also have a tendency to cause your display to show hash lines. You turn on your computer's power by flicking a wall switch, but you must turn each component on and off individually, since the disk drive and printer should be on before the computer.

The layout of your room will largely be determined by the space in which you build. The general layout should remain basically the same, however. If you are one of the few who has a quiet study, an extra bedroom or a finished basement, you'll only need a well-designed desk or work surface.

The Work Surface

Don't buy a ready-made desk until you know how much material (and peripherals) you will ultimately have. Above all, don't buy one of those desks that places the monitor some 14 inches above the keyboard. The strain on your neck will half kill you. Keep the monitor at or slightly below eye level. If you want to save some money, build your own work counter.

Figures 1 and 2 provide you with all the necessary dimensions. The heights are selected to provide the greatest comfort for both typing and writing. Before I built my new work surface, I did most of my writing by holding the paper in my lap.

My work surface was laminated with Formica and edged with $^5/_8$-inch plastic edge strips. You can use any smooth material. I think linoleum would make a great surface—it worked just fine when I did my homework on the floor as a child.

Wiring and Lighting

Lighting becomes an important factor when you work with your eyes for any extended amount of time. My space uses two separate fluorescent ceiling fixtures, both mounted slightly behind me. If the lights are placed in front of you, they tend to glare and reflect off surfaces, especially the keys on the keyboard. You can also mount an incandescent lamp, with a soft glow, on your wall for reading. I don't recommend using many incandescent lights, however, because of the heat build-up.

Notice that the light switch is by the door; this saves poking around in a dark room, looking for the wall switch. This switch should control only the fluorescent lights; the wall outlets should not be switched. The six-outlet bank for the computer's power is an exception.



Figure 2. *Elevation view of desk and shelf arrangement.*



Figure 3. *Electrical circuits plan.*

Figure 3 shows how these circuits are connected. Since 110 volts can be deadly, the wiring should only be done by one skilled in home wiring.

General Construction Techniques

We used standard interior wall construction techniques. However, if you're going to build in an unheated area, you must use insulation. You can heat the area with a very small wall heater or a plug-in space heater, which I don't recommend. A lack of heat makes an area dreary and lets moisture accumulate, and moisture is a deadly enemy of computer equipment. Besides insulating the room, we even added polyethylene sheets to all four walls, as a moisture barrier.

We found that the insulation boards worked beautifully for the insulation of the raised floor and the wall adjacent to the concrete block, It has an even greater insulating value than roll fiberglass, which is twice as thick.

We paneled the room with Masonite paneling, since it is made with no formaldehyde-containing glue. In a small space, you can easily be bothered by fumes emitted by certain materials. Avoid breathing sawdust from the Masonite, since it's sometimes made from redwood or red cedar, which can cause allergic reactions. We painted the paneling off-white to increase light reflection. The ceiling was simply painted insulation board, "scored" in squares to resemble ceiling tile.

The area of the basement in which we built the room had several runs of water pipe. This was a serious detraction, which almost led to their rerouting. I felt, however, that this replumbing would certainly turn to disaster, and chose to paint each pipe with its own bright enamel color. The colors add something to the area, and I've thanked myself a hundred times for this decision.

Because I was constantly running upstairs to answer the phone, I added a small wall phone for convenience. It has a small "chirper" for a bell and works great. The kids have figured out how to buzz me on it to settle their arguments. It seems I'll never escape. R

Address all author correspondence to Jim Stephens, 2324 Dennywood Drive, Nashville, TN 37214.

Circle 60 on Reader Service card.

ATTENTION

Foreign Computer Stores
Magazine Dealers

You have a large technical audience that speaks English and is in need of the kind of microcomputer information that CW/Peterborough provides.

Provide your audience with the magazine they need and make money at the same time.

For details on selling **80 MICRO, inCider, HOT CoCo, RUN** contact:

SANDRA JOSEPH
WORLD WIDE MEDIA
386 PARK AVE., SOUTH
NEW YORK, NY 10016
PHONE (212) 686-1520
TELEX—620430

Attention Subscribers

We occasionally make our mailing list available to other companies or organizations with products or services which we feel might be of interest to you. If you prefer that your name be deleted from such a list, please fill out the coupon below or affix a copy of your mailing label and mail it to:

CW Communications/Peterborough
RUN
PO Box 954
Farmingdale, NY 11737

Please delete my name from mailing lists sent to other companies or organizations. RUN

Name _____
Address _____
City _____ State _____ Zip _____

LIGHT YEARS AHEAD

WE GUARANTEE IT!

We feel that our products are the best on the market, and we are so sure you will think so also that we offer a 30 day money back guarantee.

PRINTMASTER/+G with IntelliFeatures™ PARALLEL PRINTER INTERFACE

This is the most advanced printer interface on the market at any price. The Printmaster/+G supports all Commodore printer commands. Prints graphics and graphics characters on all popular printers. Complete switch selection. Transparent, Emulation, Hex, List, and Lock modes. Cassette port powered. Also has external power jack. Prints enhanced graphics. And that's just the start. **Intellifeatures™ give you advanced features found in no other printer interface.** Printmaster ROM based routines can load from the Printmaster into the computer. Display the disk directory on the screen without destroying your BASIC program. Machine language terminal software loads in less than 4 seconds. ASCII/Speedscript file conversion. The Printmaster can also operate by itself. Print an ASCII diskfile directly from the disk to the printer without going thru the computer. Also comes with **Hi-res screen print** and **Banner** print programs on disk. **Optional user installable 16K or 32K printer buffer** also contains a ROM which adds many other advanced features such as printing a BASIC program from disk without going through the computer. Disassembles and prints machine language also. Many, many more features. All this and more.

Catalog #10-115 **Printmaster/+G Parallel Printer Interface** **$119.95**
Catalog #10-116 **Printmaster 16K Buffer Expansion** **$69.95**
Catalog #10-117 **Printmaster 32K Buffer Expansion** **$89.95**

DELUXE RS232 INTERFACE

The most versatile RS232 Interface on the market. Supports full RS232 signal set including Ring Detect. Switch selectable for DTE/DCE, and Busy Line polarity. No other RS232 interface currently offered has all these selections. Easy to use. Good Documentation. Comes with it's own 3 foot cable with either a male or female DB25. Type in BASIC terminal routine, program transfer routine, and more. For Male DB25 order 10-112. Female order 10-113. **$44.95**

ALSO FROM OMNITRONIX: CASSETTE INTERFACE 10-101: Use any cassette with 20/64. Make tape backups $34.95. **PRINTMASTER/U+G** 10-108: Economy parallel printer interface. Connects to the user port. Disk included contains machine language wedge which changes user port to parallel port. Does graphics. $39.95. RS232 **PRINTER ROUTINES** 10-109: Machine language software. Use RS232 printer with programs not designed for RS232 printer. Many features. $29.95. **VOLKSMODEM CABLE** 10-103: Connect Volksmodem to a Commodore. No other interface needed. $22.95.

HOW TO ORDER: See your local dealer or call **206/236-2983** or write to address below. Phone orders ask for $1.00 discount. Mail/Phone orders add $2.00 shipping for each product. COD add $1.90. 30 Day money back guarantee (less shipping). **VISA & MASTERCARD Welcome.** Call, write, or mark the reader service card for a free catalog.

Omnitronix

PO BOX 43 DEPT. R4
MERCER IS., WA 98040
206/236-2983 DLRS/DIST CALL

VISA
MasterCard

Gateway to the World

By JIM GRUBBS

Before you connect your Commodore computer to the outside world, you should be aware of its capabilities and limitations. This article examines these and gives you a small project to start you on your way to controlling the user port.

Before beginning an exercise program, you are advised to get a physical checkup. Through an examination, you gain advice on just how much exercise you should attempt. Some of us don't listen to the doctor or, worse yet, never even ask for the doctor's advice. What often results are sprained ankles, bad backs, and sometimes broken arms and legs or even more serious maladies.

Before you progress any further in connecting your Commodore computer to the outside world, let's go to the doctor and find out just how fit Messrs. VIC and 64 are, and what medical problems could occur if you try to overtax their abilities. Finally, you will put this information to work to control something of your own choosing. I'll show you how!

The VIC and 64 are amazingly versatile machines. The more that I have learned about other computers, the more I come to appreciate the connections that Commodore has made available to us as a part of the base price of the computer. In making these connections available, however, a minimal amount of protection has been included, making connection to the different gateways on your machine a bit on the delicate side. Abuse of these connections can result in anything from a blown internal fuse to damage to all of the integrated circuits that make your computer tick.

Power Supplies

A computer's fuel, or energy, comes from the power supply. There are several different versions of VIC and C-64 power supplies.

Early VICs used a small black transformer that powered the computer through a two-pin plug. C-64s use a DIN plug that is connected to a much larger external power supply unit. Newer VICs have adopted the larger transformer but still use a two-pin plug. A larger power supply box was needed in order to fit the electronics of the C-64 into the same case used for the VIC.

The external power boxes tend to get quite warm. If you are particularly safety conscious, you might want to *unplug* the power unit when the computer is not being used. (Just turning off the computer does not turn off the power supply!) My own experience, however, is that leaving the units plugged in and operating continuously does not cause problems.

Your computer's power circuitry supplies several different voltages. One of the voltages made available on both the user port and the joystick port is +5 V dc. When dealing with power sources, not only is it necessary to have the proper voltage, but the voltage source (in this case your power supply) must be able to supply the total amount of power that is going to be consumed by the circuit. This means that you must consider the current being drawn by your device.

Ohm's law says that power is equal to voltage multiplied by current. To return to the human analogy, you may be able to lift a 100-pound weight, but you must also consider how long you can hold it. Equate the weight to the voltage level and the endurance element to the current. If you try to hold up the weight for too long, you'll either drop it or collapse under the pressure.

Your computer's user manual warns you that although the 5-volt dc voltage is available, the amount of current is limited to 100 milliamperes (mA). That is *not* very much! Many of today's low-power integrated circuits use as little as 5 mA each, so it is still possible to power peripherals such as the VICModem directly from this connection. You must, however, keep the limit in mind when using your computer to drive an external device.

Now that you have a bit of background on your machine's life source, it's time to head for the doctor's office.

The Examination

In phase 1 of the Commodore doctor's examination, you are warned not to overexert the 5-volt dc power source. This cannot be stressed enough. On to the next test.

The signals available from the user port are called TTL-level signals. TTL (transistor-transistor logic) refers to a certain type of integrated circuit technology. In theory, a +5 V signal represents a logic 1, while zero volts represents a logic 0.

In actual practice, most logic 1 signals will measure between about 3.5 and 4.5 volts. The logic 0 signals will be near, but not actually at, 0 volts.

If you plan to use any of the signals from your computer, be careful not to connect anything that will require too much current.

As the doctor examines VIC and 64, he tells us that the output signals from them are real weaklings! In technical terms, these signals are capable of connection to only one TTL connection. That isn't very much—certainly not enough to drive a mechanical relay, for example.

The reason for this is fairly simple. Each of your computer's integrated cir-

BACK ISSUES

April 1984—The world of music. Hypnosis and the C-64, plus Disk Editor 64 program

May 1984—Database programs reviewed. Dragon Quest action game for the VIC, Music Maker program, and a behind-the-scenes look at Commodore

June 1984—The Joy of Modems. C-64 disk utility program, 64 Joystick Artist, and Munchin' Mushrooms game

July 1984—Softball Stats program, Commodore in the Hamshack, Morse code program, and Lost in Space game. Playing the ponies with your VIC

August 1984—Sprite utility program, Battleship War and Buried Treasure game

September 1984—Education issue. Over 40 educational programs reviewed. What to look for in a terminal program. Demystify your listings. A detective and his Commodore

October 1984—Languages issue: Comal, Logo, Pascal, Pilot and Fortran. SID Serenade, a sprite editor, and a murder mystery game

November 1984—A look at the Plus/4 and C-16, Buyer's Guide to Hardware, printer interfaces examined, Datafile program

December 1984—Trivia craze, Software Buyer's Guide, and Plus/4's word processor

Special Issue—Over 500 Magic tricks. Articles to get you up and running with your Commodore, glossary, club's list and reference poster.

January 1985—Create Your Own Games. How to select the right printer. Valuable disk tips for beginners.

February 1985—Joysticks: which ones to buy and how to use them in your own programs. Learn how to start a Commodore user's group. Fly the Grand Canyon with your VIC.

March 1985—Shape Up with Your C-64: reviews of fitness and nutrition programs. Mini-Calc spreadsheet and Money Manager programs. Word processors reviewed.

RUN

Each month RUN also brings you regular columns, reviews, programs and tutorials to help you get the most enjoyment and use out of your Commodore system.

Each back issue costs $3.50 plus $1 for shipping and handling. On orders of 10 or more back issues, there is a flat $7.50 shipping and handling fee. Quantities are limited and we cannot guarantee that all back issues are available. Send your orders to *RUN*, Attn: Back Issue Orders, 80 Pine St., Peterborough, N.H. 03458.

Circle 345 on Reader Service card

DOUBLES DISK CAPACITY!

Cuts Your Cost 50%!
Now! The back of 5¼" diskettes can be used for data storage even with single head disk drives.
- *NIBBLE NOTCH* makes it easy
- Adds the notch needed.
- SATISFACTION OR MONEY BACK.

NIBBLE NOTCH I
Cuts square notch for Apple, II, II+, IIe, IIc, III, Franklin and Commodore.
only **$14.95***
*add $2.00 each order ($5.00 foreign)
For Postage and Handling
Florida Residents Add 5% Sales Tax

ORDER TODAY!
Toll Free 1-800-642-2536
VISA
FLORIDA: 1-305-493-8355
OR SEND CHECK OR MONEY ORDER TO:
MasterCard
NIBBLE NOTCH® COMPUTER PRODUCTS
4211 NW 75th TERRACE, • DEPT. 116
LAUDERHILL, FL 33319
PATENTED ALL TRADEMARKS ARE ACKNOWLEDGED

CONVERSE WITH YOUR COMPUTER
ELIZA-64
Artificial Intelligence Demonstration Program
BREAK from games and technical programs and AMAZE and INVOLVE your family and friends.
Eliza-64 is a Commodore 64 adaptation of the famous Eliza program developed at MIT. Eliza acts as a psychotherapist analyzing your input and responding with an appropriate comment or question.
GREAT FAMILY AND PARTY ENTERTAINMENT
NOW ONLY $19.95
Ohio residents add 5½% sales tax
Send check or money order to:
OMEGA-SOFT
P.O. BOX 3686
Mansfield, Ohio 44907
Disc or Cassette Machine Language Fast
(dealer inquiries invited)

Circle 287 on Reader Service card.

C-64 COPY!
COPY CLONE with Utilities **$19.95**
Copy protected disks in 5 min. or less • Copies most protected disks
Will not damage disk drive
Over 20 utilities, including
professional disk drive analysis
30 sec. formatting
sophisticated disk editor
POWER PLUS **$19.95**
Utility adds 40+ commands, doesn't use BASIC memory • 100% machine.
• SCREEN DUMP to printer • UN-NEW
• MACHINE LANG. MONITOR • Adds BASIC commands AUTO LINE NO., RENUMBER, FIND, CHANGE, DELETE, more.
20 ACTION GAMES **FREE**
When you order both programs
Send check or m.o. (include $2.00 p.h.) CA res. add 6% sales tax to: **EDUCOMP** 2139 Newcastle Ave., Cardiff, CA 92007 • **(619) 942-3838.**

Circle 254 on Reader Service card.

Software Discounters of America
(& Peripherals, too!)
S.D. of A.
For Orders Only 1-800-225-7638
Inquires and PA 412-361-5291 Open Saturday
•Free Shipping on orders over $100 in continental USA
•No surcharge for VISA/MASTERCARD

ACCESS		Hitchhiker's Guide to	
Beach Head (TorD)	$21	the Galaxy (D)	$23
Beach Head II (D)	$27	Infidel (D)	$27
Mach 4 (R)	Call	Planetfall	$23
Raid over Moscow (TorD)	$25	Seastalker	$23
ACTIVISION		Sorcerer	$27
Decathalon (D)	$21	Zork Series	Call
Ghostbusters (D)	$23	**KOALA**	
Space Shuttle (D)	$21	Muppet Learning Keys (D)	$49
ARTWORX		Tablet w/Painter (D)	$53
Bridge 4.0 (TorD)	$16	Tablet w/Painter (R)	$65
French (D)	$19	Koala Printer (D)	$19
Grand Master Chess (D)	$19	**MICROPROSE**	
Slap Shot Hockey (D)	$16	F-15 Strike Eagle (TorD)	$23
Strip Poker (D)	$21	Kennedy Approach (D)	$23
BRODERBUND		Solo Flight (TorD)	$23
Bank St. Writer (D)	$33	**MINDSCAPE**	
Castles Dr. Creep (D)	$21	Bank St. Story Book (D)	$27
Karateka (D)	$21	Indian Jones (D)	$21
Loderunner (D)	$21	**ORIGIN**	
Music Shop (D)	$29	Ultima III	$39
Print Shop (D)	$29	**PRECISION SOFTWARE**	
Print Shop Graphics Library	$19	Superbase 64	$49
Print Shop Paper Refills	$14	**SCARBOROUGH**	
Spelunker (D)	$21	Build A Book (D)	$27
Stealth (D)	$21	Mastertype (D)	$21
Whistler's Brother (D)	$21	Net Worth (D)	$49
CBS		Writing Wizard (D)	$27
Adv. Master (D)	$29	**SPINNAKER**	
Dinosaur Dig (D)	$27	All Titles	Call
Felony (D)	$23	**SSI**	
Math Series	Call	Battle Normandy (D)	$27
Mastering the SAT (D)	$89	Breakthrough in the Ardennes (D)	$39
Murder by Dozen (D)	$23	Carrier Force (D)	$39
CONTINENTAL		Computer QB (D)	$27
Book of Adv. Games	$16	Field of Fire (D)	$27
Home Accountant (D)	$47	Gemstone Warrior (D)	$23
Home Cataloger (D)	$33	Germany 1985 (D)	$39
CREATIVE		Kampfgruppe (D)	$39
Break Street (D)	$17	Pro Tour Golf (D)	$27
Easy Disk (D)	$21	Questron (D)	$27
I am the C64 (D)	$21	Ringside Seat (D)	$27
Trolls & Tribulations (D)	$19	**SUBLOGIC**	
DATASOFT		Flight Simulator II (T)	$29
Bruce Lee (T/D)	$23	Flight Simulator II (D)	$35
Conan (T/D)	$23	Night Mission Pinball (TorD)	$21
Dig Dug (T/D)	$19	**TIMEWORKS**	
Lost Tomb (T/D)	$19	Cave Word Wizard (D)	$23
Pac Man (T/D)	$19	Data Manager 2 (D)	$33
Pole Position (T/D)	$19	Word Writer w/Speller (D)	$33
DAVIDSON		**TRILLIUM**	
All Titles	Call	Amazon (D)	$23
ELECTRONIC ARTS		Dragonworld (D)	$23
All Titles	Call	Fahrenheit 451 (D)	$23
EPYX		Rendezvous w/Rama (D)	$23
Fast Load (R)	$25	Shadowkeep (D)	$23
Impossible Mission (D)	$23	**WINDHAM CLASSICS**	
Monty's Scrabble (D)	$27	Alice in Wonderland (D)	$19
Pitstop II (D)	$27	Swiss Family Robinson (D)	$19
Summer Games (D)	$25	Wizard of Oz (D)	$19
Summer Games II (D)	Call	**ACCESSORIES**	
FISHER PRICE		BASF SS,DD	$14 Bx
All Titles	Call	Compuserve Starter Kit (5 hrs.)	$23
GAMESTAR		Data Share Printer Int. w/Graphics	$44
On-Court Tennis (TorD)	$21	Disk Case (Holds 50)	$9
On-Field Football (TorD)	$21	Disk Drive Cleaner	$9
Star League Baseball (TorD)	$21	Indus GT Disk Drive	Call
HBJ		Total AA/AD Modem	Call
Computer SAT (D)	$49	Wico Boss	$12
HAYDEN			
Sargon III (D)	$33		
INFOCOM			
Enchanter (D)	$23		

P.O. Box 278-Dept. RN Wildwood, PA 15091

***Ordering and Terms:** Orders with cashier check or money order shipped immediately. Personal/company checks, allow 3 weeks clearance. No C.O.D.'s. **Shipping: Continental U.S.A.**—Orders under $100 add $3. **free shipping on orders over $100.** PA residents add 6% sales tax. **AK, HI, FPO-APO**—add $5 on all orders. **International Order Policy**—No Credit Cards—add $15 or 15% of order whichever is greatest. Defective merchandise will be replaced with same merchandise—NO CREDITS! Return must have authorization number (412) 361-5291. Prices subject to change without notice. **Order today, get it tomorrow. Overnight delivery is just $17.50—software orders only in Continental U.S.A.**

cuits consists of hundreds of transistors. Each transistor is microscopically small. Because the physical size of the junction in the transistor is so minute, it cannot dissipate much heat. This has a direct correlation to the amount of power (or current) that can be handled.

Some computers isolate their internal signals with a buffer, to protect the computer from damage by an external device. Such a buffer can also be used to increase the current capabilities. The signals on your Commodore are *not* buffered.

So, the doctor's final word on phase 2 is *be careful*. VIC and 64 signals are very weak and will tolerate no abuse. Doing so will probably result in a dead computer! The example circuit you will build (see Figure 1) shows how to properly buffer the output of your computer so such nasty things won't happen.

The next step in the examination involves signals coming into your computer from the outside world. An example is the positioning information transmitted from the switches in your joystick to the computer. In most cases, you will use the TTL signal levels again, a 1 being represented by +5 V dc and a 0 being zero volts, or ground. You must be careful not to exceed the 5-volt mark, or accidentally input an alternating current signal. Once again, buffering is a good idea.

The doctor takes a final look just to make sure everything is there . . . all the input and output lines; voltages up to specification. It's time to go sit in the reception area for a minute and wait for the doctor to come out with the results. In the meantime, he suggests we read the user's manual and pay particular attention to the drawings and charts that show the different gateways to your computer.

The Doctor's Orders

The prognosis is good! You should be able to use your computer to connect to the world for many different applications. However, the doctor does utter a few emphatic warnings:

- *Never* connect or disconnect *anything* to or from your computer with the power *on*!
- Always double-check to make sure you are really connecting to what you think you are connecting to. The pins on the connectors are small, and it's easy to be one pin off.
- Always heed the limitations of your equipment. Don't try to draw too much power from your computer. Some projects you may want to build will require more power than your machine can supply. In such a case, it is possible to use an external power source. So there it is. The Commodore doctor has been encouraging about your machine's capabilities, provided you know its limitations. It's time to build something!



Figure 1. *Example circuit.*


TO COMPUTER USER PORT
PIN #2 (5V DC)
R1
THESE CONTACTS CONTROL YOUR APPLIANCE
D1
PIN C
R1
Q1
PIN 1
PARTS LIST
Q1 -2N2222 NPN TRANSISTOR OR EQUIVALENT
D1 -1N914 DIODE OR EQUIVALENT
R1 -1000Ω RESISTOR
RL1-5V DC RELAY, 75mA COIL RADIO SHACK #275-243 OK
DO NOT EXCEED THE CONTACT RATING FOR THE RELAY! WITH THE RELAY LISTED, A MAXIMUM CURRENT OF 2 AMPS AT 125V AC CAN BE SWITCHED.

Figure 2. *Diagram of the interface.*

A Step Toward Control

This month's program and interface are intended to get you started on your way to connecting your computer for control.

The program itself is pretty straightforward. It uses your computer's internal clock to turn a signal on the user port on and off at the times you have predetermined.

The signal will be present on pin C of the user port. If you have trouble understanding how the program selects the proper connection on which to output (pin C), I suggest you review this magazine's first installment of "Gateway to the World" (May 1984).

The interface shown (see Figure 2) is a very simple one. All of the parts should be readily available. The transistor is noncritical; I suggest the 2N2222, which is a very popular general-purpose kind of transistor.

The signal from pin C of the user port is first fed through resistor R1, which is used to limit the amount of current you draw from the computer, thus offering a certain measure of protection for your machine. As Figure 2 shows, R1 feeds into the base connection of the transistor. You might think of this as the valve that turns the electron flow on and off.

The transistor's emitter is grounded. You place a small 5-volt relay in the collector lead. The other side of the relay is connected to +5 V, which can be obtained from pin 2 on the user port. Diode D1 serves as some additional protection. When relays operate and release, a pulse can be induced into the circuit much like the one produced by the ignition coil in your car. It can destroy transistors! The diode doesn't allow this pulse to get there.

You are using the transistor as a buffer. The transistor can be turned on

Listing 1. *Commodore Controller program.*

```
10 DR=56579:W=56577:R=1:REM FOR C-64
20 REM IF VIC-20 DR=37138:W=37136
30 POKE DR,R
40 PRINT "{SHFT CLR}COMMODORE CONTROLLER"
50 PRINT "{2 CRSR DNs}ENTER CURRENT TIME":P
   RINT "(HHMMSS-24 HOUR CLOCK): ":INPUT TI
   $
60 PRINT "{2 CRSR DNs}ENTER ON TIME:":PRINT
    "(HHMMSS)":INPUT OT$
70 PRINT "{2 CRSR DNs}ENTER OFF TIME:":PRIN
   T "(HHMMSS)":INPUT OF$
80 IF OT$=TI$ THEN POKE W,R:PRINT "{2 CRSR
   DNs}RELAY ON":GOTO 100
90 GOTO 80
100 IF OF$=TI$ THEN POKE W,0:PRINT "{2 CRSR
    DNs}RELAY OFF":FOR X=1TO2000:NEXT X:GO
    TO 40
110 GOTO 100
200 REM ************
201 REM *
202 REM * (C) 1984
203 REM * JIM GRUBBS
204 REM * PO BOX 3042
205 REM * SPRINGFIELD
206 REM * ILL 62708
207 REM *
208 REM ************
```

Pin	
1	Ground
2	+5 volts
3	Reset
*4	Joy 0
*5	Joy 1
*6	Joy 2
*7	Light Pen/Firebutton
*8	Cassette Switch
9	Serial ATN In
10	+9 volts
11	+9 volts
12	Ground
A	Ground
*B	CB1
C	PB0 (bit 0)
D	PB1
E	PB2
F	PB3
H	PB4
J	PB5
K	PB6
L	PB7
*M	CB2
N	Ground

*These pins have a different nomenclature on the C-64. For this month's project, the difference is of no concern. Readers are advised to check the Programmers Reference Guide before using these pins.

Figure 3. *Pin nomenclature for user I/O.*

and off with only a very small amount of current. The transistor itself, rather than the computer, then bears the load. When the input signal is high (+5 V or so), the transistor turns on just like a switch, providing a ground path for the relay. With ground on one side of the relay and +5 on the other, the relay operates. When the signal from the computer drops to 0, the transistor turns off. There is no ground path for the relay, so it opens up.

You can use the relay's contacts for anything you desire, within the ratings limitations of the relay contacts. You could certainly, for example, turn a small cassette recorder on and off with the contacts. If you use the proper relay, you can turn any appliance on and off. The possibilities are endless. Such an arrangement can be used with the proper program to create a dial-pulse-type telephone dialer.

Next month, we will begin a visit to the joystick port. R

Address all author correspondence to Jim Grubbs, PO Box 3042, Springfield, IL 62708.

Circle 81 on Reader Service card.

BACKUP PROTECTED SOFTWARE WITH COPY II 64™

From the team who brought you **COPY II PLUS** (Apple), **COPY II PC** (IBM) and **COPY II MAC** (Macintosh) comes a revolutionary new copy program for the Commodore 64, **COPY II 64**!

- Copies most protected software — *automatically.*
- Copies even protected disks in just 3½ minutes.
- Maximum of four disk swaps on a single drive.
- Copies half and full tracks.
- Not copy protected, of course.

Available at your local dealer or direct from us.

CENTRAL POINT Software, Inc.

ONLY **$39.95**
(Plus $3 Shipping & Handling)

9700 S.W. Capitol Highway, #100/Portland, OR 97219

(503) 244-5782 MasterCard VISA **WELCOME**
(Prepayment Required)

This product is provided for the purpose of enabling you to make archival backups only.

Circle 205 on Reader Service card.

SAVE BIG ON COMPUTER PRODUCTS

MODEMS
HAYES
Smartmodem 300 190
Smartmodem 1200 459
Smartmodem 1200B 399
Micromodem II E 220
Smartcom II Software (for IBM PC) 90
Cables to Hayes Modems ..... CALL
NOVATION
SmartCat Plus 320
W/Mite 320
J. Cat 300B direct 99
103 SmartCat 300B Smart 159
103/212 Smart 300/1200 B 379
AppleCat II 300 baud for Apple 200
212 AppleCat 300/1200B for Apple 390

MONITORS
AMDEK
V300G 12" green 122
V300A 12" amber 145
V310A 12" amber (for IBM) 160
Color 300 249
Color 500 369
Color 600 475
SAKATA
SG1000 12" green 95
SA1100 12" amber 105
SC100 13" composite color 210

QUADRAM
MICROFAZER
QRMP-8 Par/Par 135
QRMSP-8 Ser/Par 139
QRMMSS-8 Ser/Ser 139
QRMPS-8 Par/Ser 139
QUADBOARD (for IBM PC)
QR 5310 (no mem. installed) 210
QR 5364 64K (mem. installed) 245
QR 4064 64K (mem. installed) 270
QR 8201 Quadcolor-1 200
QR 8202 Quadcolor-2 (upgrade kit) 200
PARADISE
Multi Display Card 300
Modular Graphics Card 290
Module A or Module B ..... CALL

AST
Six Pak Plus 250
MegaPlus II 270
1/0 Plus II 125
HERCULES
Graphics Board 329
Color Board 170

SAVE 31%-43%
OFF MFR. SUGG. RETAIL PRICES ON
PRINTERS
EPSON•OKIDATA•DIABLO
SCM•DELTA•GEMINI•NEC
•TOSHIBA•COMREX

EPSON FX-80+

EPSON
RX 80/RX 80 FT ..... CALL
LX 80 FT ..... CALL
FX 80 375
FX 100 350
LQ 1500 P ..... CALL
PowerType lettter quality 325
COMREX CRII letter quality 360

STAR MICRONICS
SG 10 ..... CALL
SD 10/15 ..... CALL
SR 10/15 ..... CALL

OKIDATA
Oki 84 ..... CALL
Oki 92 ..... CALL
Oki 93 ..... CALL

DISKETTES
wabash
Wabash 1111 5¼"SS/SD ... 11.00
Wabash 1212 5¼" SS/DD . 12.00
Wabash 2222 5¼" DS/DD . 13.00
maxell
MF-1 3½" SS/DD 34.00
MF-2 3½" DS/DD 50.00
MD-1 5¼" SS/DD 16.50
MD-2 5¼" DS/DD 21.50
MD1DD 5¼" SS 96 TPI ... 29.00
MD2DD 5¼" DS 96 TPI ... 35.00
MD2HD 5¼" DS (IBM-AT) . 45.00
FD 1 8" SS/DD 32.00
FD 2 8" DS/DD 37.00
Dysan
Dys 12 5¼" SS/DD 19.00
Dys 22 5¼" DS/DD 25.00
Dys 33 5¼"DS 96 TPI 45.00
Dys 8128 8" SS/DD 27.00
Dys 8228 8" DS/DD 32.00
3M
3M3 3½" SS/DD 34.00
3M5 5¼" SS/DD 16.50
3M5 5¼" DS/DD 21.50
3M5 5¼" DS/DD 96 TPI ... 31.00
3M8 8" SS/DD 21.00
3M8 8" DS/DD 29.00

CALL FOR QUANTITY PRICING ON 10 OR MORE BOXES OF DISKETTES

COMMODORE PRODUCTS
Peripherals and Interfaces

C 1541	Disk Drive (Commodore)	$244.00
VIC 1660	Modem (Commodore)	84.00
Cardco+G	Graphics Interface	65.00
The Connection	Graphics Interface (Specify Printer)	70.00
OkiMate 10	Printer (including interface)	199.00

CALL TOLL FREE 800-621-1269 EXCEPT Illinois, Alaska, Hawaii

Corp. Accts. Invited. Min. Ord. $15.00. Visa or MasterCard by Mail or Phone. Mail Cashier's Check, Mon. Ord., Personal Check (2 wks. to clear) Add $4.00 1st item. (AK, HI, P.R., Canada add $10.00 first item) $1.00 ea. add'l shpg. & handl. Shipments to IL address add 7% tax. Prices subj. to change. WRITE for free catalog. RETURN POLICY: Defectives Only: Most products replaced within 30 days of purchase with identical merchandise only. Computer and large peripherals replaced only when defective on arrival (within 3 work days of delivery). Other problems covered by mfr. warranty. ALL ELEK-TEK MERCHANDISE IS BRAND NEW, FIRST QUALITY AND COMPLETE. Delivery subject to availability.

ELEK-TEK, inc. 6557 N. Lincoln Ave., Chicago, IL 60645 (312) 631-7800 (312) 677-7660

Here's a four-star menu that will add a little spice to your selection routines.

Menu, please

By PAUL J. MOTISE

The menu is one of the most common and useful devices in a program. Typically, a list of items is displayed on the screen and you are asked (prompted) to enter a number or letter that corresponds to one of the items. Once you enter your choice, the program branches to another routine. Usually, you must compare the number or letter you type with the number or letter that appears next to the menu line item.

Like Magic

A more user-friendly menu, however, lets you select and enter your menu choice by pressing only the space bar and the return key. This kind of menu initially displays a cursor next to the first line item on the menu.

If that item is your choice, you press the return key. If the cursor is not on the line of your choice, you simply press the space bar, and the cursor magically drops down to the next line of the menu. Every time you press the space bar, the cursor moves down the list one line. If you scroll through to the last item in the menu and wish to go through the list again, just continue pressing the space bar.

This kind of menu is fast and easy to use, and is featured on some expensive word processors. You can have this same feature on your Commodore 64 or VIC-20 by adapting the routines in Magic Menu to your own Basic programs.

Magic Menu not only gives you the jumping-cursor method of item selection, it also gives you the check-mark (✓) character to use as a cursor. The check-mark character is not found on the VIC-20 or C-64 keyboards, nor is it listed in the *Programmer's Reference Guide*'s Commodore Table of ASCII and CHR$ codes.

I discovered the check-mark character by accident. To see the check mark, switch the computer to the uppercase/lowercase Text mode by simultaneously pressing the Commodore and shift keys. Then hold down the shift key and press the @ key. You should now see the check mark on the screen.

If you then type in (still in Text mode) print asc("✓") and press the return key, you will see that the check mark has an ASCII value of 186 in the Text mode. (Try typing print chr$(186), and then press the return key, again in the Text mode.)

You can easily adapt Magic Menu to your own Basic programs. However, there are two important points to remember. First, be sure to use the Text mode when you type and list the program, so that uppercase letters in your Print statements don't appear as graphics characters in your listing. Second, you must set the screen display to the Text mode whenever you use the menu. Although Magic Menu was written for the C-64, it should work on the VIC-20 as well, with only a few shortened Print statements to account for the VIC's narrower screen width.

The Program

Here's how the program works and how to change it to fit your needs. Basically, the menu is printed and the check-mark cursor is printed next to the first menu item. A counter keeps track of the check-mark cursor's location on the screen.

The keyboard buffer is read for the presence of either a space or a return character. If a space character is detected, the check-mark cursor is overwritten with spaces and reprinted on the next line unless the value of the counter is greater than the number of menu items.

If the value is greater, then the check-mark cursor is printed at the first menu item and the counter is reset. If a return character is detected, then the program branches out of the check-mark cursor Printing routine. To make the cursor move smoothly, it is necessary to keep track of the location of the screen cursor (which is normally invisible while the program is running).

Line 90 switches the display to the Text mode.

Line 95 sets n (see Table 1) equal to the number of menu items.

Line 100 defines the check-mark cursor as a reversed check mark, padded with reversed spaces and three cursor lefts in order to place the screen cursor at the position of the first reversed space. (Here and elsewhere in the program, I place reversed spaces at the start and end of reversed characters to improve text clarity.) The cursor lefts are important because the check-mark cursor will be made to disappear by being overwritten with spaces, and, to do this completely, the overwrite must begin at the first character.

Line 105 defines the "eraser" as

RUN It Right

C-64 or VIC-20

three spaces followed by three cursor lefts so as to properly reposition the screen cursor for Print commands that follow.

Lines 120–180 clear the screen, print the menu and print the prompt below the last menu item. The tabs before each menu item leave room for the check-mark cursor. Your own tabbed menu items must be short enough to fit on one screen line. VIC-20 owners will want to shorten the prompts on lines 175 and 180.

Line 200 positions the screen cursor to the start of the first menu item and initializes the counter l, which indicates the menu item where the check-mark cursor is displayed.

Line 210 prints the cursor.

Lines 410–430 handle the response to the prompt, using the Get statement. The program ignores keys other than return (CHR$(13)) and space (CHR$(32)). If you press the return key, you have then made a menu choice, and the program branches to line 800. If you press the space bar, the check-mark cursor moves to the next menu item.

Lines 710 and 720 move the check-mark cursor. First, the eraser is printed and the screen cursor drops to the start of the next line on the screen. The counter l increases by one. The value of l is now compared with the total number of menu items, n, to determine where the screen cursor is located.

If l is greater than n, the screen cursor falls below the last menu item, and must be reset to the first menu item, where the check-mark cursor can be reprinted. The reset is done by a branch to line 200. However, if l is not greater than n, then the screen cursor is still on one of the menu line items, and the check mark can be printed at that line (this is done by a branch to line 210).

Lines 800–5000 display the menu item chosen and branch to other parts of the program according to the item you have selected. Line 810 repositions the screen cursor to the upper-left corner of the screen and then drops it down to a line below the prompt. Line 870 uses the value of l to branch to other parts of the program.

Remember that your display will still be in the Text mode after branching occurs. If you prefer the Uppercase/Graphics mode for displays in other parts of your program, clear the screen and switch to the Uppercase/Graphics mode with this program statement:

```
PRINT "{CLEAR}"CHR$(142);
```

Happy menu-making! R

n	=	total number of items on the menu
cr$	=	check-mark cursor
e$	=	eraser, which blanks out check-mark cursor
a$	=	string to hold answer to prompt
l	=	current menu line item at which check-mark cursor appears
i	=	index counter used by For... Next loop

Table 1. *Magic Menu program variables.*

Address all author correspondence to Paul J. Motise, 6 Whetstone Drive, Gaithersburg, MD 20877.

Listing 1. *Magic Menu program for the C-64 or VIC-20.*

```
1 REM *** MAGIC MENU ***
2 REM *** COPYRIGHT 1983 BY PAUL J. MOTISE
  ***
3 REM **** VARIABLES ****
4 REM
5 REM{5 SPACEs}N=NUMBER OF LINE ITEMS IN ME
  NU
6 REM{3 SPACEs}CR$=CHECK MARK CURSOR
7 REM{4 SPACEs}E$=ERASER
8 REM{4 SPACEs}A$=ANSWER TO PROMPT
9 REM{5 SPACEs}L=LINE ITEM WHERE CHECK MARK
  APPEARS
10 REM{4 SPACEs}I=INDEX COUNTER USED BY FOR
  /NEXT LOOP
12 REM
20 REM ******************
90 PRINT CHR$(14): REM UPPER/LOWER CASE
95 N=5: REM SET NUMBER OF LINES IN MENU
100 CR$="{CTRL 9} "+CHR$(186)+" {CTRL 0}"+"
  {3 CRSR LFs}"
105 E$="{3 SPACEs}{3 CRSR LFs}": REM 3 SPAC
  ES 3 LEFT
110 REM PRINT MENU
120 PRINT"{SHFT CLR}";
130 PRINT "{CTRL 9} {SHFT M}{SHFT A}{SHFT I
  }{SHFT N} {SHFT M}{SHFT E}{SHFT N}{SHFT
   U} ":PRINT
140 PRINT TAB(5)"1) {SHFT F}{SHFT I}{SHFT R
  }{SHFT S}{SHFT T} {SHFT C}{SHFT H}{SHFT
   O}{SHFT I}{SHFT C}{SHFT E}"
145 PRINT TAB(5)"2) {SHFT S}{SHFT E}{SHFT C
  }{SHFT O}{SHFT N}{SHFT D} {SHFT C}{SHFT
   H}{SHFT O}{SHFT I}{SHFT C}{SHFT E}"
150 PRINT TAB(5)"3) {SHFT T}{SHFT H}{SHFT I
  }{SHFT R}{SHFT D} {SHFT C}{SHFT H}{SHFT
   O}{SHFT I}{SHFT C}{SHFT E}"
155 PRINT TAB(5)"4) {SHFT F}{SHFT O}{SHFT U
  }{SHFT R}{SHFT T}{SHFT H} {SHFT C}{SHFT
   H}{SHFT O}{SHFT I}{SHFT C}{SHFT E}"
160 PRINT TAB(5)"5) {SHFT F}{SHFT I}{SHFT F
  }{SHFT T}{SHFT H} {SHFT C}{SHFT H}{SHFT
   O}{SHFT I}{SHFT C}{SHFT E}"
165 PRINT:PRINT
170 REM DISPLAY PROMPT
175 PRINT"{CTRL 9} {SHFT P}RESS {SHFT R}ETU
  RN {SHFT T}O {SHFT E}NTER {SHFT C}HOICE
  {3 SPACEs}"
180 PRINT"{CTRL 9} {SHFT P}RESS {SHFT S}PAC
  E {SHFT B}AR {SHFT T}O {SHFT M}OVE {SHF
  T C}URSOR "
200 PRINT"{HOME}{2 CRSR DNs}";: L=1 : REM P
  OSITION CURSOR ON FIRST LINE ITEM
210 PRINT CR$;
400 REM GET ANSWER TO PROMPT
410 GET A$:IF A$="" THEN 410
420 IF A$<>CHR$(13) AND A$<>CHR$(32) THEN 4
  10 : REM IGNOR INVALID KEYS
430 IF A$=CHR$(13) THEN 800: REM CHOICE MAD
  E, SO BRANCH.
500 REM MOVE CHECK MARK CURSOR
710 PRINT E$: L=L+1 : IF L>N THEN 200
720 GOTO 210
800 REM PRINT MENU CHOICE
810 PRINT "{HOME}";: FOR I=1 TO N+8 :PRINT:
  NEXT: REM DROP CURSOR BELOW PROMPT
820 REM LINE CHOICE IS L
830 PRINT"{SHFT Y}OUR CHOICE IS ITEM ";L"."
  :PRINT:PRINT
850 REM BRANCH HERE FOR REMAINDER OF PROGRA
  M
870 ON L GOTO 1000,2000,3000,4000,5000
1000 PRINT"BRANCH FOR CHOICE 1":END
2000 PRINT"BRANCH FOR CHOICE 2":END
3000 PRINT"BRANCH FOR CHOICE 3":END
4000 PRINT"BRANCH FOR CHOICE 4":END
5000 PRINT"BRANCH FOR CHOICE 5":END
```



C

JIM STRASMA

Commodore Clinic is designed to help you through troubles and questions you have as you use your Commodore computer. Send questions on a postcard to:

Jim Strasma
Commodore Clinic
1238 Richland Ave.
Lincoln, IL 62656

and we will answer as many as possible in the Clinic. An unfortunate side effect of RUN*'s popularity is that we can no longer give personal replies to letters.*

HARDWARE

Q: Upon hooking up my 64 (serial #45447) to my Zenith 19-inch color TV, I noticed the display was not as sharp as the one in the store. Despite repeated attempts to tune the TV, the waviness of the images continued.

I have read that early 64s suffer from serious video problems. Could my machine be suffering from video defects? The letters on the screen are legible in blue on blue, but unreadable in many other colors—they seem smudged. Also, the screen shows diagonal waves that travel vertically up or down, distorting the image.

A letter to Commodore brought a suggestion that the cause was an asynchronous scan being put out by the TV's automatic fine tuner, but turning off the automatic fine tuner did not help. I would appreciate any help you could give me on this matter.

Bill Reed
Palmdale, CA

A: Your 64 is old enough that it might have some video problems, including the smudging together of a few combinations of colors. In part, this is not Commodore's fault; it is due to the method used to make U.S. TV signals and will continue even on the newest 64s and most non-Commodore video monitors. However, the VIC II chip has been revised since your 64 was made, and a newer VIC chip might give better results.

The bulk of your problem, however, is due to your TV, not the 64. According to information Commodore sent its dealers in December 1982, the problem is unstable vertical synchronization, and there is a simple fix—defeat the integrated vertical mode circuit on the TV.

On the Triple Plus chassis, it is located on the 9-152 series module. On 9-152-01, remove the 2K jumper to the right of R2129. On 9-152-02, unplug the yellow wire from 2H. On the Z chassis, it is on the 9-181 module and is defeated by turning jumper 5M 90 degrees.

Although it sounds simple enough to remove a wire or jumper, nothing is simple about the interior of a modern TV. Unless you are skilled at working in areas of very high voltage, leave the fix to your Zenith dealer.

Q: When using my 1541 with a Zork I disk, I received an internal error message. Since then, I have not been able to use the disk drive. It will not accept commands and states "Error #21." Is it out of alignment?

Peter Hansen
Mexico City, Mexico

A: Error 21 is probably DOS Error 21, a serious disk error. If it only happens when you try to use the Zork disk, the disk has probably become damaged, most likely by your having left the disk in the drive when the power was turned off or on. In such cases, Commodore suggests you return the disk to them with $5 U.S., and they will replace it.

On the other hand, if none of your disks work anymore, misalignment is a real possibility. Try to format a new disk. If that works, then try to use your other disks again. If only the new disk works, your drive is most likely out of alignment.

If all the disks now work, then the problem was most likely that your drive head was in an unusual position from which it could not work properly until the formatting process moved it back into proper position.

Q: About 3 months ago, I sent away for Letco's 64K Expander. As soon as it arrived, I realized I was in way over my head. I know nothing about "paging." Here I am with a dandy expander and not the least notion how to use it. Can you help?

John Desmond
Valyermo, CA

A: From the instructions you sent, it appears the Letco expander works by mapping one of eight 8K blocks of added memory into the 8K of memory used by most cartridges on the 64. It works much like the added memory on the SuperPET.

In both cases, you have access only to a small part of your added memory at any one time, but can quickly and easily choose which parts are in use, thereby gaining effective use of all parts. It is similar in principle to a spreadsheet, which can be very large but allows you to see only a small fraction of its information at a time.

This arrangement allows you to use the 64 as usual, but also means the added memory can be used only by machine language programs or via Peeks and Pokes from Basic.

Worse yet, only programs that are specially designed to work with your particular memory expander can use more than one 8K bank of it. To use multiple banks in a single program, each piece must call the next one as it is needed, much as the Basic Load command can be used to make one program load another.

Unless you have a specific use for the added memory and are skilled enough to use it, bank-switched add-on memory probably isn't a good idea for you.

Q: We purchased a Commodore 1702 video monitor, which came with an 8-pin DIN plug. Our 64 has a 5-pin DIN jack. What can we do?

I.A. Smith
Boston, MA

A: You can buy a suitable 5-pin DIN cable from many Commodore dealers. If none in your area has it, try a stereo store.

The cable you need has a 5-pin DIN plug at one end and four RCA phono plugs at the other. It is normally used to plug European stereos into speakers and tape decks. Also, the 5-pin cable is intended to use the jacks on the front of the monitor, not those on the rear. If you want to use the rear jacks, you'll need to modify 64s with 5-pin DIN jacks.

According to an article in *Baron's Microcomputing Reports*, if you disconnect resistor R10, the chrominance signal required by the 1702's rear connector will be available on pin 4 of the 5-pin DIN jack, which formerly carried composite video. Since this will make the computer incompatible with ordinary TVs, you may want to add a switch to reconnect the resistor when using a TV. (I haven't tested this modification, so proceed at your own risk.)

PROGRAMMING

Q: Some programs appear to use lengthy variables (for example, DELTA = 1). I thought variables could only be two characters. Does the computer disregard all after the first two?

Paul Arneth
Sandy Hook, CT

A: That's correct. PET Basic variables may be any practical length, but only the first two characters are significant. One other limitation is that no part of a variable name may read

Nobody copies better !!

Since November 1984, Mr. Nibble has successfully copied heavily protected diskettes for grateful C-64 owners!

While others promise,

MR. NIBBLE™

delivers!

The next generation in archival methods is here today!

- *No better disk copier at any price*
- *Easy-to-use — no complicated instructions*
- *Totally automatic — no knowledge of DOS required*
- *You'll LOVE MR. NIBBLE™ — if not, return within 10 days for full refund*

Own ***THE FINEST DISK COPIER SYSTEM*** *for The C-64 and 1541 disk drive -* ***Order today!***

Full Circle Software

FULL CIRCLE SOFTWARE, INC.
P.O. Box 1373
Dayton, Ohio 45401
Phone (513) 223-2102

$49.95 includes shipping & handling (Ohio residents add 6½ sales tax)

10 day return privilege

Special MSD Version now available!

Circle 265 on Reader Service card.

as a Basic keyword. The value of using long names is that they can be more descriptive. In the example you cite, Delta is very descriptive of the function of that variable in a flight simulator, whereas the equivalent DE = 1 would require a Remark statement for clarity each time it is used.

Q: There is a beast beneath the keyboard of my 64, and its number is −1.49011612E-08. To awaken the beast, run this:

```
10 A=40
20 B=.18
30 C=A+B
40 D=40.18
50 PRINT D-C
```

The zero you would expect to see has been eaten by the beast. Is there a glitch in Commodore's engineering?

Gaylen Moore
Bovey, MN

A: No, you've simply discovered that the computer uses binary (base 2) for its calculations, while you use decimal (base 10). Your beast comes from errors in converting from one to the other. Precision in all Microsoft Basics except the one in Commodore's B-128 model is limited by the space set aside to do these conversions. A fix for your line 50 is shown below.

```
50 PRINT INT(100*(D-C)+.5)/100
```

This change rounds the result to the nearest two digits, well within the limits of precision on all Microsoft Basics. To select more or fewer digits of precision, add or subtract zeroes from the numbers used for both multiplication and division in my version of line 50.

Let me also remind you that in scientific work, if you want two valid known decimal places in your answer, line 10 should also be changed to

```
10 A=40.00
```

The computer doesn't care about the extra zeroes, but without them, anyone checking your program must assume A was calculated only to the nearest whole number.

Q: Why do I get a Syntax error when I try to type in more than two lines of a program that has five or six lines between line numbers?

Gilbert Neldner
Haines City, FL

A: Programs that have lines longer than two lines have done one of two things: either they have been typed in using the abbreviated forms of the Basic keywords, or they have been run through a compactor program after they were finished. If the Basic line you see is five or six screen lines in length, it almost certainly has been compacted. To type it in, you will have to split its parts down into several smaller Basic lines, no one of which is longer than two screen lines. An uncompactor program to automate this chore was featured in the November 1984 issue of *RUN*.

If it is important to restore the line to its original oversize length later on, you'll have to run it through a compactor program afterwards, such as the one also included in the November *RUN*. As the name suggests, compactor programs combine Basic lines as much as possible, up to the theoretical maximum line length (255 characters), without affecting the logic of the program, and also delete Remark statements and spaces that are not within quote marks. Most require a disk drive.

Q: I would like to sell, as a plug-in cartridge, a program that I have written. How can I get it mass-produced? Should I have the program copyrighted? If so, how?

Curtis Finke
Evansville, IN

A: Several companies will gladly sell you EPROM burners to convert your program into ROM form. Two with which I am familiar are the Prom Queen from Gloucester Computers (1 Blackburn Center, Gloucester, MA), and the Promenade from Jason Ranheim (580 Parrott, San Jose, CA). To complete the process, you will then need cartridge shells. These are available from at least two companies: Eastern House Software (3239 Linda, Winston-Salem, NC) and Richvale Telecommunications (10610 Bayview, Richmond Hill, Ontario, Canada). These companies or others like them may also be willing to burn the needed ROMs for you, saving you the need to have an EPROM burner.

Recent court decisions suggest ROM-based programs can now be copyrighted, so long as they claim to be so. Therefore, be sure to include a copyright notice, such as "Copyright 1985 Curtis Finke, all rights reserved" both in the code stored in the ROM and on the outside of the ROM and cartridge. That should be enough to copyright your program. However, you can gain some advantages in a lawsuit to enforce your copyright if the copyright has been registered at the U.S. Copyright Office in Washington, D.C. The cost is small, but contact the copyright office for current details.

Q: When I first ran the color adjustment check in the *Commodore 64 User's Guide* (holding CTRL and a number), it worked excellently. But when I went back to do it again, it would only display letters in color and wouldn't display color bars when I held down the space bar. Is this a defect?

Ronnie Barcak
Fort Stewart, GA

A: I expect your 64 is working just fine. You merely need to press one more pair of keys when you do the color-bar test—the CTRL key plus the 9 key. This turns on reverse field (labeled RVS ON on the front of the 9 key), which makes the space character show up as a bright bar on your screen. The bar will be the same color as any characters you type and will change in color when you change the character colors.

To turn *off* the color bars, merely press the return key, alone or together with a shift key. You can also turn it off without moving the cursor

by simultaneously pressing the CTRL key with 0 (the RVS OFF key).

Q: After typing in a program, I saved it to my 1541 disk, then loaded and ran it. Later, I wrote another one. It, too, loaded and ran all right.

Now here's the funny part. When I went back to load the first program, I got the second instead. I can't figure it out; I hope you can.

Joe Nakles
Blairsville, PA

A: The problem often arises when a disk has been used for a while, contains some programs, and at least one program has been scratched. Then another program is saved, but something happens and the save doesn't work. The red error light flashes and you know you have a problem.

Your files have become cross-linked. The only sure cure is to copy the entire disk to a freshly formatted disk, copying one file at a time, rather than using a disk backup program.

The most probable cause is that at some previous time you scratched (erased) an improperly saved program or file (one whose name appeared in the directory with an asterisk next to its filetype, but could not be loaded). For future reference, the proper way to get rid of such improperly saved files is with the disk Validate command (known as the Collect command on the Plus/4 and C-16).

Q: In typing a program, there are occasions when one must press the CLR key (between quotation marks, of course). What has happened is that, for some reason, my leading quote mark wasn't there, with the consequence that the program was wiped out. Is there any way to recover the typed program after hitting CLR?

L.P. Thomason
Jacksonville, FL

A: Pressing the CLR key should have no effect on your program. If you accidentally erase the screen by pressing the CLR key, you can view your program listing again by simply typing the word LIST and pressing the return key. Then, retype the line where you initially erred.

Q: I recently purchased a 64, but already had a VIC and 1540 disk. Is there a way to get the 64 to work with the 1540? I have been told there is a command to slow the disk's transfer speed, but I have also been told that the only way to get the 1540 to work is to have a chip changed to make it a 1541. I don't believe this because I have seen many pictures of the 64 with the 1540.

Rob Gregg
Topeka, KS

A: The disk command that slows its transfer speed won't help you—it's designed to return a 1541 disk to 64 speed after using a similar command to change it to VIC speed. Apart from added speed when used with a VIC, there's no need to use either command. For future reference, the two commands are:

@UI- (speeds a 1541 by 25% for VIC only)
@UI+ (restores normal speed)

Both examples assume you're using the DOS wedge program on your test/demo disk.

A command that *will* help you is POKE 53265,11. It turns off the 64's video screen, preventing the interrupts from the VIC-II chip that normally keep the 64 from working with the 1540. Since it's difficult to work with the screen off, the easiest way to use this command is as follows:

```
POKE 53265,11:LOAD "NAME",8
```

or

```
POKE 53265,11:SAVE "0:NAME",8
```

where "NAME" is the name of the program you want to load or save. After the command has been obeyed and the drive activity light turns off,

Now you can add friction feed capability to your Epson — MX 70/80, RX 80 type printers
with our
MICRO-GRIP™ V

- Micro-Grip™ gives you single sheet feed capability you want without the high cost of buying a friction feed printer.
- Designed for the Epson MX-70/80, RX-80, and printers based on the Epson design such as the IBM #5152, Commodore 4022, and the H.P. 828086/820905 B.
- Easy to install, will not disturb the tractor feed capabilities of your machine.
- Unconditional money back guarantee if not completely satisfied.
- Just **$44.95/ea.** (add $3.00 for shipping)

Note: Diagram is not drawn to scale!



* NOTE: Micro-Grip™ is not a substitute for a friction feed printer. It is a retrofit mechanism for the purpose of obtaining single sheet correspondence from your tractor feed printer.

Printing will start approximately 1½" from the top of the page.

Micro-Grip™ is a trademark of Bill Cole Enterprises.

#670 Micro-Grip™
Suggested List Price — $44.95/ea.
Wholesale Price Schedule
3 – 5 — 20% (35.96/ea.)
6 – 11 — 30% (31.47/ea.)
12 on up — 40% (26.97/ea.)

Dealers: Co-operative advertising is available. Write for details.

Circle 82 on Reader Service card.

Bill Cole Enterprises, Inc.
MANUFACTURERS AND DISTRIBUTORS OF COMPUTER SUPPLIES

Terms & Conditions
A minimum order of 10.00 is required, not including shipping. Prices effective 1/10/85 and are subject to change without notice. Automatic credit is extended to Federal agencies, but to keep our prices competitive, we must request payment with order from all other individuals and institutions. No C.O.D. orders accepted except for freight charge. No merchandise may be returned without prior written authorization from this office. Merchandise ordered in error or not wanted is subject to a 25% restocking charge. Defective material replaced at no charge, Mass. residents add 5% sales tax.
Orders outside the U.S. — please write for a pro-forma invoice.

P.O. Box 60•DEPT. R4
WOLLASTON, MA 02170-0060
617-773-2653•617-963-5510
For Credit Card Orders Only! Call Toll Free 1-800-225-8249
We carry a COMPLETE line of computer supplies. Ask for our Free Catalog

turn the screen back on by simultaneously holding down the restore and stop keys.

Since this is a painful method at best, and not included in most programs for the 64, I'm sure you'll soon order Commodore's 1541 upgrade chip for your 1540.

Q: Could you tell me how to write a program to generate random non-repeating numbers?

Bob Hendershot
Carrollton, TX

A: The first step is to decide how many random numbers you need and what range (top and bottom values) and increment (distance between possible values) you require. Then you can dimension a suitable array, fill it with appropriate numbers and finish by shuffling the values within the array. After all this, you generate your random, non-repeating sequence by printing the contents of the array in order.

Here is a program to generate and shuffle a suit of cards:

```
100 REM RND DEMO
110 X=RND(-TI):REM RANDOMIZE
120 DIM A(13)
130 REM MAKE 13 CARDS
140 FOR I=1 TO 13
150 : A(I)=I
160 NEXT
170 REM NOW SHUFFLE
180 FOR I=1 TO 99
190 : C1%=RND(1)*13+1
200 : C2%=RND(1)*13+1
210 : T=A(C1%)
220 : A(C1%)=A(C2%)
230 : A(C2%)=T
240 NEXT
250 REM PRINT SEQUENCE
260 FOR I=1 TO 13
270 : PRINT A(I)
280 NEXT
290 END
```

The key lines are 110, which makes the sequence of random numbers more truly random; 190–200, which select a random integer between 1 and 13; and 210–230, which do the actual shuffling.

Q: The VIC-20 has 22 columns across its screen. How do you display a word like "William" (7 characters) in the center of the screen—in other words, how do you move over half a space?

H.L. Jackson
Minneapolis, MN

A: Given any string of fewer than 22 characters, its contents may be centered on the VIC's screen by printing it this way:

```
PRINT TAB(22-LEN(A$)/2);A$
```

(64 owners should change the 22 to 40.) If there is a leftover character, it will appear on the left, just as it

RABBIT
For the 64 or VIC
$39.95
Alternative to the 1541 Disk Drive!
Load or save 8K in 30 seconds! It's less expensive than disk and can even be used as a backup to the flaky 1541!
Yes, the RABBIT is that and much more. Uses the Commodore cassette deck but loads and saves much, much faster than regular Commodore load/save. Think about it — loads or saves an 8K program in almost 30 seconds, 16K in 1 minute, etc. That's nearly as fast as the 1541 disk. RABBIT is on cartridge so it's always there. Also has other useful commands. Specify for use on the 64, or on the VIC 20 —
"It was the best purchase for my computer that I have ever made!"
"Congratulations on your 64 Rabbit. It's a super piece of work."

AutoLoad/Directory
Cartridge for the 64.
This cartridge has a push-button switch on it that allows you to: 1) Load and then automatically run the first program on disk, and 2) Display the disk directory – either at the touch of a button! It may not sound like much but it is absolutely one of the most convenient accessories you can install on your 64. Housed in an attractive plastic cartridge complete with easy to install instructions, works with every software package (including menus and commercial software) we have tried and it doesn't take away any memory. Think about it the next time you type: LOAD "*",8,1 RUN or LOAD "$",8 LIST. Remember, it's only $19.95.

MAE NOW THE BEST FOR LESS!
Please for your own protection consider the MAE first before you buy that other assembler. We've had numerous customers who wasted their money on some cheaper off brand assembler tell us how much better the MAE is.
The most powerful Macro Assembler/Editor available for the Commodore 64 and other CBM/PET computers, and also for the ATARI 800/XL and Apple II/IIE.
MAE includes an Assembler, Editor, Word Processor, Relocating Loader, and more all for just $59.95.
We could go on and describe the MAE but we thought you would like to read our customers' comments. The following are actual unedited comments from correspondence about the MAE:
"Excellent Development Package."
"I like MAE and wish that you had it on the Macintosh."
"Compares to DEC and INTEL."
"It is a superb program."

TelStar 64™ by Eastern House
A Communications Cartridge for the Commodore 64.
Upload/Download, Status Line, etc. Works with your Commodore 1600 or 1650 Modem. Auto-dialing, etc. when used with the new CBM 1650 Modem.
Cartridge and Manual – $49.95

Eastern House
3239 Linda Dr.
Winston-Salem, N.C. 27106
(919) 748-8446
Send for free catalog!
VISA
MasterCard
Circle 50 on Reader Service card.

should when you type the same phrase on a typewriter. To move over half a space, you'd have to switch to the high-resolution screen and draw your own letters dot by dot.

SOFTWARE

Q: I have the CP/M cartridge for the 64. I also bought Fortran and Cobol. I've tried to write programs in Fortran, but the CP/M editor was not easy to use. Could you recommend some other editor?

Yeong-Guk Kwon
Lubbock, TX

A: Reader John McGlothlin, of San Bruno, CA, writes, "The best source for software I've found has been CompuServe (currently database XR4 in the CBM Programmers' SIG). An example is VDO.BIN, a text editor that works more easily than the one included in CP/M."

To take advantage of such programs, you will need to get a modem, such as Commodore's new model 1660, which comes with a free membership in CompuServe. Using the terminal program disk included with the 1660, you can call CompuServe. Once you get past the hassle of signing on, you will see a menu of things CompuServe can do. At this point, type "GO CBM", and you will be in Commodore's Information Network. From there, you can print out several screens of helpful information about getting to the programs you want.

You will also need a better-than-standard terminal program in order to download programs from CompuServe. The one sold by CompuServe and Commodore for this purpose is VIDTEX, but there are others. The dealer who sold you a modem probably has a suitable program.

Q: Being in Thailand, it is not practical to dial up the Commodore Information Network. Can you give me an address where I can get CP/M programs for the Commodore 64?

Curtis Hamilton
American Consulate
Chiang Mai, Thailand

A: One company that supports CP/M on the 64 is Cardinal Software (13646 Jefferson Davis Hwy., Woodbridge, VA 22191; 800-762-5645). The company offers disks of CP/M programs and utilities, including a CP/M terminal program and a modification to let CP/M use two 1541 disk units as drives A: and B:.

Q: In a computer store, I noticed a joystick port for the VIC. It said, "Now you can play two-player games on your VIC." Is that possible?

David Rainbolt
Marshall, AR

Circle 72 on Reader Service card.

SIXTH SENSE™

The Thinking Terminal!

The *Ultimate* home modem software for the Commodore 64! **YOU** control its actions, **even when you're not home!** Here is the software that makes contact with remote computers, gathering and dispensing information in a discretionary manner following your instructions. And its sophistication makes it easier to use than other modem programs! Up and download with ASCII, CompuServe B, and XMODEM protocols. Other protocols may be added. 700 line **Virtual Screen**, **split-screen** line input, **macro language**, flexible data routing, high-speed operation and many other capabilities give you greater control at better performance than you thought possible with your Commodore 64. With **SIXTH SENSE**, you can compress hours into minutes, freeing your other five senses for more productive and satisfying activities. Discover the power of computer communications at its best!

Discover SIXTH SENSE

ONLY $89.95

MICROTECHNIC SOLUTIONS, INC.
P.O. BOX 2940 NEW HAVEN, CT. 06515
(203) 389-8383

Commodore 64 is a trademark of Commodore Inc. CompuServe is a trademark of CompuServe Inc.

A: Yes, with proper wiring and programming, a second or even a third joystick can be plugged into the user port. In the old days, before the VIC, all PET joysticks were connected there. However, a joystick or joysticks so connected will only work with programs either you or someone else writes specifically for them, because they use different memory addresses and codes than the standard joystick(s) on the VIC and 64.

Q: **Why is it that Commodore never answers letters sent to them about problems one is having with their products? I have written repeatedly to their West Chester, PA, address about several things, but three months later, I have not even received an acknowledgement of my letters.**

Roy Babin
Sterling, IL

A: Actually, Commodore *does* answer many such letters, but apparently not all of them. To assure proper delivery to their Customer Support department, Commodore suggests you include the code "C-2655" in the lower left corner of your envelope. Be sure you also address the letter to 1200 Wilson Drive, West Chester, PA 19380.

Another way to get an answer to a question, usually overnight, is to ask it via the Commodore Information Network on CompuServe. To do this, you'll need to buy a modem. If it's a Commodore modem, it will come with a free CompuServe membership and instructions on using the Commodore Information Network.

UPDATES

Update: Although we are way behind in some things "down under," there is one thing we have before the States! In your September 1984 column, Jeff Rosenblad asked about descenders on the MPS 801. A replacement character ROM chip is now available from Paul Blair (35 Calder Crescent, Holder Act 2611, Australia; (062) 88 3584). The cost in Australia is $32, postpaid. It provides a much more acceptable print.

Mrs. Maureen Williams
Boulder, Western Australia

A: Thanks for writing and for the good-looking sample printout from the new ROM. It apparently gains descenders by stealing a bit from the ascenders (for example, the "H" doesn't go as high above the line, so the "y" can go below it). Paul is a good source of Commodore information "down under," and I'm always glad to hear from or about him. (Anyone wanting the ROM shipped outside of Australia should add extra postage for overseas airmail.) R

Circle 91 on Reader Service card.

THE Short Wave Listener FOR RECEPTION OF MORSE CODE & RADIO TELETYPE SIGNALS.

Plug the SWL cartridge into your Commodore "64" Expansion Port, connect a shortwave radio and you'll be watching text readout from weather stations, news services, ships and HAM radio operators all over the world. A whole new use for your home computer. The SWL contains both program in ROM and radio interface circuit to copy Morse code and all speeds/shifts of radio teletype. Plus the on screen tuning indicators mean you never have to take your eyes off the video for perfect tuning. Housed in a small 3"×2-1/2"×7/8" enclosure, with speaker in/out and practice hand key jacks, it needs no other computer connection or power supply. Unshift on space, word wrap around, real time clock, and keyword or manual printer control for permanent paper copy, so that you won't miss a single bit of the action. For about the price of another "Pac-Zapper" game, you can tie into the exciting world of digital communication with the Microlog SWL.

$64

MICROLOG
INNOVATORS IN DIGITAL COMMUNICATION
18713 MOONEY DRIVE
GAITHERSBURG, MD 20879 • (301) 258-8400

LEARN MORSE CODE THE RIGHT WAY WITH THE Morse Coach.

$4995

A complete Morse code tutor in a convenient plug-in cartridge for your Commodore "64." The Morse Coach means business. It's not a toy program or a simple random code generator. Originally developed jointly by Microlog and several government agencies experienced in Morse instruction. Four years of extensive service prove it's the quickest way to Morse proficiency.The method works! You start from absolutely no knowledge of Morse, progress through the alphanumeric symbols, and on to any speed desired. The "alphabet" part of the program introduces new characters and plots the progress on a bar-chart. The speed/test section correlates the input, analyzes mistakes and provides a printout of the analysis/test results on your Commodore screen or printer. As a bonus, it also boosts typing skill. You've never seen *any* tape or program do that! In fact, there's never been a system so thorough, so efficient and so effective as the Microlog Morse Coach.

Circle 335 on Reader Service card

AA COMPUTER EXCHANGE

"SOUTH'S LARGEST COMMODORE 64 DEALER"

OVER 2000 ITEMS IN STOCK

REQUEST OUR FULL CATALOG TODAY

ORDER LINE: 1-800-447-0088
INQUIRIES & FL: 904-388-0018

HARDWARE & ACC.
C-64 Computer ..... Call
C-128 ..... Call
1541 Disk Drive ..... Call
1702 Color Monitor ..... Call
SFD 1001 1 Meg Drive .. $399
MSD Dual Drive 499
Indus GT Disk Drive 269
1660 Auto Modem 79
Volksmodem 12 (1200/300) 209
Total Comm. Auto Modem . 69
MPP 1064 w/VIP Term 72
C-64 Power Supply 1-yr 34
Omnitronix Deluxe RS-232 35
Graphic Printer Intrfce 30

ACCESS SOFTWARE
Beach Head 24
Raid Over Moscow 24

COMPUSERVE
Starter Kit (5 hr) 23
Vidtex 28

KOALA
Koala Pad 58
Koala Printer 17

PRECISION SOFTWARE
Superbase 47

BATTERIES INC.
Paper Clip w/Spellpack ... 79
The Consultant 68
Home Pak 34
Home Organizer Series (EA) 15

MISC.
Smart 64 Term 29
Telstar 64 Term (Cart) 25

SIGHT N' SOUND
Keyboard $34
Synthesizer 34
Processor 24

PRACTICORP
64-Doctor $20
Practicalc 64 37
Practfile 37
PS: Spreadsheet 54
Fleet System 2 65

MIRAGE CONCEPTS
Data Base Mgr. w/Report .. 71
W.P. Prof. Version 63
W.P. Personal Version 33

SKYLES ELECTRIC
"1541 Flash" Disk Drive Speed-Up w/Switch 75
Blitz (Compiler) 75

SUBLOGIC
Flight Simulator II 37

XETEC
Fontmaster Wordprocessor 29

GRAPHICS
Doodle 28
Inkwell's Flexidraw 129
Peripheral Vision w/Pen ... 39
Print Shop 29

EPYX
Fast Load (Cart) 26

UTILITIES
CSM Drive Alignment 32
Auto Load w/Reset (Cart) .. 15
Super Clone 39
Ultrabyte Disk Nibbler 29

2726 PARK ST., JACKSONVILLE, FL 32205

Orders with cashiers check, money order and VISA/MC shipped promptly • For personal/company checks allow 3 weeks for clearance • No CODs • For VISA/MC add 3% • Shipping charges extra, $3.00 minimum • Prices may differ in AA stores • Florida residents add 5% tax • Prices subject to change without notice.

Circle 172 on Reader Service card.

Circle 96 on Reader Service card.

Xetec **$39.95**

On Screen Status Display



A - Cursor location
B - Scroll Indicator
C - Print features currently being used
D - Filename of text
E - Percentage of RAM (memory) used
F - Ruler (also message line)
G - Word wrap/justification flag
H - 'Block marked' flag
I - Insert mode flag
J - Characters per inch
K - Number of the current font
L - Name of the current font

Overview of FONTMASTER word processor features:

1) Powerful block manipulation commands (Cut, Paste, Move, Overlay).
2) User - friendly effects include (fonts, super/sub scripts, underlining, bold face, etc.)
3) Up to eight different fonts can be used simultaneously.
4) Many printing options such as page numbering, titles, word-wrap, right justification, and more.
5) Eight disk I/O commands (Save, Load, Verify, Erase, Etc.).

Create Your Own **or choose from over 15 type styles provided in this unique program.**

Including: Bauhaus, English, Shadow, Manhattan, **Block**, *Italic*, Stop, Script, **Bold**, Hairpin, BYTE, Stopbold, **Pudgy**, Mirror, ∩dɐɥɔɐɯ, †ø¼¢₹Ω∑∞

VISA MasterCard

Xetec inc. (913) 827-0685
3010 Arnold Road Salina, KS 67401

ATTENTION COMMODORE 64 OWNERS

We'll pay for your mistake!

We know that it's difficult, especially since everyone is trying to come out with one. Now that error track protection is going the way of the dinasaour, you probably purchased an obsolete piece of software. Well we will give you $25.00 credit*for any original copy utility software disk that you would like to trade in for the "NEW REVISED CLONE MACHINE." Our program can now back up non-standard sectors with complete control, detect and reproduce density-frequency alterations, alter the number of sectors on a track, sync to particular reference sectors (including a single sync Bit copy) PLUS reformat a single track.

Other back up programs have only recently caught up with our ability to reproduce errors. Included is Fast Clone as well as all of the other standard Clone Features, we've even made it more user friendly too! THE CLONE MACHINE was the first utility of its kind and others followed. Well, we still feel that it's time for the others to try to play catch up again.

OUR SPECIAL MSD VERSION NOW AVAILABLE TOO!!

STILL ONLY $49.95

*NOTE: Micro-W reserves the right to cancel this offer at any time without notice

Available from:

Micro-W. DISTRIBUTING, INC.
1342B Route 23
Butler, N.J. 07405
CALL: (201) 838-9027

I Speak Basic to My Commodore 64

Aubrey B. Jones, Jr.
Hayden Book Co., Inc.
50 Essex St.
Rochelle Park, NJ 07662
Softcover, 232 pp., $9.95

As C-64s are used in more and more classrooms, the need for good lesson books will be strong. *I Speak Basic to My Commodore 64* is primarily intended to fill this need.

The book is a computer literacy course designed to introduce students to Basic language programming. It's written in outline form, with very few normal text paragraphs. When more information is required, extensive notes are provided at the end of the section.

This outline style will be somewhat awkward if the book is used alone as a self-teaching tool. It is best suited to a classroom setting.

To help the student, many examples, charts and helpful hints are included. Program listings are very easy to read. The entire layout and text size is very well suited to classroom use.

As for limitations, there are several to be aware of. First, you should remember that this book is just an introduction to Basic programming. Only the very elementary Basic commands and statements are covered.

Certain topics that are important to the operation of the C-64 are omitted. For example, while there is a brief section on cassette usage, there is no discussion of the 1541 disk drive.

Also missing is any mention of printers and making hardcopies of program listings. Whenever areas beyond the scope of this book are noted, the reader is told to see the *Commodore 64 Programmer's Reference Guide.*


I Speak BASIC to My COMMODORE 64
Aubrey B. Jones, Jr.
A field-tested computer literacy course that introduces students to BASIC language programming.
HAYDEN

These limitations might make the book inappropriate for some courses of study. But if all you need is a lesson manual to introduce students to Basic programming, *I Speak Basic* should fit your needs.

Larry Bihlmeyer
Pontiac, MI

Commodore 64 Subroutine Cookbook

David D. Busch
Robert J. Brady Co.
Bowie, MD 20715
Softcover, 194 pp., $12.95

Have you ever found yourself in need of a quick sound effect to add a finishing touch to your Basic program? Or maybe you need a simple timer for a game program.

Searching through stacks of old magazines and programming books for simple, effective subroutines and programming tricks can be frustrating. Even when you find what you're looking for, you still have to work out a way to incorporate it into your existing program, and this often involves extensive editing, renumbering of lines and renaming of variables.

The Commodore 64 Subroutine Cookbook solves many of these problems by bringing together over 60 of the most useful Basic subroutines into one well-organized volume.

Each subroutine is accompanied by a line-by-line description that explains how it works, as well as a few paragraphs that detail how the subroutine might be used in your own programs.

In addition to sections dealing with sound, joysticks and the computer's internal clock, there are chapters devoted to game routines, business and financial subroutines, communications, datafiles and an advanced section on bit-level operations. There is even a chapter containing nine subroutines that allow you to add a number of new functions to Commodore Basic.

Because most of the subroutines are short, they are easily appended onto existing programs by using the simple merge methods described in the first chapter. Since each subroutine is complete and does not build upon previous routines in the book, you can begin with those chapters

and subroutines that interest you the most.

While the *Commodore 64 Subroutine Cookbook* may not be suited to the programming neophyte, as long as you know a Peek from a Poke, you should have no trouble using the subroutines, as well as understanding the organization and logic behind them.

Whether you're cooking up a program to figure the compound interest on your money market certificates, or simply looking for a way to manipulate on-screen objects with a joystick, the *Commodore 64 Subroutine Cookbook* will provide the right ingredients.

Bob Guerra
Charlestown, MA

The Anatomy of the 1541 Disk Drive

Abacus Software
PO Box 7211
Grand Rapids, MI 49510
Softcover, 320 pp., $19.95

After you've learned everything you can about your Commodore 64, you may want to learn more about the 1541 disk drive and its internal workings. *The Anatomy of the 1541 Disk Drive* progresses from basic operations and commands to simple file structures, data storage techniques and technical details of the hardware and internal software of the 1541. Various utility programs are included with full listings and complete operational descriptions. There are plenty of examples throughout the book, plus a brief discussion of the programs found on Commodore's Test/Demo disk.

The major item of interest in this book is a detailed disassembly listing of the DOS ROMs. The extensive comments provided here make it a very handy reference for advanced users who might want to write routines to be executed within the disk controller. There are unlimited possibilities in this area for those willing to spend the time to learn and experiment.

The book is very well written, and it presents the material in a clear, logical fashion. Some details are missing, such as how to clear an entire disk without having to reformat. On the other hand, this book presents information on how to scratch-protect a file, which is not covered in most other books of this type.

Basic 4.0 disk commands are referenced at times, even though they do not apply to the Commodore 64. However, this does present a handy translation reference between Basic 4.0 and DOS commands, if needed.

I would highly recommend *The Anatomy of the 1541 Disk Drive* as a starting point for the serious 1541 user. For those less-advanced users, the sections on datafile techniques will be of great interest and value. There's something here for everyone who wants to expand his knowledge of the 1541 disk drive.

Robert Baker
Atco, NJ

New Releases

Assembly Language Programming with the Commodore 64

Marvin L. DeJong (Brady Communications Co., Inc., Bowie, MD 20715. Softcover, 296 pp., $14.95.) This introductory guide shows how to write, debug and execute assembly language programs. Exercises and problems familiarize you with the instruction set of the 6510 microprocessor.

Commodore 64 Tutor for Home and School: How to Program in Logo, Pilot and Basic

Julie Knott and Dave Prochnow (Scott, Foresman and Co., 1900 East Lake Ave., Glenview, IL 60025. Softcover, 300 pp., $15.95.) Designed for beginners, this book provides a concise introduction to the C-64. Each language is introduced, followed by analysis of sample programs.

The Second Book of Machine Language

Richard Mansfield (Compute! Publications, Inc., 324 West Wendover Ave., Suite 200, Greensboro, NC 27408. Softcover, 446 pp., $14.95.) This book uses the rules and fundamentals covered in Mansfield's *Machine Language for Beginners* to construct a large, sophisticated machine language program for the C-64 or VIC-20.

How to Sell Your Commodore Computer Software

(Associated Technology, Rt. 2, PO Box 448, Estill Springs, TN 37330.) This manual gives information on obtaining national directory listings, pricing new software, writing user's manuals and operating a mail order service.

Cookbook of Creative Programs for the Commodore 64: Projects for Music, Animation and Telecommunications

Robert Rinder (New American Library, 1633 Broadway, New York, NY 10019. Softcover, 206 pp., $12.95.) Explores the graphics and sound capabilities of the C-64 by showing you how to create light shows and music. Nine ready-to-run programs are included.

74470 12069

N

Compiled by SHAWN LAFLAMME



Pitstop II

Epyx, Inc. (1043 Kiel Court, Sunnyvale, CA 94089) has introduced Pitstop II for the C-64.

Pitstop II features two-player competitive racing on the tracks and in the pits, as you combine strategy and driving skill to beat your opponent. Available on disk, Pitstop II retails for approximately $35.

Check Reader Service number 400.

Battle of the Bulge

Strategic Simulations, Inc. (883 Stierlin Road, Bldg. A–200, Mountain View, CA 94043) has introduced Breakthrough in the Ardennes for the C-64.

Simulating the Battle of the Bulge, the game attempts to incorporate all the factors that played a part in the actual battle. Available on disk, Breakthrough in the Ardennes retails for $59.95.

Check Reader Service number 402.

Weather Tamers

Weather Tamers, an educational program for ages 12 and up, allows you to create the weather for North America using various meteorological elements.

The program aims to encourage cooperation and scientific thinking. It is available on disk for the C-64 and retails for $39.95. CBS Software, One Fawcett Place, Greenwich, CT 06836.

Check Reader Service number 403.

Be Your Own Coach

Be Your Own Coach is the second release in the series called To Your Health, from Avant-Garde Publishing Corp. (PO Box 30160, 1907 Garden Ave., Eugene, OR 97403).

The program is a runner's training tool that aims to minimize injury and maximize each runner's own abilities. It is available on disk for the C-64. Retail price is $79.95.

Check Reader Service number 407.

Electronic Novel

Mindwheel is one of the first titles to be released in the Electronic Novel series from Synapse Software (5221 Central Ave., Richmond, CA 94804).



Mindwheel involves a journey into the minds of four deceased people. The Mindwheel package, including disk and hardcover book, retails for $39.95.

Check Reader Service number 405.

High-Rise Adventure

Rock 'n Bolt is a game of strategy and action for the C-64, from Activision, Inc. (2350 Bayshore Frontage Road, Mountain View, CA 94043).

You must guide Louie, who dances across high-rise construction beams and girders, as you try to complete construction of a 100-story building in record time. Rock 'n Bolt is available on disk for $29.95.

Check Reader Service number 425.

Spelunker

Broderbund Software (17 Paul Drive, San Rafael, CA 94903) has introduced Spelunker for the C-64.

Spelunker combines the arcade action of a maze-style game with the strategy of an adventure game. It is available on disk for $29.95.

Check Reader Service number 404.

Bounty Bob Is Back

Miner 2049er II, the sequel to the popular Miner 2049er, offers ten all-new action screens and even more jumping and climbing challenges.

You must dodge ricocheting ore lumps and make your way through a radioactive mine. Miner 2049er II is available for the C-64 and retails for $35. MicroLab, 2699 Skokie Valley Road, Highland Park, IL 60035.

Check Reader Service number 408.

Computerized Music Videos

Computer Hitware is a series of software packages that combine today's popular music with color graphics, creating a kind of music video.

You can arrange your own graphics displays to accompany the program's pre-recorded music. The first release features Duran Duran. The programs are available on disk for the C-64, retailing for $19.95 each. Passport Music Software, 625 Miramontes St., Suite 103, Half Moon Bay, CA 94019.

Check Reader Service number 411.

Basic Compiler

Nanosec Corp. (Lincoln Plaza, 3544 Lincoln Ave., Ogden, UT 84401) has released Pro-Compiler for the Commodore 64.

The program compiles Basic programs to straight machine code. Your compiled program can have up to 48K. During compilation, other Basic programs or subroutines can be included. Available on disk for $99.95.

Check Reader Service number 409.

3-D Graphics

Pioneer Software (1112 Fort St., Victoria, British Columbia, Canada V8V 4V2) has released Perspectives, a three-dimensional graphics animation program for the C-64.

The program offers six on-screen help menus that allow you to design your own graphics. Perspectives is available on disk and retails for $39.95.

Check Reader Service number 410.

Full-Sized Musical Keyboard

Music Port is a new musical keyboard and software system for the Commodore 64.

The system features a 37-key electronic keyboard with digital synthesizer capability. It allows you to create your own accompaniment and edit multi-track arrangements. Ten-minute songs can be stored on disk.

Music Port retails for $149. Tech Sketch, Inc., 26 Just Road, Fairfield, NJ 07006.

Check Reader Service number 423.

Circle 185 on Reader Service card.

Make your '64 work fulltime

MAKE YOUR OWN CHARTS...
CHARTPAK-64
Produce pro-quality charts and graphs instantly in 8 chart formats. Hardcopy in two sizes to popular dot matrix printers. $39.95

ORGANIZE YOUR DATA...
DATAMAT-64 Powerful, data managment package. Free form screen design. Complete flexible reporting, sorting, selection. More. $39.95

DETAIL YOUR DESIGNS...
CADPAK-64 Superb lightpen design tool. Draw LINEs, BOXes, CIRCLEs, ELLIPSEs; pattern FILLing; freehand DRAW; COPY sections of screen; ZOOM; more. Hardcopy. $49.95

CHART YOUR OWN STOCKS...
TAS-64 Sophisticated technical analysis charting package. 7 moving averages. 3 oscillators, trading bands. $84.95

CREATE SPREADSHEETS & GRAPHS
POWER PLAN-64
Powerful spreadsheet with builtin graphics. 275 pp. manual, tutorial, help, format, cell protect, much more. $49.95

Other titles available. FREE CATALOG and name of nearest dealer, write or call (616) 241-5510.

For postage and handling, include $4.00 ($8.00 foreign) per order. Money Order and checks in U.S. dollars only. Mastercard, VISA and American Express accepted. Michigan residents include 4% sales tax.

You Can Count On Abacus Software

P.O. Box 7211 Grand Rapids, MI 49510 - Telex 709-101 - Phone 616/241-5510

Dot-Matrix Printer

Inforunner Corp. (Airport Business Center, 431 N. Oak St., Inglewood, CA 90302) has released the Riteman C+, a dot-matrix printer that connects directly to the C-64 through the serial port.

The Riteman C+ prints in a 9×9 dot-matrix at 105 cps and has seven printing modes. Retail price is $299.

Check Reader Service number 424.

Calc Now!

Calc Now!/64 is a spreadsheet package for the C-64. It has a capacity of up to 64 columns by 254 rows and 39K of free memory for data.

Designed for home or business use, Calc Now! is available on disk for $39.95. Cardco, Inc., 300 S. Topeka, Wichita, KS 67202.

Check Reader Service number 416.

The Gold Disk

Gold Disk, Inc. (2179 Dunwin Drive #6, Mississauga, Ontario L5L 1X3 Canada) has introduced The Gold Disk Subscription Series for C-64 users.

Every month, subscribers receive a disk containing a feature program. Also included are tutorials, games, a programming puzzle, music, sound effects and a "programmer's corner."

A six-month subscription to The Gold Disk costs $54.95; a one-year subscription costs $99.95.

Check Reader Service number 428.

C-64 Graphics Package

Graph-Tech Software (1315 Third Ave. #4C, New York, NY 10021) has released 3-D World 64, a graphics package for the C-64.

With 3-D World 64, you can create three-dimensional drawings to be viewed on-screen or printed out on the Commodore 1520 Printer/Plotter. 3-D World 64 is available on disk for $39.95.

Check Reader Service number 414.

Stellar Conflict

Handic Software (520 Fellowship Road, Suite B206, Mount Laurel, NJ 08054) has released Stellar Conflict, a C-64 action game.

Stellar Conflict offers sound effects, animation and the option to create your own scenarios. The game is available on disk for $49.95.

Check Reader Service number 415.

Medical Diagnostics Program

Family Medical Advisor is a C-64 program designed to diagnose illness,

Circle 220 on Reader Service card.

Software That Works For Generations

6 Types of Charts and Sheets
Indices
User Fields
Notes, Footnotes and Sources
No Limits
Adapts to Your Hardware
Comprehensive
Easy to Use

And Much, Much More

Send for brochure and sample printouts.

Family Roots includes detailed manual and 2 full diskettes of programs for your Apple II, IBM PC, Commodore 64 and CP/M.*

Other genealogy software also available.

Price $185. Satisfaction Guaranteed.

American Express, Visa & Mastercard Accepted

* Trademarks for Apple Computer, Inc., International Business Machines, CBM, Inc., & Digital Research.

Family Roots™

QUINSEPT, INC.
P.O. Box 216, Lexington, MA 02173
(617) 641-2930

Circle 198 on Reader Service card.

DUST COVERS

★ CUSTOM MADE TO FIT
★ Heavy 32-oz. VINYL ANTI-STATIC
★ EXTENDS EQUIPMENT LIFE
★ Choice of Colors Lt. Tan or Brown

COMPUTERS:	
C-64/VIC20	7.00
KEYBOARD COVERS FOR ATARI; APPLE IIe; IBM; KAYPRO; TI99	8.00
DATASETTE (OLD)	5.00
DATASETTE (NEW, C2N)	5.00
DISK DRIVES:	
C-1541	8.00
MSD S/D; APPLE S/D	8.00
MSD D/D; APPLE D/D UNIT	10.00
PRINTERS (DOT MATRIX):	
C-1525; MPS801	10.00
C-1526; BMC BX80; BMC BX80F/T	13.00
GEMINI 10/10X; DELTA 10	13.00
GEMINI 15/15X; DELTA 15	16.00
EPSON MX80; RX80; RX80F/T	13.00
EPSON FX80; FX80F/T	13.00
EPSON MX100; FX100	16.00
PANASONIC KX-P1090; CARDCO	13.00
MONITORS:	
C-1702 COLOR	16.00
BMC COLOR	16.00
SANYO CRT 36 (GREEN)	14.00
AMDEK COLOR I	16.00
VIDEO RECORDERS:	
FOR MOST RECORDERS (CUT-OUT FOR CLOCK)	13.00

Order by stating NAME and MODEL and COLOR CHOICE TAN or BROWN. Enclose check or M.O. + 1.50 Ship & Hdlg. California Res. Include 6.5% Sales Tax.

SPECIAL COVERS WILL BE MADE TO YOUR DIMENSIONED SKETCH. SEND YOUR REQUIREMENTS FOR OUR LOW PRICE QUOTES

CROWN CUSTOM COVERS
9606 SHELLYFIELD ROAD
DOWNEY, CA 90240
(213) 862-8391

Circle 325 on Reader Service card.

HOT ACCOUNTS™
The most highly acclaimed bookkeeping system for the Commodore 64®

A Superb!
An exceptional program that outshines all others.
RUN Magazine, Nov. 1984

HOT ACCOUNTS™ teaches you bookkeeping as it automatically performs dozens of full-service accounting functions. It is a complete system that will instantly organize your records and receipts and supply charts, formal statements, and budget information. Now your records can be accurate, up to date and confidential. ▪ Tracks charge cards, checkbooks, all transactions ▪ Requires no prior knowledge of accounting ▪ Home or small business ▪ Improves your financial image ▪ Cost less than 1 hour with a C.P.A.

HOT ACCOUNTS™ Bookkeeping System on Diskette
For **RUSH** delivery, send check or money order for $64.95 to:
Computer Ed. Software
1002 Brookes Ave. W., Ste 100
San Diego, CA 92103
Credit card orders, call **toll-free**
1-800-621-0852 ext. 238
VISA MASTERCARD

P.S. *Use* HOT ACCOUNTS™ *to do your taxes and the price is tax deductible!*

BONUS OFFER! Order now and receive a full featured, 60 function **word processing** & 3-D **business graphics** package as our **FREE** gift to you.

poisoning or the effects of drug abuse.

The program analyzes data accumulated from yes-or-no questions and displays the most probable medical condition. Related disorders with similar symptoms are also identified. It is available on disk for $38. Navic Software, PO Box 14727, North Palm Beach, FL 33408.

Check Reader Service number 427.

Voice Synthesizers

Votrax, Inc. (1394 Rankin Road, Troy, MI 48083) has released Personal Speech System and Type-'N-Talk.

These two devices convert computer data into spoken English. Each operates from a CMOS synthesis chip and general microprocessor. Both units are compatible with the C-64 and the VIC-20.

The Personal Speech System is



priced at $395, while Type-'N-Talk retails for $249.

Check Reader Service number 420.

Roll Call USA

Roll Call USA, a trivia game for the C-64, was recently released by Creative Software (230 East Caribbean Drive, Sunnyvale, CA 94089).

This game will challenge your knowledge of the history and geography of the United States, with questions on the fifty states, the capitals and major industries. Roll Call USA is available on disk and retails for $14.95.

Check Reader Service number 401.



Commodore Control System

The ADC-1 is a measurement, monitoring and control system that allows you to acquire data and control external devices.

ADC-1 is connected to the C-64 through the RS-232C serial port. The

Here's why your competitors sell Run magazine.

RUN
The Home User's Guide to Commodore Computing

"**RUN** is an excellent magazine—no two ways about it—the best new publication in the marketplace."

No. Coast Programming
East Lake, OH

"**RUN** sales have increased faster than any other title. Our drivers report that customers are waiting in the stores for the deliveries of **RUN**."

Levity Magazine Distributors
No. Hollywood, CA

"Buyers come into the store just for **RUN** magazine. It's a very good seller and provides lots of support for Commodore users."

The Software Store
San Antonio, TX

*Commodore is a registered trademark of Commodore Business Machines, Inc.

Commodore is the hottest selling computer on the market. There are 4 million Commodores in American homes today. More than any other computer. It makes sense to tap this growing market. And computer retailers everywhere are doing it by selling **RUN** magazine—the fastest growing Commodore publication on the market.

Take it from your competitors– RUN sells. For details on how to become a **RUN** dealer, call our Direct Sales department at **1-800-343-0728.** In NH, call **1-924-9471.** Order now and get your **FREE** four color poster to help promote **RUN.**

Unconditional Guarantee—If within four months you have not sold **RUN,** just return the cover logos and you'll receive full credit to your account.

system (which includes a Basic module and a BSR controller) has a retail price of $395. Remote Measurement Systems, PO Box 15544, Seattle, WA 98115.

Check Reader Service number 406.

Foreign Language Programs

Artworx Software Co., Inc. (150 North Main St., Fairport, NY 14450) has released the Linkword Language series of foreign language programs for the C-64.

The four programs in the series are Spanish, French, German and Italian. Linkword uses a system based upon imagery, linking foreign words to acoustically similar English words.

Each package contains both disk and cassette versions of the program, along with an audio tape to assist in pronunciation. The programs retail for $24.95 each.

Check Reader Service number 422.



Enroll at MIT

Kermit's Electronic Storymaker is the first release in the Muppet Institute of Technology series, from Simon & Schuster (1230 Avenue of the Americas, New York, NY 10020).

The program is designed to help children ages four and up develop their reading, writing, vocabulary and grammar skills. It is available on disk for the C-64. Retail price is $39.95.

Check Reader Service number 417.



Commodore-Compatible Printer

Okidata (532 Fellowship Road, Mt. Laurel, NJ 08054) has released the Okimate 120 dot-matrix printer.

The Okimate 120 prints bidirectionally in Draft mode with short line-seeking logic at 120 cps. Features include a Commodore character set, true descenders and double-width characters.

The printer comes with an interface cable, making it compatible with the C-64, Plus/4, C-16 and VIC-20. Retail price is $269.

Check Reader Service number 421.

Word Processing Package

Word Runner is a word processing package designed for ease of use.

The program requires the use of very few commands and allows all editing to be done in one mode. Word Runner is available on disk for the C-64. Retail price is $44.95. N-Systems, PO Box 160, Steger, IL 60475.

Check Reader Service number 413.

Circle 112 on Reader Service card.

New dimensions in Bible study.



THE WORD® processor
the complete KJV Bible on disks $199.95*
TOPICS
an index to over 200 Scripture subjects $49.95*
* plus $3 postage/handling plus sales tax in Texas.

Requires APPLE II+, IBM PC and compatibles, TRS80, CP/M 2.2 (Z-80), KAYPRO, OSBORNE, COMMODORE 64, Z-100.

For information contact:
Bible Research Systems
9415 Burnet, Suite 208
Austin, TX 78758
(512) 835-7981
"Software for personal Bible study."

Circle 235 on Reader Service card.

wabash®

When it comes to Flexible Disks, nobody does it better than Wabash.

MasterCard, Visa Accepted.
Call Free: (800) 235-4137



PACIFIC EXCHANGES
100 Foothill Blvd.
San Luis Obispo, CA
93401 (In Cal. call
(805) 543-1037)

Circle 243 on Reader Service card.

COOMODORE 64
THE RECIPE BOX

Now you can easily store and recall your favorite recipes on your Commodore computer. THE RECIPE BOX is a complete menu-driven disk system that comes with these additional features:

SEARCH BY INGREDIENT—Only have a pound of hamburger in the freezer? Let THE RECIPE BOX show you all the recipes that you have on file that use hamburger, or any other ingredient you choose.

SEARCH BY CATEGORY—Code your recipes as to breakfast, lunch, dinner, snacks, etc.

SEARCH BY CATEGORY/INGREDIENT—Any combination of the above.

AUTOMATIC MEASUREMENT—THE RECIPE BOX will automatically scale up or down the amount of ingredients you need according to how many servings you want.

SCREEN OR PRINTED OUTPUT—Have printed copies to use in the kitchen or give to friends.

THE RECIPE BOX requires one disk drive and an optional 1521 compatible printer. Send check or money order for $19.95 to:

Aries Marketing Co.
P.O. Box 4196
4200 Shannon Drive
Baltimore, MD 21205

Md. residents add 5% sales tax

DEALER INQUIRES INVITED

Circle 156 on Reader Service card.

BETTER KEYBOARD UTILITY.

A simply elegant solution—blank "Cheat Sheets" give you the keyboard commands you need, instantly, for any program.

You've got the best personal computer in the world and lots of software to run on it. But unless you work with each of these programs every day, how do you keep the commands straight? "F5" in one program means something else in another. Our solution? Simple. A pack of 12 cards die cut to fit your keyboard. Ready for YOU TO FILL IN. Have all of your program commands right where you want them . . . on your keyboard. Order a couple of packs today.

$12.95 set of 12 custom die cut sheets **$19.95** set of 24 custom die cut sheets

BETTER DUST PROTECTION FOR VIC & COMMODORE

Choose an attractive static-free cover for your keyboard, monitor or complete system.

Don't confuse these attractive covers with cheap static-filled clear plastic covers. These deluxe covers are custom-fitted to each element of your Commodore, and are sewn, not glued. The interior of the supple leather-like material is lined with a special soft fabric liner to prevent scratching. Soft camel color fits beautifully in any office or home. Available: computer cover ($9.95), monitor cover ($12.95), 1541 disk drive cover ($8.95), dataset cover ($7.95). Printer covers (specify type) $12.95.

$7.95 to **$12.95**

We Can Solve All Your Commodore Color Problems

Unique Problem Solvers for Older Commodores (with 5 Pin Monitor Din Plug).

The Interference Stopper. . . A new kit that installs in minutes with two simple solder connections. Best results when combined with items below. Absolutely stops 90% of the RF interference. **$15.95**

The Color Sharpener. . . Use if your "old 64" is hooked up to a TV. Just plug into the monitor plug, and the color and contrast immediately improve. Dramatically crisp letters. Great graphics. **$18.95**

The NEW Color Sharpener CABLE. . . Use if your "old 64" is hooked up to a monitor. A new 2 prong cable, with a Color Sharpener built in for your monitor. **$24.95**

The Monitor "Improver". . . If you have a Commodore 1701 monitor, this cable (3 prongi gives you a picture you won't believe. Better than the cable Commodore built. (Also hooks your "old 64" to the 1702.) **$24.95**

RESET SWITCHES

2 Versions for Every Need

At last, the "needed" switch for Vic-20 and Commodore. Commodore left out a reset switch. Our switches will return control to you every time.

Version 1—Install it Yourself. Requires two simple solder connections, and drill a small hole. Works great. Saves money.

A steal at **$9.95**

Version 2—Use in any Commodore Application. A special **buffered** flow-thru version, that plugs in, gives a "Y" connection that provides your computer with another serial port **and** a reset switch. The ultimate in versatility, convenience and simple installation. No soldering.

Introductory priced at **$19.95**

Is Your Commodore Disk Drive Hot and Bothered?

Most of them are, you know. They suffer from read and write problems frequently. We've been told that most of these problems occur because the drive has overheated, throwing the head out of alignment.

Our inexpensive muffin fan sits on top of the disk drive and blows cooling air through it.

We went one step further. We built a surge protector into a second fan model.

$79.95 Fan with Surge protector **$54.95** Muffin fan

Order Today!

Please send me the following:
(Please describe fully. Send U.S. funds only.)
Your satisfaction guaranteed or your purchase price refunded.

Qty.	Item	Price
____	_____	$ _____
____	_____	$ _____
____	_____	$ _____
	Total for Merchandise	$ _____
	Shipping and Handling (foreign orders add $5.00)	$ 2.00
	5% State Tax (WI Residents only)	$ _____
	TOTAL ENCLOSED	$ _____

Please charge to: ☐ MasterCard ☐ VISA

Number _____

Expires _____

SHIP TO:

Name _____

Address _____

City _____

State/Zip _____

Mail to: Bytes & Pieces, Inc. 550 N. 68th St. Wauwatosa, WI 53213 / (414) 257-1214

Dealer Inquiries Invited

Circle 44 on Reader Service card.

ASYNC-CARTRIDGE 64™

6551 Asynchronous Communications Interface Adapter for Commodore 64® .

- **Plugs into cartridge slot allowing serial communications to 19.2 K BPS.**
- **Provides socket for 8K EPROM. You can put your communications software on a cartridge.**
- **Used as Device 2 (RS232 Port) with ASYNC-WEDGE software on 8K EPROM.**
- **Compatible with Cartridge-Maker-64™ with the addition of a blank 8K EPROM.**

(Commodore 64 is a registered trademark of Commodore Business Machines, Inc.)

ASYNC-CARTRIDGE 64	$59.95
ASYNC-WEDGE 64	19.95
BLANK 8K EPROM	5.50
Shipping	3.00

(If C.O.D. add $2.00)

Custom Programming Group, Inc.
47-2A Marchwood Road Exton, PA 19341
(215) 363-8840

Circle 167 on Reader Service card.

KEYBOARD CHORD/SCALE MASTER

BEGINNERS OR ADVANCED: LEARN TO PLAY CHORDS AND SCALES ON THE PIANO, ORGAN, OR LATEST ELECTRONIC SYNTHESIZER.

- **CHORD AND SCALE DISPLAYS...** Enhance your skills by sight and sound reinforcement through the reference library.
- **DRILL...**Chord and scales in all common key signatures, randomly selected by the computer.
- **QUIZ...**A continuous percentile determined by correct answers.
- **COMPETE...**A competitive game for the classroom or at home displaying cumulative scores.
- **Written in Machine Language.**

For Commodore 64, diskette only.
Send $39.95 + $1.50 postage/handling.
Michigan residents add 4% sales tax.
Check or money order.
Dealer/Distributor inquiries welcomed

VALHALA SOFTWARE
205 E. Hazelhurst
Ferndale, Michigan 48220
(313) 548-6754

Circle 128 on Reader Service card.

FAST LOAD

Plug this cartridge into the back of your C-64 and load, save, and copy all software **5 times faster** on your 1541 disk drive. Only $39.95

SOFTWARE SWAP

Send us a disk full of your software and we will send you a disk full of ours. Enclose $2.00 for postage and handling (no tapes please).

DISCOUNT SOFTWARE

Games—Business and Home Management—Utilities—Educational. You select the type of software (listed above) and we will send you 25 programs of that type of software for your computer. Please specify: C-64____ Vic-20____ Tape____ Disc____ Category 25 programs $9.95____ 3 Categories 75 programs $19.95____

Modem Phone (707) 822-8445 **SATELLITE TECHNOLOGY** **Voice Phone** (707) 822-7352
1062 G St., Suite G
Arcata, CA 95521

Shipping Charges: add $2.00 shipping and handling ($3.50 for C.O.D.). If California resident, add 6% sales tax.

NAME _____

STREET ADDRESS _____

CITY/STATE _____ **ZIP** _____

Check or money order____ C.O.D.____
Information Only____

Subscription Problem?

RUN does not keep subscription records on the premises, therefore calling us only adds time and doesn't solve the problem.

Please send a description of the problem and your most recent address label to:

RUN
Subscription Dept.
PO Box 954
Farmingdale, NY 11737

Thank you and enjoy your subscription.



Two Good Interfaces

Everyone knows about the Cardco/ ?+G interface, but I just bought a GPI graphics printer interface by Xectec. The interface is 100% compatible with software written for the VIC-1525 printer and gives you complete emulation of the special Commodore graphics set. This is real handy, especially when you are using Commodore software such as the Easy Script word processor.

I have an Epson RX 80 F/T printer hooked up to it, and my interface gives me the conveniences of an Epson printer and the compatibility of a Commodore printer. The nice thing is that it comes with a standard 2K buffer and costs about $89.

Donovan Palmer
Montrose, CO

Your article on printers and interfaces ("Selecting the Right Printer" by Jim Strasma, January 1985) was just what I needed. When this issue arrived, I had already decided on a Gemini-10X printer, but wasn't sure what interface to use. After reading this article and making phone calls to some of the mail-order houses that advertise in *RUN*, I finally ordered the Micrografix MW-350.

The system is great. My only complaint is that none of the people who mentioned the advantage of the MW-350 having a 4K buffer told me that the 4K is optional. The unit comes standard without any buffer.

Gerry Scerra
Sutton, MA

Alien Voice Module

In March of 1984 I purchased an Alien Voice Module for my VIC-20, and recently I purchased a C-64. When I tried to get the C-64 software for the module, I discovered that Alien and Mathews Research is no longer in existence.

Do you or any of your readers possibly know where I could acquire some software?

Michael Gibney
Box 925
Salem, MA 01970

Our attempts at contacting Alien and Mathews Research were futile. Readers?

Editors

The Ideal Computer?

I've only had a glimpse of the Commodore 128PC, but it looks very close to my description of the ideal computer, down to the numerical keypad on the right-hand side.

I hope the new model also contains the wedge in residence and a couple of programs like Easy Script and The Manager.

The expansion to 128K is great, and the compatibility with my 1000 C-64 programs is absolutely wonderful!

Now I am ready to peel those greenbacks and get myself a 128PC! Congratulations to those at Commodore.

Alfred Coya
Miami, FL

The C-64's Basic 2.0 needed the wedge. The new C-128 has Basic 7.0, which will offer as much if not more than the wedge. As for built-in software, there isn't any. However, this new machine offers 6000 existing software programs that will run on it, in addition to new software that's being developed.

Editors

Commodore in Italy

In Italy, the VIC-20 is still by far the best-selling micro. Close seconds seem to be the C-64 and Timex-Sinclair's Spectrum.

As to applications here, I guess we've followed the typical trend of starting off with games (arcade, not adventure), learning Basic and writing limited programs before moving on to machine language.

Most street-corner newsagents are crammed with computer magazines, and at least 15 or so are either American or British. We have about five Commodore-only Italian magazines and five or six more cassette-based ones, plus plenty of Basic courses. The English involved isn't too much of a problem, as English is just about the most popular second language here. Also, there are plenty of computer-based translating companies.

Certainly one of the biggest areas of applications (apart from games) is in education. Although not really fully started in schools yet, there is plenty of educational software available, ranging from English teaching games and translating dictionaries to statistical analysis. Good-quality Italian software is available, but not in the States or Britain. A large portion of Italian software is made up of translations.

D. Purvis
Brescia, Italy

How to type listings from RUN

Typing in listings can be difficult enough without having to worry about strange graphics characters, charts or tables. That's why we decided to make it easy to enter listings from *RUN* by translating everything we thought might be confusing in any program.

When you see something between the curly brackets, all you have to do is press the keys indicated. For example:

{SHIFT L}—means hold down the shift key and press the L key at the same time.

{COMD J}—means hold down the Commodore key (it is on the lower left side of the keyboard) and press the J key at the same time.

{SHIFT CLR}—hold down the shift key and press the CLR/HOME key.

CLR/HOME key.

{HOME}—press the CLR/HOME key without shifting.

{CTRL 6}—hold down the control key and press the 6 key.

{FUNCT 2}—function 2 (in this case, you hold down the shift key and press the function 1 key).

{CRSR UP}{CRSR DN}{CRSR LF}{CRSR RT}—these are the four cursor directions.

{UP ARROW}—means the arrow key (the one with the pi sign under it).

{LB.}—the British pound sign (£).

{PI}—the pi sign key (π); (shift and press the up arrow key).

Our translating program does not designate single spaces between characters. Within quotations, these spaces are often critical to the screen display. Be sure to read the listings closely and include these single spaces as you type in your program.

In some instances, when a large number of characters or spaces are repeated in a listing, we will represent them this way: {22 spaces} or {17 CRSR LFs}.

Print vs Print#

RUN readers should be aware of difficulties that may arise when entering listings that contain the PRINT and PRINT# commands.

These two commands may look very similar, but they are different. If, for example, you use a question mark (?) to abbreviate PRINT in a line such as 10 PRINT#4,A$, then you are signaling to the Commodore computer that you are trying to print the variable #4, which is not a legal variable name.

The command PRINT#4 actually means "print to file number 4." You can abbreviate PRINT# by hitting the P key and the shift and R keys at the same time and then entering the file number. But *do not* abbreviate PRINT# with a question mark.

If you think of PRINT as one command and PRINT# as an entirely different command, then you should have no problems.

■ ■ ■

Manuscripts: Contributions in the form of manuscripts with drawings and/or photographs are welcome and will be considered for possible publication. *RUN* assumes no responsibility for loss or damage to any material. Please enclose a self-addressed, stamped envelope with each submission. Payment for the use of any unsolicited material will be made upon acceptance. All contributions and editorial correspondence (typed and double-spaced, please) should be directed to *RUN* Editorial Offices, 80 Pine Street, Peterborough, NH 03458; telephone: 603-924-9471. **Advertising Inquiries** should be directed to Advertising Offices, CW Communications/Peterborough, Inc., Elm Street, Peterborough, NH 03458; telephone: 603-924-7138. **Subscription problems, placement orders, renewals or address changes:** Call 1-800-645-9559 or write to *RUN*, Subscription Department, PO Box 954, Farmingdale, NY 11737. **Problems with advertisers:** Send a description of the problem and your current address to: *RUN*, Elm Street, Peterborough, NH 03458, ATTN.: Rita B. Rivard, Customer Service Manager, or call 1-800-441-4403.

RUN is a member of the CW Communications/Inc. group, the world's largest publisher of computer-related information. The group publishes 52 computer publications in 19 major countries. Members of the group include: Argentina's *Computerworld/Argentina*; Asia's *The Asian Computerworld*; Australia's *Computerworld Australia, Australian Micro Computerworld, Australian PC World and Directories*; Brazil's *DataNews* and *MicroMundo*; China's *China Computerworld*; Denmark's *Computerworld/Danmark* and *MicroVerden*; Finland's *Mikro*; France's *Le Monde Informatique, Golden* (Apple) and *OPC* (IBM); Germany's *Computerwoche, Microcomputerwelt, PC Welt, Software Markt, CW Edition/Seminar, Computer Business* and *Commodore Magazine*; Italy's *Computerworld Italia*; Japan's *Computerworld Japan* and *Perso ComWorld*; Mexico's *Computerworld/Mexico* and *CompuMundo*; Netherland's *CW Benelux* and *Micro/Info*; Norway's *Computerworld Norge* and *MikroData*; Saudi Arabia's *Saudi Computerworld*; Spain's *Computerworld/Espana* and *MicroSistemas*; Sweden's *ComputerSweden, MikroDatorn, Min Hemdator* and *Svenska PC World*; the UK's *Computer Management, Computer News* and *Computer Business Europe*; the U.S.' *Computerworld, Hot CoCo, inCider, InfoWorld, MacWorld, Micro Marketworld, PC World, RUN, 73 Magazine* and *80 Micro*.

RUN AMOK

Item: In the Special Issue, there were two errors in the C-64 Basic Music Lesson program listing on p. 24 (in the article Sound & Music, by Peggy Herrington). In line 10, insert REM after the line number; in line 200, line 210 was inadvertently tacked on after Data item 30.

Item: Also in the Special Issue, in the Magic item Double-spaced Listing (p. 120), the Open statement should read: OPEN 128,4:CMD 128:LIST

Item: On the wall chart in the Special Issue, the ASCII codes for the function keys were incorrectly listed. They should have been:

Funct 1	133	Funct 2	137
Funct 3	134	Funct 4	138
Funct 5	135	Funct 6	139
Funct 7	136	Funct 8	140

Item: In the listing of the Trace Utility program in Magic item $169 of January 1985 (p. 12), line 125 was inadvertently omitted from the relocation routine. Insert the following: 125 A = INT(S/256):B = S – (A*256): POKE S + 38,A: POKE S + 33,B

Circle Reader Service card #165

TAPE USERS
MAJOR
BREAKTHROUGH
Buzzy BUZZARD'S
C-64 Tela Tape Term
$29.95
At last, an efficient term program for your dataset and modem. 25 cps!
Download and upload all types of programs.
Basic and Machine language.
•GAMES•••UTILITIES•••EDUCATIONAL•
Download and upload tape to tape or disk to tape
TO ORDER SEND CHECK OR MONEY ORDER.
FOR COD AND CREDIT CARD ORDERS
Call 1-904-384-6652
SYSOP'S INVITED TO INQUIRE ABOUT A SEND SUBROUTINE
TELASOFT
2144 Blanding Blvd.
Jacksonville, Florida 32210
C-64 TRADEMARK OF COMMODORE BUSINESS MACHINES

List of Advertisers

Reader Service		Page
335	A.A. Computers	133
8	Abacus Software	56
89	Abacus Software	22
185	Abacus Software	137
*	Apropos Technology	15
243	Aries Marketing Co.	141
301	Basix Softworx	45
*	Batteries Included	17
112	Bible Research Systems	140
193	Big Bytes Computers	115
82	Bill Cole Enterprises	129
156	Bytes & Pieces of WI	141
176	Carbotech, Inc.	115
192	Cardinal Software	92
81	Central Point Software	123
225	Cheatsheet Products	103
*	Comal Users Group	85
*	Commodore Business Machines	CIV
64	Compuserve	3
*	Computer Centers of America	53
325	Computer Ed. Software	138
274	Computer Friends Inc.	55
62	Computer Peripheral Exchange	99
29	Computer Warehouse	91
300	Covox, Inc.	107
198	Crown Custom Covers	138
44	Custom Programming Group	141
105	Data Share, Inc.	7
32	Davka Corporation	87
14	Eastcoast Software	37
50	Easternhouse Software	130
287	Edu-Comp	121
73	Edu-Tax	85
205	Elek-Tek	123
84	Federal Hill Software	103
162	Franklin Engineering	49
265	Full Circle Software	127
144	Giga International Corp.	97
124	Good Guys Co.	115
9	H & E Computronics	CIII
19	Inforunner	CII, 1
179	Jameco Electronics	22
202	Jason-Ranheim Co.	103
327	Kyan Software	36
150	Lifeware, Inc.	85
189	Megasoft Ltd.	28, 29
172	Micro WDI, Inc.	108
172	Micro WDI, Inc.	133
177	Micro World Electronix	44
91	Microlog Corporation	132
68	Microprose Software	21
155	Microsphere	62, 63
212	Micro-Sys	65
27	Microtechnic Solutions	38
72	Microtechnic Solutions	131
43	Mimic Systems	9
345	Nibble Notch Computer Products	121
*	Omega-Soft	121
60	Omnitronix	119
171	PC Gallery	57
235	Pacific Exchanges	141
208	Parsec Research	11
221	Playnet	13
*	Pro-Line Software	104
74	Prof Jones/Frogg House	60
93	Professional Software	2
15	Protecto Enterprizes	66-83
23	Public Domain, Inc.	107
220	Quinsept Inc.	138
219	R J Brachman Associates	96
188	Radix Marketing	109
	RUN Magazine	
	Run Sub Problems	141
	Back Issues	121
	Foreign Dealer	119
	Mailing List	119
	Toll Free Number ReRUN	112
	ReRUN	84
	RUN Subscription	64
128	Satellite Technology	141
*	Schnedler Systems	90
*	Sequential Circuit	89
90	Skyles Electric Works	19
254	Software Discounters of America	121
137	Solid State Software	106
92	Star Micronics, Inc.	40, 41
63	Starpoint Software	23
40	Sublogic Corporation	31
165	Telasoft	143
86	Telelearning Systems	59
209	Tussey Computer Products	39
*	Ultrabyte Inc.	49
35	Universal Software	44
167	Valhala Software	141
96	Xetec, Inc.	133

See Protecto Enterprizes' Special Catalog Sale Section, pages 66–83.

***This advertiser prefers to be contacted directly.**
Advertising Sales: (603) 924-7138 or (800) 411-4403;
Steve Robbins, Ken Blakeman.
West Coast Sales office:
(415) 328-3470, Giorgio Saluti,
1-800-227-8365. In Calif.: 1-800-344-4636.

For further information from our advertisers, circle the corresponding Reader Service number on the Reader Service card.

The RUN Advertising Department

can now be reached at our new toll free number

1-800-441-4403

Introducing the Most Powerful Business Software Ever!

FOR YOUR TRS-80 • IBM • APPLE • KAYPRO • COMMODORE 64 • MSDOS OR CP/M COMPUTER*



The VERSABUSINESS™ Series

Each **VERSABUSINESS** module can be purchased and used independently, or can be linked in any combination to form a complete, coordinated business system.

VERSARECEIVABLES™ $99.95

VERSARECEIVABLES™ is a complete menu-driven accounts receivable, invoicing, and monthly statement-generating system. It keeps track of all information related to who owes you or your company money, and can provide automatic billing for past due accounts. VERSARECEIVABLES™ prints all necessary statements, invoices, and summary reports and can be linked with VERSALEDGER II™ and VERSAINVENTORY™.

VERSAPAYABLES™ $99.95

VERSAPAYABLES™ is designed to keep track of current and aged payables, keeping you in touch with all information regarding how much money your company owes, and to whom. VERSAPAYABLES™ maintains a complete record on each vendor, prints checks, check registers, vouchers, transaction reports, aged payables reports, vendor reports, and more. With VERSAPAYABLES™, you can even let your computer automatically select which vouchers are to be paid.

VERSAPAYROLL™ $99.95

VERSAPAYROLL™ is a powerful and sophisticated, but easy to use payroll system that keeps track of all government-required payroll information. Complete employee records are maintained, and all necessary payroll calculations are performed automatically, with totals displayed on screen for operator approval. A payroll can be run totally, automatically, or the operator can intervene to prevent a check from being printed, or to alter information on it. If desired, totals may be posted to the VERSALEDGER II™ system.

VERSAINVENTORY™ $99.95

VERSAINVENTORY™ is a complete inventory control system that gives you instant access to data on any item. VERSAINVENTORY™ keeps track of all information related to what items are in stock, out of stock, on backorder, etc., stores sales and pricing data, alerts you when an item falls below a preset reorder point, and allows you to enter and print invoices directly or to link with the VERSARECEIVABLES™ system. VERSAINVENTORY™ prints all needed inventory listings, reports of items below reorder point, inventory value reports, period and year-to-date sales reports, price lists, inventory checklists, etc.

VERSALEDGER II™ $149.95

VERSALEDGER II™ is a complete accounting system that grows as your business grows. VERSALEDGER II™ can be used as a simple personal checkbook register, expanded to a small business bookkeeping system or developed into a large corporate general ledger system **without any additional software.**

- VERSALEDGER II™ gives you almost unlimited storage capacity (300 to 10,000 entries per month, depending on the system),
- stores all check and general ledger information forever,
- prints tractor-feed checks,
- handles multiple checkbooks and general ledgers,
- prints 17 customized accounting reports including check registers, balance sheets, income statements, transaction reports, account listings, etc.

VERSALEDGER II™ comes with a professionally-written 160 page manual designed for first-time users. The VERSALEDGER II™ manual will help you become quickly familiar with VERSALEDGER II™, using complete sample data files supplied on diskette and more than 50 pages of sample printouts.

SATISFACTION GUARANTEED!

Every **VERSABUSINESS™** module is guaranteed to outperform all other competitive systems, and at a fraction of their cost. If you are not satisfied with any **VERSABUSINESS™** module, you may return it within 30 days for a refund. Manuals for any **VERSABUSINESS™** module may be purchased for $25 each, credited toward a later purchase of that module.
All CP/M based Computers must be equipped with Microsoft BASIC (MBASIC or BASIC-80)

To Order:
Write or call Toll-free (800) 431-2818
(N.Y.S. residents call 914-425-1535)

- add $3 for shipping in UPS areas
- add $4 for C.O.D. or non-UPS areas
- add $5 to CANADA or MEXICO
- add proper postage elsewhere

DEALER INQUIRIES WELCOME
All prices and specifications subject to change / Delivery subject to availability.

COMPUTRONICS INC

50 N. PASCACK ROAD, SPRING VALLEY, N.Y. 10977

*The VersaBusiness Series is available for TRS-80 · IBM · APPLE · KAYPRO · COMMODORE 64 · OSBORNE · XEROX · TELEVIDEO · SANYO · ZENITH · NEC · DEC · TI · EPSON · MORROW MICRO DECISION · NORTHSTAR · MSDOS and CP/M computers with 8" disk drives (Computer names are tradenames and/or trademarks of their respective manufacturers).

Circle 9 on Reader Service card.



IT'S NOT HOW MUCH YOU PAY.



IT'S HOW MUCH YOU GET.

The computer at the top has a 64K memory.

It has the initials I, B, and M. And you pay for those initials.

The Commodore 64™ has a 64K memory.

But you don't pay for the initials, you just pay for the computer. About one third the price of the IBM PCjr.™

The Commodore 64 also has a typewriter-type keyboard with 66 typewriter-type keys. (Not rubber chicklet keys like the IBM PCjr.)

It has high resolution graphics with 320 x 200 pixel resolution, 16 available colors and eight 3-dimensional sprites.

It has 9-octave high fidelity sound.

The Commodore 64 is capable of running thousands of programs for home and office. And if you add a printer or color monitor, disk drive and a modem—all together it just about equals the price of the IBM PCjr all alone. With no peripherals.

So you can buy a computer for a lot of money.

Or buy a lot of computer for the money.

COMMODORE 64

IT'S NOT HOW LITTLE IT COSTS,
IT'S HOW MUCH YOU GET.